

# 2026 Summary of Revisions

## City of Bismarck Construction Specifications for Municipal Public Works Improvements

The City of Bismarck has revised the Construction Specifications for Municipal Public Works Improvements for 2026.

The following is a list of specification sections and standard plates that have significant revisions. Specification numbers listed below are the numbers in the 2026 revision, which may not correspond to the previous version. Other sections have been revised for clarity, formatting, or other minor revisions. If further explanation of any revisions is required, please contact the City of Bismarck Engineering Department. Specifications with revisions highlighted are available on the City website at: [www.bismarcknd.gov/Engineering](http://www.bismarcknd.gov/Engineering)

### GENERAL

- Measurement and Payment subsections were revised to refer Section 107 with additional specific requirements
- Bid item list revised for simplicity and clarity

### DIVISION 100 - GENERAL PROVISIONS

#### Section 101 - Abbreviations and Definitions

- 3 - Added definitions

#### Section 102 - Bidding and Contract Documents

- 2 - Added specification for Online Bidding, previously a special provision
- 9 - Added specification for Supply of Materials

#### Section 104 - Control of Work

- 2 - Added specification for Online Project Management, previously a special provision
- 7 - Revised Contractor's Responsibilities to include open communication and added specification regarding damage caused by public traffic.

#### Section 105 - Legal Relationships and Responsibilities

- 4 - Added specification for Access requirements during construction

#### Section 107 - Measurement and Payment

- 1 - Added general specification regarding measurement and payment

- 2 - Clarification on retainage held on change orders and release of retainage

## **DIVISION 200 - EARTHWORK**

### Section 202 – Excavation and Embankment

- 3.11 – Clarified Tolerances to include portions removed from previous section(s)

### Section 205 – Erosion and Sediment Control

- 2.9 – Added approved Inlet Filter

## **DIVISION 300 – BASE COURSES**

### Section 301 – Sand Subbase

- Section Removed – No longer in use

### Section 303 – Cement Stabilized Subgrade

- 3.5 – Added specification for Pulverization, previously Special Provision

## **DIVISION 400 – FLEXIBLE PAVEMENT**

### Section 402 – Bituminous Prime and Tack Coat

- 2.2 – Removed SS-1 as acceptable tack coat oil

### Section 403 – Bituminous Seal

- 2.2 – Revised to refer Gradation requirements to NDDOT specifications

### Section 404 – Scrub Seal

- Added, previously Special Provision

### Section 405 – Fog Seal

- Added, previously Special Provision

### Section 406 – Milling Pavement Surface

- Previously Section 404
- 3 – Revised to state millings shall become property of Contractor

### Section 407 – Crack Treatments

- Previously Section 405

### Section 408 – Asphalt Removal

- Previously Section 406

## **DIVISION 500 – RIGID PAVEMENT**

### Section 501 – Portland Cement Concrete Pavement

- 3.23 – Revised Random Crack Seal requirements
- 3.27 – Added Concrete Removal requirements
- 3.28 – Added Uncontrolled Cracking Specification

## **DIVISION 600 – CONCRETE SIDEWALKS, DRIVEWAYS, AND CURB AND GUTTER**

### General

- Moved all concrete removal items to Section 501

### Section 601 – Concrete Sidewalks

- 3.9 – Added requirement for “T” posts on ADA ramps
- 3.13 – Added Uncontrolled Cracking Specification

### Section 602 – Concrete Driveways

- 3.12 – Added Uncontrolled Cracking Specification

### Section 603 – Concrete Curb and Combined Curb and Gutter

- 4.12 – Added Uncontrolled Cracking Specification

## **DIVISION 800 - SEWERS**

### Section 801 - Sanitary Sewer

- 3.4 – Added requirement for sanitary service wyes
- 3.5 – Clarified backfill surface maintenance requirements
- 3.10 – Added complete backfill requirement for leakage tests
- 3.11 – Added complete backfill requirement for televising

### Section 802 - Storm Sewer

- 3.5 – Revised In-Line cleanouts to be made with 2-way tee in lieu of wye
- 3.12 – Revised riprap grout requirements at end of FES
- 3.13 – Added requirement for flush and televise of storm sewer

## **DIVISION 900 - WATER DISTRIBUTION**

### Section 901 - Watermain

- 2.7 – Added requirement for 14” and larger gate valves have beveled gear actuators
- 3.6 - Added requirement that corporation stops be closed and left in place when used for testing and/or flushing

## **DIVISION 1000 - ELECTRICAL**

### Section 1002 – Underground Circuits

- 3.2 – Added requirement for bored conduits to be installed 12” behind curb

#### Sections 1004 - Streetlight Units

- 2.2a, 2.3a, 2.4a, 2.5a – Added approved manufacturer and model: Traditional Concrete, Inc
- 2.6a, 2.7a – Revised model number for Millerbernd Manufacturing
- 2.8 – Revised requirement for splice connectors

### **DIVISION 1200 - MISCELLANEOUS CONSTRUCTION**

#### Section 1202 - Seeding

- 2.1 – Corrected error in Class IV seed mix

#### Section 1205 - Manholes and Inlets

- 2.4 – Revised elevation datum from NGVD29 to NGVD88

#### Section 1206 - Casting and Adjustment

- 2.3 – Revised grate model number for Beehive castings
- 3.7 – Revised casting adjustment requirements

#### Section 1209 - Sanitary Sewer and Water Service Connections

- 2.9 & 2.10 – Clarified requirements for tapping sleeves and saddles

#### Section 1210 – Pavement Marking

- Section revised and updated

**STANDARD DETAILS.** The following Standard Details have been revised (drawings with revisions highlighted are available on the City of Bismarck website):

- 200 - 1
- 600 - 15,16,19
- 802 - 3
- 1003 - 1,2,5
- 1004 - 1,2
- 1205 - 2,6,7,18
- 1206 - 1,2

**CONSTRUCTION SPECIFICATIONS**  
**FOR**  
**MUNICIPAL PUBLIC WORKS IMPROVEMENTS**  
**BISMARCK, NORTH DAKOTA**

Prepared by



221 NORTH FIFTH STREET  
P.O. BOX 5503  
BISMARCK, ND 58506-5503  
Gabriel J. Schell, P.E., City Engineer

February 1969  
Revised February 2026



**NOTE/DISCLAIMER**

The specifications represented in this document are in accordance with established City of Bismarck civil engineering practices and are an electronic facsimile of the specifications on file in the City of Bismarck Engineering Department. However, neither the City of Bismarck nor its employees can or do warranty these specifications to be the complete specifications for any or all City of Bismarck civil construction projects. The specification document, together with all addendums listed in each construction project specifications, shall be the project specifications for the City of Bismarck civil engineering projects.

## CONTENTS

### **DIVISION 100 – GENERAL PROVISIONS**

101	Abbreviations and Definitions
102	Bidding and Contract Documents
103	Scope of Work
104	Control of Work
105	Legal Relationships and Responsibilities
106	Prosecution and Progress
107	Measurement and Payment

### **DIVISION 200 – EARTHWORK**

201	Clearing and Grubbing/Miscellaneous Removals
202	Excavation and Embankment
203	Watering
204	Subgrade Preparation
205	Erosion and Sediment Control

### **DIVISION 300 – BASE COURSES**

301	(Blank)
302	Aggregate Base and Aggregate Surface
303	Cement Stabilized Subgrade

### **DIVISION 400 – FLEXIBLE PAVEMENT**

401	Asphaltic Concrete Pavement
402	Bituminous Prime and Tack Coat
403	Bituminous Seal
404	Scrub Seal
405	Fog Seal
406	Milling Pavement Surface
407	Crack Treatments
408	Asphalt Removal

### **DIVISION 500 – RIGID PAVEMENT**

501	Portland Cement Concrete Pavement
502	Slabjacking
503	Controlled Density Fill (CDF)
504	Concrete Pavement Repair

### **DIVISION 600 – CONCRETE SIDEWALKS, DRIVEWAYS, AND CURB AND GUTTER**

601	Concrete Sidewalks
602	Concrete Driveways
603	Concrete Curb and Combined Curb and Gutter

**DIVISION 700 (BLANK)**

**DIVISION 800 – SEWERS**

- 801 Sanitary Sewer
- 802 Storm Sewer
- 810 Cured in Place Pipe (CIPP)

**DIVISION 900 – WATER DISTRIBUTION**

- 901 Water Main
- 910 Water Main Pipe Bursting

**DIVISION 1000 – ELECTRICAL**

- 1001 (Blank)
- 1002 Underground Circuits
- 1003 Streetlighting Feedpoint
- 1004 Streetlight Units

**DIVISION 1100 (BLANK)**

**DIVISION 1200 - MISCELLANEOUS CONSTRUCTION**

- 1201 Topsoil
- 1202 Seeding
- 1203 Sodding
- 1204 Mulching
- 1205 Manholes and Inlets
- 1206 Castings and Adjustment
- 1207 Geosynthetics
- 1208 Chain-Link Fencing
- 1209 Sanitary Sewer and Water Main Service Connections
- 1210 Pavement Marking
- 1211 Traffic Control
- 1212 Highway Signs and Posts
- 1213 Mailboxes – Remove and Reset

**STANDARD DETAILS**

- 200-1 Typical Grading Sections
- 205-1 Concrete Erosion Blanket
- 205-2 Erosion Control Berm
- 205-3 Silt Fence with Wire Back
- 400-1 AC Patch
- 400-2 Crack Seal
- 500-1 Concrete Joints
- 500-2 Joint Details
- 500-3 Dowel Placement
- 504-1 Spall Repair

504-2	Spall Repair
504-3	Spot Full Repair
504-4	Spot Full Repair
600-1	Standard Concrete Sidewalk
600-2	Commercial Concrete Sidewalk
600-3	Type 1 and 2 Curb Ramps
600-4	(Blank)
600-5	Sidewalk Trench Drain
600-6	Drop Curb Driveway
600-7	Dividing Driveways - (Sheet 1 of 2)
600-8	Dividing Driveways - (Sheet 2 of 2)
600-9	Radius Driveway
600-10	Commercial Driveway
600-11	Mountable Curb and Gutter
600-12	Standard Curb, Curb and Gutter
600-13	(Blank)
600-14	Mountable Curb and Gutter with Inlet
600-15	Intersection Curve
600-16	Valley Gutter
600-17	Standard Curb and Gutter with Inlet
600-18	Sidewalk & Right-of-Way Grading
600-19	Typical Driveway Installation
801-1	Cleanout
801-2	Sanitary Sewer Pipe Bedding
802-1	Storm Sewer Pipe Bedding
802-2	HDPE to Reinforced Concrete Pipe Connection Detail
802-3	Perforated Pipe In-Line Cleanout
802-4	Perforated Pipe End of Run Cleanout
900-1	Concrete Thrust Blocking
900-2	Water Main Payment Diagram
900-3	Watermain Pipe Bedding
900-4	Hydrant Setting
1002-1	Trench in Conduit
1002-2	Trench Direct Buried
1002-3	Street Crossing in Conduit
1002-4	Crossing in Conduit
1002-5	Junction Box
1003-1	Pad Mounted Feed Point
1003-2	Pole Mounted Feed Point
1003-3	Feed Point Wiring
1003-4	Feed Point Wiring
1003-5	Feed Point Name Plate
1004-1	Embedded Base
1004-2	Type CL & CL1 Base
1004-3	Street Light Type BL, L & L1
1004-4	Street Light Type CL & CL1
1004-5	Street Light Type D1

1205-1	Sanitary Sewer Manhole
1205-2	Sanitary Sewer Drop Manhole
1205-3	Storm Sewer Manhole
1205-4	Cast-In-Place Storm Sewer Manhole
1205-5	Type 24" Inlet/Manhole and Type 24" Inlet
1205-6	Type 36" and Type 72" Inlet - (Sheet 1 of 2)
1205-7	Type 36" and Type 72" Inlet - (Sheet 2 of 2)
1205-8	Roof Slab for Type 36" and 72" Inlet with Type 24" Casting
1205-9	Slotted Drain Inlet - (Sheet 1 of 2)
1205-10	Slotted Drain Inlet - (Sheet 2 of 2)
1205-11	Air Release Manhole
1206-1	Manhole, Inlet, and Valve Box Adjustment in Asphalt
1206-2	Manhole, Inlet, and Valve Box Adjustment in Concrete
1206-3	Floating Manhole Casting Detail - (Sheet 1 of 2)
1206-4	Floating Manhole Casting Detail - (Sheet 2 of 2)
1208-1	Chain-Link Fence and Gates
1209-1	Typical 1"-2" Water Service
1211-1	Work Zone ADA Compliant Temporary Pedestrian Barricades
1212-1	Road Closed, Type III Barricade, Fence Detail
MISC-1	Temporary Curb Mount Detail

## DIVISION 100

### SECTION 101 – ABBREVIATIONS AND DEFINITIONS

#### 101-1 REFERENCES

The specifications rely on many cross-references, both to internal sources in the specifications and external sources in other contract documents, City of Bismarck manuals, and other industry resources. If the contract documents reference an external publication, the City of Bismarck intends that the reference be to the most recent issue, including interim publications before the date of the advertisement, unless the contract specifies otherwise.

Each contract item listed in the contract references a section number from the specifications; therefore, all of the provisions of that referenced section that are relevant to the proper completion of the contract item are binding upon the CONTRACTOR. This includes the requirements found in the “General” subsections as well as those specific requirements listed thereafter.

Within the specifications, references to other sections of the specifications apply the same as if they were a part of the section from which they were referenced. A cross-reference to a specific section of these specifications includes all general requirements of the referenced section.

#### 101-2 ABBREVIATIONS

Wherever the following abbreviations are used in the contract documents, their meaning shall be as follows:

AASHTO	American Association of State Highway and Transportation Officials
AC	Asphaltic Cement
ACI	American Concrete Institute
ACPA	American Concrete Pipe Association
ADA	Americans with Disabilities Act
AGC	Associated General Contractors of America
AIA	American Institute of Architects
AISI	American Iron and Steel Institute
ANLA	American Nursery and Landscaping Association
ANSI	American National Standards Institute
ARTBA	American Road and Transportation Builders Association
ASCE	American Society of Civil Engineers
ASLA	American Society of Landscape Architects
ASTM	ASTM International
ATSSA	American Traffic Safety Services Association
AWPA	American Wood Protection Association
AWWA	American Water Works Association

## DIVISION 100 – GENERAL PROVISIONS

AWS	American Welding Society
BMP	Best Management Practices
CADD	Computer-Aided Drafting Design
CRSI	Concrete Reinforcing Steel Institute
DBE	Disadvantaged Business Enterprise
EEO	Equal Employment Opportunity
ESAL	Equivalent Single Axle Load
EPA	U.S. Environmental Protection Agency
FAA	Federal Aviation Administration
FHWA	Federal Highway Administration, U.S. Department of Transportation
HDPE	High-Density Polyethylene
IES	Illuminating Engineering Society
ISSA	International Slurry Surfacing Association
ITE	Institute of Transportation Engineers
ITS	Intelligent Transportation System
IMSA	International Municipal Signal Association
LED	Light Emitting Diodes
MUTCD	Manual on Uniform Traffic Control Devices
NCHRP	National Cooperative Highway Research Project
NDCC	North Dakota Century Code
NDDEQ	North Dakota Department of Environmental Quality
NDDOT	North Dakota Department of Transportation
NDPDES	North Dakota Pollutant Discharge Elimination System
NEC	National Electrical Code
NEMA	National Electric Manufacturers Association
NEPA	National Environmental Policy Act
NHTSA	National Highway Traffic Safety Administration
NPCA	National Precast Concrete Association
NRMCA	National Ready-Mix Concrete Association
NTCIP	National Transportation Communications for ITS Protocol
NTPEP	National Transportation Product Evaluation Program
OSHA	Occupational Safety and Health Administration, U.S. Department of Labor
PCA	Portland Cement Association
PCC	Portland Cement Concrete
PCI	Precast/Prestressed Concrete Institute
PVC	Polyvinylchloride - PVC Pipe
QA	Quality Assurance
QC	Quality Control
SAE	SAE International
SG	Specific Gravity
SSPC	The Society for Protective Coatings
SWPPP	Storm Water Pollution Prevention Plan
UL	Underwriters Laboratory, Inc.
USACE	United States Army Corps of Engineers
USFWS	U.S. Fish and Wildlife Service
VMA	Voids in Mineral Aggregate

### 101-3 DEFINITIONS

Wherever the following terms are used in the contract documents, their meaning shall be as follows:

**Act of God.** An unforeseeable act, event, or happening resulting from natural causes such as earthquake, tornado, or other cataclysmic phenomena.

**Actual Quantity.** The quantity of a contract item measured by the ENGINEER.

**Addendum.** A document issued by the CITY after the advertisement and before the bid opening that modifies or supplements the proposal package and will become part of the contract.

**Advertisement for Bids.** A public announcement inviting proposals. The advertisement will identify how to get a copy of the proposal package, how to submit a proposal, and the date, time, and place of the bid opening.

**Award.** The CITY's acceptance of a proposal.

**Base Course.** The layer or layers of specified or selected material placed on a subbase or subgrade to support a surface course.

**Bid Bond.** The security furnished to guarantee the Bidder will enter into the contract if the Proposal is accepted.

**Bidder.** An individual or legal entity submitting a proposal.

**Bid Opening.** The public opening of proposals at the date, time, and location identified in the Advertisement.

**Bid Item List.** A list of the bid items and estimated quantities in the proposal forms. The bid item list becomes the list of contract items after execution of the contract.

**Bid Schedule.** Bid document which includes all bid items, unit of measurement and estimated quantities.

**Bid Unit Price.** The price per unit for a contract item submitted by the Bidder on the proposal forms. After award the bid unit price becomes the contract unit price.

**Business Day.** Any calendar day, except Saturdays and holidays.

**Calendar Day.** Every day shown on the calendar. A day begins and ends at midnight.

**Certificate of Compliance.** A certificate provided by the CONTRACTOR to the Engineer.

## DIVISION 100 – GENERAL PROVISIONS

**Change Order.** A written order from the CITY to the CONTRACTOR, and signed by both parties, detailing contract revisions for work within the scope of the original contract.

**City.** The City of Bismarck or its representatives.

**City Engineer.** The Director of the City of Bismarck Engineering Department acting directly or through authorized representatives.

**Engineer.** An authorized representative of the City of Bismarck Engineering Department, who is responsible for engineering supervision of construction.

**Construction Limits.** The area from the beginning station to the ending station of the project and between the slope stakes or as shown on the Plans.

**Contract.** The written agreement between the CITY and the CONTRACTOR setting forth the obligations of the parties for the performance of the prescribed work.

The contract includes the following:

1. Proposal for bids, instructions to bidders, and requirements for bidders
2. General provisions
3. Special provisions
4. Specifications
5. Contract drawings
6. All addenda issued by the City prior to receipt of bids
7. Bid of the Contractor
8. Bid bond, performance, and payment bonds and maintenance bond, if any
9. Certificate of insurance
10. Notice of award
11. Resolution of City awarding the bid
12. Agreement
13. All provisions required by law to be inserted in the contract whether actually inserted or not.

**Contract Amount.** The total amount of the contract, including all contract revisions to date.

**Contract Bond.** The security, executed by the CONTRACTOR and the surety or sureties, furnished to the CITY to guarantee complete execution of the contract and all supplemental agreements and the payment of all legal debts pertaining to project construction.

**Contract Item (Pay Item).** A specific unit of the work for which the contract provides a price. During the bidding process, the term “bid item” may be used to describe these items.

**Contract Unit Price.** The price included in the contract for a contract item.

## DIVISION 100 – GENERAL PROVISIONS

**Contract Time.** The amount of time allowed for completion of the contract, including authorized time extensions. The contract time will be a number of working days, a number of calendar days, a completion date, or a completion date with a minimum number of working days. The contract time may include milestones.

**Contractor.** The individual or legal entity contracting with the CITY for performance of prescribed work.

**Employee.** Any person working on the project covered by the contract that is under the direction or control of, or receives compensation from, the CONTRACTOR or a subcontractor.

**Subcontractor.** An individual or legal entity with whom the CONTRACTOR sublets part of the contract.

**Superintendent.** The CONTRACTOR's authorized representative in responsible charge of the work.

**Surety.** The legal entity or individual, other than the CONTRACTOR, executing a proposal guaranty or contract bond.

**Employee.** See CONTRACTOR.

**Engineer.** See CITY.

**Equipment.** All machinery, tools, apparatus, and supplies necessary for maintenance, construction, and completion of the work.

**Extra Work.** Work not provided for in the contract but considered essential by the ENGINEER for satisfactory completion of the contract within its intended scope.

**Final Completion.** A project is considered as final complete when all construction, including all punch list items, is fully complete and accepted by the ENGINEER.

**Force Account.** Payment for contract revisions per approved costs and additives.

**Haul Road.** Highways, streets, or roads designated by the CITY for use by the CONTRACTOR to haul material to or from the project.

**Highway, Street, or Road.** A general term indicating a public way used by vehicles and pedestrians. Includes entire area within the right of way.

**Holidays.** City of Bismarck holidays are as follows:

1. Every Sunday;
2. New Year's Day, January 1;
3. Martin Luther King Jr. Day, the third Monday of January;
4. Presidents' Day, the third Monday of February;
5. Good Friday, the Friday before Easter Sunday;

## DIVISION 100 – GENERAL PROVISIONS

6. Memorial Day, the last Monday in May;
7. Independence Day, July 4;
8. Labor Day, the first Monday in September;
9. Veterans Day, November 11;
10. Thanksgiving Day, the fourth Thursday in November;
11. Christmas Day, December 25; and
12. Every day appointed as a public holiday by the president of the United States or the Governor of the State

If January 1, July 4, November 11, or December 25 fall on a Sunday, the following Monday is a holiday.

If January 1, July 4, November 11, or December 25 fall on a Saturday, the previous Friday is a holiday.

**Interim Completion.** Substantial completion only for defined work areas or scope items as defined in the project documents.

**Materials.** Any substances, products, supplies, assemblies, or raw materials specified for use in the performance of the work.

**Median.** The portion of a divided street separating the traveled ways.

**Milestone.** Completion of a phase or critical objective.

**Notice to Bidders.** A notice issued by the CITY of projects available for proposals in an upcoming bid opening.

**Notice to Proceed.** The CITY's notice to the CONTRACTOR to begin the work.

**Pavement Structure.** The combination of subbase, base course, and surface course placed on a subgrade to support and distribute the traffic load to the roadbed.

**Plan Quantity.** The quantity of a contract item shown on the bid item list and the Plans.

**Plans.** The Project Plans and Standard Drawings that show the location, character, and dimensions of the prescribed work, including layouts, profiles, cross sections, and other details.

**Project.** The specific section of infrastructure on which construction is to be performed under the contract.

**Project Number.** A number generated by the CITY containing coded project data. Found on the cover sheet of the Plans.

**Project Site.** All areas used by the CONTRACTOR in the performance of the work.

## DIVISION 100 – GENERAL PROVISIONS

**Proposal.** (Commonly referred to as Bid) A Bidder's offer on CITY forms, to perform the work at the prices quoted.

**Proposal Forms.** The CITY-provided forms on which a Bidder must prepare and submit its Proposal for the work. That portion of the Proposal package containing certifications, affidavits, acknowledgements, and the bid item list. The Proposal form is prepared and submitted by the Bidder and is then considered a Proposal.

**Proposal Package.** All documents made available to prospective Bidders by the CITY before the opening of Proposals. These documents will become part of the contract.

**Request for Proposals.** A publication addressing the work required for the project. The request for proposals may include the Special Provisions and the Proposal forms.

**Responsive Proposal.** A Proposal that meets all requirements of the Proposal package.

**Responsible Bidder.** A Bidder who has met all of the CITY's prequalification requirements and submits a qualifying bid on a project.

**Retainage.** Withholding of a portion of the final payment to assure the CONTRACTOR has finished a project completely and satisfactorily.

**Right-of-Way.** A general term denoting land, property, or interest therein, acquired for or devoted to a roadway.

**Roadbed.** The graded portion of a highway, street or road, within top and side slopes, prepared as a foundation for the pavement structure.

**Shop Drawings.** Supplemental design sheets or similar data, such as drawings, diagrams, illustrations, samples, schedules, or calculations, that the contract requires the CONTRACTOR to submit to the ENGINEER. Once the CITY has reviewed a work drawing, it becomes part of the contract.

**Sieve.** U.S.A. Standard Sieve, as defined in ASTM E11. The specified percent passing for each sieve is measured by weight.

**Special Provisions.** See Specifications.

**Specifications.** The compilation of written requirements for performance of the work, including the following:

**Standard Specifications.** A book of specifications approved for general application and repetitive use.

**Special Provisions.** Revisions or additions to the standard specifications that cover special conditions for the project.

**Stabilization.** The modification of soils or aggregates by incorporating materials that increase load-bearing capacity, firmness, or resistance to weathering or displacement.

**Standard Drawings.** An approved set of drawings showing Standard Details of construction and materials for the work on a project.

**Standard Specifications.** See Specifications.

**Station.** When used as a definition or term of measurement, a station is 100 linear feet.

**Structures.** Bridges, culverts, catch basins, drop inlets, retaining walls, cribbing, manholes, end walls, buildings, sewers, service pipes, underdrains, foundation drains, and similar features that may be encountered in the work.

**Subcontractor.** See CONTRACTOR.

**Subbase.** The layers of specified or selected materials of designated thickness placed on a subgrade to support a base course.

**Subgrade.** The top surface of an embankment or cut section on a graded roadway. It is the foundation for the subbase, base course, and surface course.

**Substantial Completion.** A project is substantially complete when it is operational and ready for use by the CITY.

**Superintendent.** See CONTRACTOR.

**Surety.** See CONTRACTOR.

**Surface Course.** One or more layers of a pavement structure designed to accommodate the traffic load, the top layer of which resists skidding and traffic abrasion. The top layer is sometimes called “Wearing Course.”

**Traffic.** Vehicles, pedestrians, and other modes of transportation.

**Total Sum Bid.** The total amount of a Proposal; the sum of the price extensions for all bid items.

**Work.** The providing of all labor, materials, equipment, and incidentals necessary to complete the project in accordance with the contract.

**Work Order.** A written directive from the ENGINEER to the CONTRACTOR to perform changed work, extra work, or other additional work.

**Working Day.** Every Calendar Day not defined as a Holiday.

## **SECTION 102 – BIDDING AND CONTRACT DOCUMENTS**

### **102-1 PROPOSALS**

No bids received after the time set for the receipt of the proposals will be considered. The right is reserved to hold all bids for a period of 30 days and to reject any or all bids. Bidders are invited to be present at the opening of Proposals.

### **102-2 ONLINE BIDDING**

All bids shall be submitted and received via online bidding. Bids shall be submitted through QuestCDN's Virtual Bidding (vBid). See additional information available in the project advertisement or through [www.QuestCDN.com](http://www.QuestCDN.com).

### **102-3 FORM OF PROPOSAL AND SIGNATURE**

The Proposal must be made on forms provided for that purpose, or forms provided by the Bidder which follow the same format, enclosed in a sealed envelope, and marked and addressed as required in the Advertisement. It must state the unit prices and the sum of money for which the Bidder proposes to supply the materials and perform the work called for in the Proposal and Schedule of Work. Bidders shall submit a bid on a unit price basis for each item of work so listed in the Proposal. The total of all estimated prices will be determined as the sum of the products of the estimated quantity of each item and the unit price bid for the item. If the bid is made by an individual, it must be signed with the full name of the Bidder whose address must be given. If made by a firm, it must be signed in the co-partnership name by a member of the firm, and the name and address of each member of the firm must be given. If made by a corporation, it must be signed by an officer of the corporation in the corporate name, and the corporate seal must be attached to such signature.

The Bidder may substitute a computer-printed spreadsheet of the Bid Schedule for the CITY-furnished Bid Schedule found in the Proposal. The substitute Schedule shall be attached to the last page of the CITY-furnished Bid Schedule in the Bidder's Proposal.

The following information shall appear on top of each page of the computer-printed Bid Schedule:

1. Improvement District Number or Project Number.
2. Date of Bid Opening.

## DIVISION 100 – GENERAL PROVISIONS

3. Type and Description of Work (i.e., Sanitary Sewer, Water Main, Storm Sewer, and Incidentals).
4. Page Number.
5. Bidder's Name and Address.
6. Acknowledgement of Addenda.

The substitute Bid Schedule shall be printed on sheets of approximately the same size as the Bid Schedule in the Proposal, and the words and numerals shall be clear and legible. Each page shall be arranged, numbered, and contain the same bid items as the corresponding Bid Schedule in the Proposal. Column headings shall be the same as those in the CITY-furnished Bid Schedule.

Each bid item shall be separated from the bid items above and below by one or more blank spaces. Solid lines for separating columns and items are not required, but dashed lines may be placed either vertically or horizontally.

The total sum of the bid shall be at the bottom of the last page of the computer-printed Schedule. CONTRACTOR shall initial in ink next to the total sum.

The bidder, or authorized representative, shall sign the substitute Bid Schedule in ink on the last page of the computer printout. The signer's name and title shall be printed below or beside the signature. The person signing the substitute Bid Schedule above shall also sign and complete the Affidavit in the Bidder's Proposal, as regularly required.

In case of discrepancies between item descriptions or quantities in the CITY-furnished Bid Schedule in the Proposal and those in the computer-printed Bid Schedule, the CITY-furnished Bid Schedule in the Proposal will govern. Any omitted items or missed items will be considered as "zero," and no payment will be considered for that item.

### **102-4 BID BOND**

Unless otherwise specified, each bid shall be accompanied by a bid bond in the amount of 5 percent of the amount of the bid, meeting the requirements of Section 48 of the North Dakota Century Code, as amended.

The bid bond shall be conditioned such that the principal's bid is valid for a minimum of 30 calendar days, or such time as detailed in the project documents, and if accepted and a contract is awarded, the principal shall return the executed contract within ten days of receipt of the notice of award.

### **102-5 CONTRACT BOND**

The Performance and Payment Bond required in Section 102 shall not be included as a separate item, but shall be incidental to the project.

### **102-6 CONTRACTOR'S INSURANCE**

## DIVISION 100 – GENERAL PROVISIONS

The CONTRACTOR shall not commence work under the contract until a "Certificate of Insurance" has been obtained and submitted to the CITY for all insurance required under this section and proof of such insurance has been delivered to the CITY, nor shall the CONTRACTOR allow any Subcontractor to commence on any subcontract until all similar insurance required of the Subcontractor has been obtained and proof has been delivered to the CITY.

**(a) Compensation Insurance.** The CONTRACTOR shall take out, and maintain during the life of the contract, Workers Compensation Insurance for all of CONTRACTOR's employees employed at the site of the project. In case any work is sublet, the CONTRACTOR shall require the Subcontractor similarly to provide Workers Compensation Insurance for all of the latter's employees unless such employees are covered by the protection afforded by the CONTRACTOR. In the case of employees engaged in hazardous work under the contract, at the site of the project, who are not protected under the Workers Compensation statute, the CONTRACTOR shall provide and shall cause each subcontractor to provide Employer's Liability Insurance for the protection of its employees not otherwise protected.

**(b) Public Liability and Property Damage Insurance.** The CONTRACTOR shall take out, and maintain during the life of the contract, such Public Liability and Property Damage Insurance as shall protect it, the CITY, and any Subcontractor performing work covered by the contract, for claims and damages for personal injury including accidental death and including the coverage for "Assault and Battery" as well as from claims for property damage (including damage to CITY's property), which may arise from operations under the contract, whether such operations by itself or any Subcontractor or by anyone directly employed by either of them to, from, or on the site and the amounts of such insurance shall be as follows:

Public Liability Insurance in an amount not less than \$500,000 per person and in an amount not less than \$2,000,000 per occurrence for personal injuries, etc., including accidental death to any person, and Property Damage Insurance not less than \$2,000,000. Where excavation, trenching, or tunneling is involved, the Property Damage Liability Coverage under the Comprehensive General Liability Policy shall specifically provide coverage for damage to underground property. The CITY OF BISMARCK shall be named as an additional insured on all the policies required under this section, with a waiver of subrogation in favor of the CITY OF BISMARCK.

**(c) Satisfactory Coverage.** In the event the form of any policy or certificates or the amount of the insurance or the companies writing same are not satisfactory to the CITY, the CONTRACTOR shall obtain new policies or certificates in compliance with these Specifications. The CONTRACTOR shall not cause any policies to be canceled or to permit them to lapse, and all insurance policies shall include a clause to the effect that the policy shall not be canceled or changed until 30 days after the CITY has received written notice as evidenced by the return receipt of the registered letter.

**(d) Proof of Insurance.** "Certificates of Insurance" shall contain true transcripts from the policy, authenticated by the proper officer of the insurer, evidencing in particular

those insured, the extent of the insurance, the locations and operations to which the insurance applies, the effective date and expiration date, and the notice of cancellation clause mentioned herein above.

### **102-7 DEBARMENT CERTIFICATION**

As required by Bismarck City Ordinance, all suppliers, CONTRACTORS, and service providers doing business with the CITY must certify that they are in compliance with all federal, state, and local laws, regulations, and orders including, but not limited to, those regarding non-discrimination, wages and hours, Workers Compensation, and immigration. Failure of compliance may result in the cancellation of any CITY contract and exclusion from consideration for future contracts.

By submission of a bid or proposal, the bidder or proposer certifies, to the best of its knowledge and belief, that it and its principals:

- (a) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any federal department or agency;
- (b) Have not, within a three year period preceding this certification, been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense including, but not limited to, a violation of federal or state antitrust statutes, or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, immigration violations, or receiving stolen property in connection with obtaining, attempting to obtain, or performing a public (federal, state, or local) contract;
- (c) Are not presently indicted for or otherwise criminally or civilly charge by a governmental entity (federal, state, or local) with commission of any of the offenses listed in subparagraph (b) of this certification; and
- (d) Have not within a three year period preceding this certification had one or more public contracts (federal, state, or local) terminated for cause or default.

The bidder or proposer also certifies that if it later becomes aware of any information contradicting the statements above, it will provide that information to the CITY.

If the bidder or proposer is unable to certify to all statements in this certification, it shall indicate so in its bid or proposal or in a transmittal letter or message accompanying its bid or proposal and provide a written explanation to the CITY.

### **102-8 LOCAL CONDITIONS**

Bidders shall satisfy themselves as to the nature of the material to be handled and the local site conditions affecting the work, and if conditions are found to be different than anticipated by the CONTRACTOR subsequent to the signing of the contract, it shall not

in any way relieve the CONTRACTOR from its obligation or any risks from the fulfillment of all the work and terms of the contract.

### **102-9 SUPPLY OF MATERIALS**

Bidders shall fully inform themselves as to the source of acceptable materials needed for the work and regarding the carrier rates and transportation facilities for those materials before submitting bids.

Changes in carrier rates, or the alteration of transportation facilities for those materials, during the life of the contract will not constitute cause for claiming extra compensation.

### **102-10 INDEMNITY AGREEMENT FOR CONTRACTORS**

The CONTRACTOR agrees to indemnify and hold harmless the CITY OF BISMARCK, its appointed and elective officers and employees, from and against any and all loss or expense, including attorney's fees and costs by reason of liability imposed by law upon the CITY, its elected or appointed officials or employees, for damages because of bodily injury including death at any time resulting therefrom sustained by any person or persons and on account of damage to property including loss of use thereof, arising out of or in consequence of the performance of this work, whether such injuries to persons or damage to property is due to the negligence of the CONTRACTOR, its agents or employees, its subcontractors, their employees, CITY OF BISMARCK, its appointed or elected officers, employees, or their agents, except only such injury or damage as shall have been occasioned by the sole negligence of the CITY, its appointed or elected officials or employees.

### **102-11 REQUEST FOR ALTERNATE SPECIFICATIONS**

The reference to manufacturer's name and catalog or model numbers shall be interpreted as establishing a standard of quality, not as limiting competition.

Pre-approved materials and equipment are listed in the Specification or Standard Drawings. CONTRACTORS intending to price material or equipment not referenced in Specifications or Standard Drawings shall request in writing, to the CITY ENGINEER, to have the material or equipment recognized as an approved equivalent. The CONTRACTOR must include complete descriptive technical data on the proposed item consisting of: model numbers, type, size, and performance characteristics. Procedure also applies to requests by suppliers.

The request for consideration of an approved equivalent must be provided to the CITY ENGINEER no later than 10 days prior to bid opening, unless otherwise specified. All equivalents approved for bid may be listed in addenda sent to all plan holders in advance of bid opening.

CONTRACTORS choosing to use material or equipment other than those shown on Drawings or specified in detail, but approved for bid, shall be responsible for physical

## DIVISION 100 – GENERAL PROVISIONS

dimensions and coordination. The CITY OF BISMARCK will not be responsible for costs of necessary changes and additional work required by the CONTRACTOR or any other trades arising from such use.

If the alternate is deemed unacceptable to the ENGINEER, the bidder may request, in writing, that the matter be scheduled for consideration by the Board of City Commissioners. Such request must be made to the City Administrator no later than 7 days prior to the Board of City Commissioners meeting set for the award date. Requests for consideration by the Board of City Commissioners after that date shall not be honored.

### **102-12 AWARD AND CONTRACT SECURITY**

The bidder to whom the award is made will be required to enter into a written contract with the CITY OF BISMARCK as required by Section 48 of the North Dakota Century Code. Pursuant to NDCC Section 48, simultaneously with the CONTRACTOR's delivery of the executed contract, the CONTRACTOR shall furnish a Performance Bond from a responsible surety in an amount not less than 100 percent of the total contract amount as security for the faithful performance of the contract and a Payment Bond from a responsible surety in an amount not less than 100 percent of the total contract amount as security for the payment of all persons performing labor on the project under the contract and furnishing materials in connection with the contract.

After the proposals are opened and read, the products of the quantities and the respective unit prices bid and the summation of said products in each Proposal will be verified or corrected. In case of discrepancy, the bidder's apparent intent indicated shall govern. Discrepancies between the multiplication of units of work and unit prices will be resolved in favor of the unit prices. Discrepancies between the indicated sum of any column of figures and the correct sum thereof will be resolved in favor of the correct sum. Discrepancies between words and figures will be resolved in favor of the words. However, if the bidder's intent is not apparent, the Proposal will be rejected. The verified or corrected totals of the Proposals considered will be compared and the results of such comparison made public. Until the award of the contract, however, the right will be reserved to reject any and all proposals and to waive technicalities as may be deemed best for the interests of the CITY. All quantities are estimated and shall be equal per each item for comparison of bids per each unit of area. Addenda quantities shall govern over bid Proposal quantities which shall govern over Plan quantities.

The award of the contract, if made, will be to the lowest responsible bidder whose Proposal complies with all the requirements specified. The award, if made, will be made within the time specified in the Advertisement for Bids unless an extension of this limit is agreed to in writing by both parties. In the case of participation in the project by federal and/or state government, or any agency, subdivision, or other participating party, or if concurrence of the aforementioned parties is required by law, any award made by the Board of City Commissioners shall be deemed subject to concurrence of the participating and/or regulatory parties.

## DIVISION 100 – GENERAL PROVISIONS

If the project includes more than one unit or contains alternates, the basis of award shall be the lowest and best bid for the units or alternates selected by the CITY. Units or alternates not selected shall not be included in forming the basis of determining the lowest bid. Bidders shall be aware that there is no guarantee that all units or alternates will be awarded and balance their bids accordingly.

Prior to the CITY execution of the contract, the successful (or apparent low) bidder shall submit to the CITY ENGINEER a schedule of proposed progress showing the proposed starting and completion dates and with curves showing the percentage of the major features of the work scheduled for completion at any date together with a composite curve showing the percentage of the entire contract which will be completed at any date.

The proposed Progress Schedule shall show the starting date and the number of working days deemed necessary by the CONTRACTOR to complete the work on or before the completion date shown in the Proposal.

The number of working days shown on the Progress Schedule shall not exceed the number of calendar days, excluding Sundays and holidays, between the proposed starting date and the completion date shown in the Proposal.

After the proposed Progress Schedule, Payment and Performance Bonds, Certificate of Insurance, and any other required documents have been submitted to the CITY ENGINEER, they will be reviewed and forwarded to the CITY ATTORNEY with a recommendation to execute the contract. By entering into a contract, the CONTRACTOR represents that it has carefully reviewed the Plans, Specifications, and General and Special Provisions and has inspected the site conditions and that it has the capability to complete a good and workmanlike project in conformance with the Plans, Specifications, and General and Special Provisions.

As provided by North Dakota statutes, no contract will be awarded to any CONTRACTOR who is not the holder of a current license in the class within which the value of the project falls. A foreign corporation must have a Certificate of Authority to do business in North Dakota before a contract can be awarded to said corporation.

The CITY OF BISMARCK reserves the right to cancel the award of any contract at any time before the execution of said contract by all parties without any liability against the CITY.

All bidders' bonds, except in case of defaults, will be returned, upon request, within a reasonable time and as provided by law.

All bidders should note that after the award of the contract to the lowest bidder is approved by the Board of City Commissioners, and the contract is fully executed, ALL bid documents submitted to the CITY will be destroyed utilizing standard office practices, with the exception of the bid of the successful bidder. Should a non-successful bidder want its bid documents returned, it should include a self-addressed,

## DIVISION 100 – GENERAL PROVISIONS

postage-paid envelope with the bid, or request that the bid documents be saved in a self-addressed envelope included with the bid to be picked up at the Engineering Department upon the signature of the bidder.

### **SECTION 103 – SCOPE OF WORK**

#### **103-1 SUBCONTRACTING**

All work performed under the contract shall be by the company or firm to which the contract is awarded, and no portion of the work shall be awarded to a subcontractor unless authorized in writing by the ENGINEER acting on the approval of the Board of City Commissioners. The CONTRACTOR shall be responsible for the coordination and control of the subcontractor(s).

#### **103-2 MOBILIZATION**

This work consists of preparatory work and operations, including movement of personnel, equipment, and supplies and establishment of offices, CONTRACTOR's buildings, and facilities necessary for work on the project. This work and all other work and operations which must be performed along with all costs incurred before the beginning work on the project site shall be incidental to the project.

#### **103-3 CHANGES**

The Board of City Commissioners reserves the right to make any changes in the alignment, grade, or design as may be deemed advisable, and should any changes so made cause the CONTRACTOR extra expense or operate to decrease CONTRACTOR's expense, the ENGINEER shall make due allowance, as agreed upon by ENGINEER and CONTRACTOR, which action shall be binding upon both parties. The CONTRACTOR with whom the contract for the execution of the work is made will be required to make any extension which the Board of City Commissioners may require. The extensions shall be constructed at the same unit price for the same class of work as bid upon for this work, provided that should the prices of materials be increased or diminished over the prices of the same materials at the present time for the same class of work, the ENGINEER shall make due allowance. The action shall be binding upon both parties and provided further that such extensions shall be ordered prior to the completion of the contract.

#### **103-4 PATENTS**

The CONTRACTOR will be held responsible and be required to make good at the CONTRACTOR's expense any and all damages and suits for damages caused by infringements of the patent rights on devices or equipment for the requirements of the contract and is to indemnify and hold harmless the CITY OF BISMARCK from all claims, damages, or expenses by the use thereof. All fees and royalties covering the same are

## DIVISION 100 – GENERAL PROVISIONS

to be included in the price bid by the CONTRACTOR for the work to be done under the Specifications.

### **103-5 TRAFFIC CONTROL DEVICES**

The CONTRACTOR is expected to be familiar with all federal, state, and local laws, codes, ordinances, and regulations which in any manner affect those engaged in the work or the materials or equipment used in or upon the site or in any way affect the conduct of the work. No pleas of misunderstanding or ignorance on the part of the CONTRACTOR will in any way serve to modify the provisions of the contract. The CONTRACTOR shall provide and maintain on a 24 hour basis all necessary safeguards and traffic control devices at its own expense.

The CITY OF BISMARCK has adopted the U.S. Department of Transportation Manual on Uniform Traffic Control Devices, 2009 Edition, or latest Edition, and all revisions, for all traffic control devices and their placement. For all materials and equipment used for traffic control on all construction projects in the CITY OF BISMARCK, the CONTRACTOR shall comply with Section 704 of the Standard Specifications for Road and Bridge Construction and the Design Standard Drawings of the North Dakota Department of Transportation. The documents referred to above are available at the City of Bismarck Engineering Department.

When detours for roadway closures are not incorporated within the Plans or are required because of an emergency situation, water main break, sewer collapse, etc., the CONTRACTOR shall submit a traffic control plan to the ENGINEER for review and approval.

## **SECTION 104 – CONTROL OF WORK**

### **104-1 ENGINEER**

The ENGINEER is the authority on the engineering details of the project and the administrative responsibilities for the satisfactory completion of the project. The ENGINEER will give the grades and locations for all work, and no work depending upon such grades or locations shall be commenced until after the same have been established. Upon all questions concerning the interpretations of these Specifications or the plans, the decision of the ENGINEER shall be binding upon both parties. Detailed Plans of all work not completely shown on the Plans now on file will be furnished by the ENGINEER from time to time, and the work shall be executed in accordance with such detailed plans.

The ENGINEER has authority to reject defective material or work that does not meet the contract requirements or is not installed per manufacturer's recommendations. The ENGINEER has the authority to suspend the work for the following reasons:

- a. The CONTRACTOR fails to carry out contract requirements;
- b. The CONTRACTOR fails to carry out orders from the ENGINEER;
- c. During periods of unsuitable weather;

## DIVISION 100 – GENERAL PROVISIONS

- d. For conditions considered unsuitable for performance of the work;
- e. For other conditions or reasons in the public interest; or
- f. For other reasons the ENGINEER and CONTRACTOR mutually agree on.

### **104-2 ONLINE PROJECT MANAGEMENT**

The CITY utilizes Virtual Project Manager (VPM) online software ([www.virtual-pm.com](http://www.virtual-pm.com)) for construction management of its projects. VPM is a no-cost, paperless system used for project documentation and administration. The CONTRACTOR shall use VPM's web-based platform for all project-related submittals, review and approval of pay estimates, and other required project management functions. All CONTRACTOR personnel responsible for these functions shall obtain and maintain a VPM account for the duration of the project.

### **104-3 CONTRACTOR**

The foreman of the CONTRACTOR in charge of the work will be held to represent the CONTRACTOR during the absence of the latter or CONTRACTOR's legal representative. Instructions given to the CONTRACTOR's foreman on the work by the ENGINEER will be held as having been given to the CONTRACTOR.

### **104-4 CHARACTER OF WORKMEN**

If any person employed on the project, whether a CONTRACTOR'S employee or not, is intemperate, prejudiced, abusive, or disorderly, the ENGINEER may direct the CONTRACTOR in writing to discharge the person from the work. Re-employ this person on the project only with the ENGINEER'S approval. If the CONTRACTOR fails to remove a person as directed by the ENGINEER or to provide sufficient personnel for the proper execution of the work, the ENGINEER may suspend the work by written notice until the CONTRACTOR complies.

### **104-5 METHODS AND APPLIANCES**

The methods and appliances adopted by the CONTRACTOR shall be such as will enable the CONTRACTOR to secure a satisfactory quality of work and complete the work within the time specified. The choice of methods and appliances to complete the work in compliance with the Plans and Specifications is solely the CONTRACTOR's. It is the responsibility and obligation to produce a complete project that fully complies with the Plans and Specifications and is of satisfactory quality. The ENGINEER may at any time inform the CONTRACTOR of apparent deficiencies in the work, and the CONTRACTOR will make whatever adjustments are, in the CONTRACTOR's judgment, necessary to bring the work back into conformance. Failure of the ENGINEER to so advise the CONTRACTOR shall not in any way relieve the CONTRACTOR from its obligations which shall remain in full force and effect until the discharge of the contract. The Board of City Commissioners of the CITY OF BISMARCK reserves the right, in

case of improper construction, to suspend the work at any time and to reject the work or to order the reconstruction of any part or all of the work improperly done.

#### **104-6 MONUMENTS, BENCH MARKS, WITNESS AND GRADE STAKES**

All monuments, bench marks, and witness and grade stakes are the property of the CITY, and in the event of the destruction or removal by the CONTRACTOR, such stakes shall be replaced by the ENGINEER at the CONTRACTOR's expense. Any interruption of work and/or costs incurred by the CONTRACTOR due to any delays caused during the replacement of destroyed monuments, bench marks, and witness and grade stakes shall be borne by the CONTRACTOR. The CONTRACTOR shall be responsible for notifying the ENGINEER a minimum of 72 hours prior to the expected survey.

#### **104-7 CONTRACTOR'S RESPONSIBILITIES**

The CONTRACTOR shall maintain open communication with the ENGINEER throughout the duration of the project and respond to correspondence with the ENGINEER in a timely manner.

Unless otherwise specified, the CONTRACTOR shall furnish all labor, materials, and equipment necessary for the completion of the Schedule of Work in accordance with the Plans and Specifications. The CONTRACTOR shall provide all labor equipment and materials required to perform the work, incidental thereto, for which no express provisions have been made. The CONTRACTOR shall assume all risks or damages to persons or property prior to the final acceptance of the work. The CONTRACTOR shall so conduct its operation as not to interfere with the work of other contractors in the vicinity. The CONTRACTOR shall maintain at all times an efficiently sized crew headed by a competent construction foreman and the necessary skilled labor to efficiently complete the work.

The CONTRACTOR shall be responsible for maintenance and operation of all constructed facilities until final acceptance unless otherwise noted in Specifications, notes, or Special Provisions. This includes locating of CONTRACTOR-constructed underground facilities.

When damage occurs to work that is substantially complete, prior to final acceptance of a project, and is caused by public traffic, the CONTRACTOR shall identify the party that is responsible for the damage, pursue all reasonable means to recover the costs of the damage, and repair the damage to the work. When the CONTRACTOR cannot recover the costs by reasonable means, the CITY will pay the CONTRACTOR for the unrecovered costs. Repairs shall be authorized by the ENGINEER prior to any repair work by the CONTRACTOR.

### **104-8 SHOP DRAWINGS**

Before any of the materials are delivered to the job, the CONTRACTOR shall submit to the CITY ENGINEER complete Shop Drawings.

The Shop Drawing submittal shall include two copies in paper format or one electronic copy in PDF format. An approved electronic copy will be sent to the CONTRACTOR upon approval, paper format of approved drawings will not be provided unless requested by the CONTRACTOR.

Shop Drawings shall be submitted for all types of supplied materials including water, sanitary sewer, storm sewer, and electrical. The Shop Drawings shall include catalog numbers, performance data, dimensions, and other descriptive information.

Paper format Shop Drawings may be in the form of printed catalog sheets showing all necessary information and shall be bound together, neatly indexed, and tabbed.

Each Shop Drawing folder or set of drawings shall be stamped, initialed, and dated, electronically or on hard copy, by CONTRACTOR to indicate it has thoroughly reviewed them.

The CITY review of Shop Drawings is for general compliance with contract documents. The CITY review does not relieve the CONTRACTOR from responsibility for errors, omissions, or deviations from contract requirements.

Shop Drawings not in conformance with the Specifications may be returned to the CONTRACTOR without review.

### **104-9 CONFORMITY WITH PLANS & SPECIFICATIONS**

Unless specific tolerances are specified, all work performed and all materials furnished shall be in reasonably close conformity with the lines, grades, cross sections, dimensions, and material requirements shown on the Plans or indicated in the Specifications.

Plan dimensions and contract specification values are to be considered as the target value from which any deviations are allowed. It is the intent of the Specifications that the materials and workmanship shall be uniform in character and shall conform as nearly as realistically possible to the prescribed target value or to the middle portion of the tolerance range. The purpose of the tolerance range is to accommodate occasional minor variations from the median zone that are unavoidable for practical reasons. When a maximum or minimum value is specified, the production and processing of the material and the performance of the work shall be so controlled that the material or work will not be preponderantly of borderline quality or dimension.

In the event the ENGINEER finds the materials or the finished product in which the materials are used are not within reasonably close conformity with the Plans and

## DIVISION 100 – GENERAL PROVISIONS

Specifications but that reasonably acceptable work has been produced, the ENGINEER will then make a determination if the work will be accepted and remain in place. In this event, the ENGINEER will document the basis of acceptance by contract modification which will provide for an appropriate adjustment in the contract price for such work or materials as the ENGINEER deems necessary to conform to a determination based upon engineering judgment.

In the event the ENGINEER finds the materials or the finished product in which the materials are used or the work performed are not in reasonably close conformity with the Plans and Specifications and have resulted in an inferior or unsatisfactory product, the work or materials shall be removed and replaced or otherwise corrected by and at the expense of the CONTRACTOR.

### **104-10 DELAYS**

The CONTRACTOR will not be entitled to any compensation for foreseeable or unforeseeable causes resulting in delays or hindrances to the work. Extensions of time will be granted for unavoidable delays, which in the opinion of the ENGINEER are clearly beyond the control of the CONTRACTOR and outside of normal occurrences including, but not restricted to, acts of God or of the public enemy, acts of the CITY, acts of another CONTRACTOR in the performance of a contract with the CITY, fires, epidemics, quarantine restrictions, strikes, freight embargoes, and abnormal weather. The ENGINEER must receive a written request for time extension from the CONTRACTOR not more than 20 days after commencement of delay before any time extension will be considered. Requests made beyond the 20-day limit will be cause for denial. Any extension of time will not relieve the CONTRACTOR or its sureties from their obligations which shall remain in full force and effect until the satisfactory discharge of the contract.

Extra time may be granted to complete the project due to material delays at the discretion of the ENGINEER. No monetary compensation shall be made for material delays.

### **104-11 MULTIPLE CONTRACTS ON SAME SITE**

When different types of construction work on the same section of public right-of-way or site are let under separate contracts, the CONTRACTORS shall cooperate with each other to the fullest extent possible that the prosecution of the work under each contract will be carried out for the best interests of the CITY. The CITY assumes no liability for any delay caused by any CONTRACTOR, its subcontractor(s) or supplier(s), to any other CONTRACTOR, its subcontractor(s) or supplier(s).

### **104-12 COOPERATION BETWEEN CONTRACTORS**

The CITY reserves the right to contract for and perform other work on or near the site of work and coordinate the work and cooperate with the CONTRACTOR for the other work. The CONTRACTOR is responsible for all liability, financial or otherwise, in connection with the contract, and shall hold the CITY harmless from damages or claims

resulting from inconvenience, delay, or loss due to the CONTRACTOR's failure to coordinate the work or cooperate with the CONTRACTOR for the other work. If a conflict occurs between the CONTRACTOR for the other work, the ENGINEER will provide direction.

#### **104-13 TRANSPORTATION OF MATERIALS**

The CONTRACTOR is authorized to ship all construction materials which are to be incorporated into the project to the CITY OF BISMARCK in care of the CONTRACTOR. Such materials are exempt from the federal tax on transportation of said materials. The exemption of federal tax does not apply to shipments of fuel, lubricants, spare parts, and items of construction equipment belonging to the CONTRACTOR and which will not be incorporated into the construction project and which will not become the property of the CITY OF BISMARCK. This authorization is granted with the distinct understanding that the CITY OF BISMARCK will receive all benefits from the exemption from payment of the tax. The tax is not included in the CONTRACTOR's bid, and all transportation charges shall be paid by the CONTRACTOR.

#### **104-14 EXTRA WORK**

The CONTRACTOR shall perform extra work for which there is no price in the contract whenever it is deemed necessary or desirable in order to complete fully the work as contemplated. If the CONTRACTOR contends that additional compensation is due for work or material not clearly covered in the contract, the CONTRACTOR shall promptly notify the ENGINEER in writing of the intention to file a claim and the basis for additional compensation before beginning or continuing construction on the affected work. If the basis for the claim does not become apparent until after proceeding with the work, and it is not feasible to stop the work, the CONTRACTOR shall immediately notify the ENGINEER that work is continuing and that written notification of the intent to file a claim will be submitted within 10 calendar days. Failure to give the required notification or to provide the ENGINEER proper facilities and assistance in keeping strict account of actual costs will constitute a waiver of the claim for additional compensation in connection with the work already performed. Notification of a claim, and the fact that the ENGINEER has kept an account of the costs involved, shall not be construed as proving or substantiating the claim's validity. Such work shall be performed in accordance with the Specifications. Work contained in the Plans and Specifications shall not be considered extra work and shall not be paid for by the CITY as such unless specifically agreed to in writing.

When work not shown on the plans is to be performed by the CONTRACTOR, the ENGINEER and the CONTRACTOR shall determine compensation based on mutually agreed prices, on a per unit or lump sum basis, for the extra work.

The ENGINEER may request the CONTRACTOR to provide an estimate of the proposed unit prices or a lump sum for the extra work. The ENGINEER may request the CONTRACTOR to justify the estimate by providing one or more of the following: (a)

## DIVISION 100 – GENERAL PROVISIONS

Labor requirements by trade in hours for each task, (b) equipment costs and time requirements, (c) material costs, and (d) any additional costs.

If the prime CONTRACTOR uses a subcontractor to exclusively perform the revised work, the CITY shall pay the prime CONTRACTOR an additional markup on the subcontractor's agreed upon price as per section (f) "Subcontracting" below.

If the ENGINEER and the CONTRACTOR cannot agree on compensation for the extra work, or when it is considered to be in the best interest of the CITY, the ENGINEER may order the work done on a force account basis. Compensation for force account work shall be justified in the following manner:

**(a) Labor.** For all laborers (skilled and unskilled) and foremen in direct charge of the specific operations, the CONTRACTOR shall receive the rate of wage (or scale) agreed upon in writing before beginning work for each and every hour that said laborer and foremen are actually engaged in such work.

The wages of any foreman who is employed partly on the force account work and partly on other work will be prorated according to the number of workers in the two classes of work as shown by the payrolls.

The CONTRACTOR shall receive the actual costs paid to, or on behalf of, workmen by reason of subsistence and travel allowances, health and welfare benefits, pension fund benefits, or other benefits, when such amounts are required by a collective bargaining agreement or other employment contracts generally applicable to the classes of labor employed on the work, but excepting any amounts which are already included in the wage rates paid. Any subsistence or travel allowance paid to the workmen shall be prorated according to the number of hours employed on the force account and other classes of work.

An amount equal to 20 percent of the sum of the above items will also be paid to the CONTRACTOR.

**(b) Bond, Insurance, and Tax.** For premiums paid on additional bond, property damage, liability, and workers compensation insurance contributions, and Social Security Taxes on the force account work, the CONTRACTOR shall receive the actual cost, to which cost 6 percent will be added. The CONTRACTOR shall furnish satisfactory evidence of the rate or rates paid for such bond, insurance, and tax.

**(c) Materials.** For materials accepted by the ENGINEER and used, the CONTRACTOR shall receive the actual costs of such materials delivered on the work, including transportation charges paid by the CONTRACTOR (exclusive of machinery rentals as hereinafter set forth), to which cost 15 percent will be added plus any sales tax paid by the CONTRACTOR. For all materials used in connection with, but not entering permanently into the work, reasonable depreciation will be allowed.

## DIVISION 100 – GENERAL PROVISIONS

**(d) Equipment.** For the use of authorized equipment and additional traffic control devices required by the force account work, the CONTRACTOR will receive rental rates determined in accordance with the *Rental Rate Blue Book* published by Equipment Watch. No percentage shall be added to these rates. No allowance will be allowed for equipment replacement or replacement escalators, cost of facilities capital, interest, small tools, or any other additives not listed. All equipment hours will be paid for as straight time. The only equipment payments that will be made are as follows:

**(1) Owned Equipment.** Payment for the actual hours of CONTRACTOR-owned equipment will be at 70 percent of the hourly ownership cost determined in accordance with the *Rental Rate Blue Book*. The hourly ownership cost equals the regionally adjusted monthly ownership cost divided by 176 hours per month.

The computed hourly equipment cost times the number of hours claimed shall not exceed the CONTRACTOR's actual purchase price for the piece of equipment being claimed.

Subcontractor-owned equipment will be paid for in the same manner as CONTRACTOR-owned equipment unless such equipment has been rented, leased, or hired by the CONTRACTOR, as provided for in (2) below.

**(2) Leased, Rented, or Hired Equipment.** Payment for leased, rented, or hired equipment shall be the actual invoice payment plus sales tax as verified by paid invoices signed by the lessor, or by checks issued by the CONTRACTOR. If the lease rental is weekly, the weekly rate shall be divided by 40 to get an hourly equipment cost for the claim. If the lease or rental is monthly, the monthly rate shall be divided by 176 to get an hourly equipment cost for the claim.

The computed hourly equipment cost, for each individual piece of equipment, times the number of hours claimed shall not exceed the CONTRACTOR's actual lease or rental cost for the time frame claimed.

**(3) Idle Time.** The number of hours of equipment use to be paid for will only be the hours that the equipment is operating on the claim item. No payment will be made for equipment on standby unless the standby is directed in writing by the ENGINEER, or the standby is proven to be as the direct result of the CITY's actions or inactions. Standby will be paid at 50 percent of the hourly base rate calculated by dividing the monthly rate by 176. The listed weekly, daily, or hourly rates will not be used. Operating costs will not be paid for hours of idle time.

Payment for standby time will not be made on any day the equipment operates for 8 or more hours. For equipment accumulating less than 8 hours operating time on any normal work day, standby payment will be limited to only that number of hours which, when added to the operating time for that day, equals 8 hours. Standby payment will not be made in any case on days not normally a work day.

## DIVISION 100 – GENERAL PROVISIONS

The above rental rates to be paid on equipment will be on the size normally used to operate the equipment, subject to approval of the ENGINEER. The above rental rates include gas, oil, repairs, and any other incidentals necessary for the operation of the equipment but do not include the operators. No work will be paid for until unit prices, rental rates, and wages have been agreed upon in writing.

Procedures governing rented or owner-operated equipment, attachments and accessories, types and quantity of equipment, measurement of equipment time, use of equipment in excess of 50 hours per week, standby time, and equipment transportation charges will be as set forth in the *Rental Rate Blue Book*.

**(e) Miscellaneous.** No additional allowance will be made for general superintendence, the use of small tools, or other costs for which no specific allowance is herein provided.

**(f) Subcontracting.** For any extra work, including force account work, performed by a Subcontractor with the written authorization of the ENGINEER, the CONTRACTOR will receive an additional allowance for administrative and overhead expense. The additional allowance will be a percentage of the total extra work invoice equal to 10 percent of the first \$10,000 plus three percent of the balance in excess of \$10,000.

**(g) Authority of ENGINEER.** The ENGINEER has authority to require alterations in the equipment and labor force assigned to force account work, to limit authorization of overtime work to that normally used on the project for work of similar nature, or to require overtime when an emergency exists, and to require the cessation of force account work when adverse conditions severely limit productivity.

**(h) Daily Records.** The CONTRACTOR's representative and the ENGINEER shall compare records of the cost of work done as ordered on a force account basis at the end of each day for the purpose of resolving differences.

**(i) Statements.** No payment will be made for work performed on a force account basis until the CONTRACTOR has furnished the ENGINEER with duplicate itemized statements of the cost of such force account work detailed as follows:

1. Name, classification, date, daily hours, total hours, rate, and extension for each laborer and foreman.
2. Designation, dates, daily hours, total hours, rental rate, and extension for each unit of machinery and equipment.
3. Quantities of materials, prices, and extensions.
4. Transportation of materials.
5. Cost of property damage, liability and workers' compensation insurance premiums, unemployment insurance contributions, and Social Security Tax.

Statements shall be accompanied by receipted invoices for materials used including transportation charges paid by the CONTRACTOR. The statements shall be adjusted, when applicable, to reflect any discounts offered by the supplier. When materials used

## DIVISION 100 – GENERAL PROVISIONS

in the force account work are not specifically purchased for that work but are taken from the CONTRACTOR's stock, the CONTRACTOR shall furnish an affidavit certifying such materials were taken from stock, the quantity claimed was actually used, and that the price and transportation costs claimed are the CONTRACTOR's actual costs.

On or before the tenth day succeeding the completion of the extra work authorized by a "Work Order," the CONTRACTOR shall present to the ENGINEER the original "Work Order," together with a full and complete itemized statement of such extra work, with date of completion of the work mentioned therein. Upon certification by the ENGINEER or his authorized representatives as to the correctness of such items with regard to the amount and character of labor performed and materials furnished under such "Work Order," the ENGINEER shall enter the same as part of the estimate of the amount due the CONTRACTOR. The CONTRACTOR shall not be entitled to receive payment for any extra work in which he fails to present the "Work Order" within the time and in the manner hereinbefore mentioned.

The additional payment based on the percentages specified above shall constitute full compensation for all items of expense not specifically provided for the force account work. The total payment made as provided above shall constitute full compensation for such work.

### **104-15 OBSERVATION AND TESTING**

All materials and equipment used in the construction of the project shall be subject to adequate observation and testing in accordance with generally accepted standards.

The CONTRACTOR shall provide at its expense the necessary testing and inspection services required by the Plans and Specifications unless otherwise provided.

All concrete field testing personnel shall be certified through the American Concrete Institute (ACI) at the minimum level of an ACI Concrete Field Technician Grade I.

All independent testing laboratories provided by the CONTRACTOR shall be accredited independent testing laboratories (heretofore referred to as "independent testing laboratory") currently certified through the American Association of State Highway and Transportation Officials (AASHTO) accreditation program to perform the required testing and reporting procedures for the specific project.

All laboratory testing reports shall be supplied by the CONTRACTOR to the ENGINEER within 48 hours via email or as directed by the ENGINEER. Hard copies can also be delivered within 48 hours to the ENGINEER

If the Plans and Specifications, laws, ordinances, rules, regulations, or orders of any public authority having jurisdiction require any work to specifically be inspected, tested, or approved by someone other than the CONTRACTOR, the CONTRACTOR will give the ENGINEER timely notice of readiness. The CONTRACTOR will then furnish the ENGINEER the required certificates of inspection, testing, or approval.

## DIVISION 100 – GENERAL PROVISIONS

Neither observations by the ENGINEER nor inspections, tests, or approvals by persons other than the CONTRACTOR shall relieve the CONTRACTOR from its obligations to perform the work in accordance with the requirements of the Plans and Specifications.

The ENGINEER will at all times have access to the work. In addition, authorized representatives and agents of any participating federal or state agency shall be permitted to inspect or observe all work, materials, payrolls, records of personnel, invoices of materials, and other relevant data and records. The CONTRACTOR will provide facilities for such access and observation of the work and also for any inspection or testing thereof.

If any work is covered contrary to the request of the ENGINEER, it must at the ENGINEER's request be uncovered for the ENGINEER's observation and replaced at the CONTRACTOR's expense.

If any work has been covered which the ENGINEER has not specifically requested to observe prior to its being covered, or if the ENGINEER considers it necessary or advisable that covered work be inspected or tested by others, the CONTRACTOR at the ENGINEER's request will uncover, expose, or otherwise make available for observation, inspection, or testing as the ENGINEER may require, that portion of the work in question, furnishing all necessary labor, materials, tools, and equipment. If it is found that such work is defective, the CONTRACTOR will bear all the expenses of such uncovering, exposure, observation, inspection, and testing and of satisfactory reconstruction. If, however, such work is not found to be defective, the work will be under Section 104, "Extra Work" or an extension of the contract time, or both, directly attributed to such uncovering, exposure, observation, inspection, testing, and reconstruction, and an appropriate work order shall be issued.

### **104-16 FINISHING AND CLEANUP**

The CONTRACTOR shall remove all loose trash from jobsite and dispose of properly on a daily basis. From time to time or as may be ordered by the ENGINEER and immediately after completion of the work, the CONTRACTOR shall at its own expense clean up and remove all refuse, including any remaining survey stakes, and unused materials of any kind resulting from the work. Upon failure to do so within 24 hours after request by the ENGINEER, the work may be performed by the CITY and the cost thereof charged to the CONTRACTOR and deducted from the CONTRACTOR's final estimate. All excavated areas along trails, sidewalks, curbs, and other structures shall be backfilled with earth, and the cost of such work shall be incidental to the item of construction.

### **104-17 WARRANTY**

The CONTRACTOR shall guarantee all work and materials and guarantee the performance of the finished project free from material defect or failure for a period of two years from the date of substantial completion, and the performance bond shall remain in

full force and effect for the period. The CONTRACTOR shall provide this warranty regardless of whether the cause of a failure is known or attributable to the CONTRACTOR, except for damage caused by a third party by no fault of the CONTRACTOR.

In the event the deficiency in work or performance is caused by poor workmanship by the CONTRACTOR, the CONTRACTOR's liability may, at the discretion of the ENGINEER, extend past the warranty period.

## **SECTION 105 – LEGAL RELATIONSHIPS AND RESPONSIBILITIES**

### **105-1 DAMAGES**

The CONTRACTOR will be held responsible and be required to make good, at the CONTRACTOR's expense, any and all damages to personal property caused by carelessness, neglect, or want of due precaution on the part of the CONTRACTOR.

### **105-2 UTILITIES**

It shall be the responsibility of the CONTRACTOR to be familiar with the location of the existing sanitary sewer, water mains and service lines, storm sewer, oil pipelines, gas mains and service lines, telephone and communication lines, power, light and telephone poles and guys, steam lines, valve boxes and stop boxes, mail boxes, and all appurtenances pertaining to utility and public services. No additional compensation shall be made for extra work or delays due to marked or unmarked utilities, whether shown on plans or not.

The CONTRACTOR shall notify all underground facility operators at least 48 hours in advance excluding Saturdays, Sundays, or holidays, and in accordance with NDCC Chapter 49-23 of any construction and consult with personnel of said utility companies regarding any changes or conflicts.

The CONTRACTOR is responsible for repairing or replacing any lawn irrigation systems damaged by the CONTRACTOR at no cost to the CITY.

### **105-3 PROTECTION, MAINTENANCE, AND RESTORATION OF PROPERTY**

The CONTRACTOR shall protect public and private property during all construction activities. The CONTRACTOR shall assume liability for any damage to public or private property resulting from construction activities, defective work or materials, or non-execution of the contract until project acceptance.

The CONTRACTOR shall maintain, with no additional compensation, existing or newly established grassed lawn and boulevard areas in City rights-of-way and easements within work zones. Maintenance shall include regular mowing to keep grassed areas to a maximum of six inches tall during construction and four inches tall prior to project

## DIVISION 100 – GENERAL PROVISIONS

acceptance by the ENGINEER. This shall include areas that are not disturbed during construction but where access for regular maintenance by property owner is restricted by construction activities.

The CONTRACTOR shall restore, with no additional compensation, damaged property to a condition similar or equal to preconstruction conditions. Restoration shall be done in a manner acceptable to the ENGINEER and/or property owner.

### **105-4 ACCESS**

The CONTRACTOR shall provide access to residences, businesses, other private property with existing access, and public institutions during construction. If at times during construction phases this is not possible, the CONTRACTOR shall notify the ENGINEER and PROPERTY OWNERS prior to disruption of access to coordinate and make alternate arrangements. All residents shall be notified in writing of access closures 24 hours in advance. All businesses and public institutions shall be notified in writing of access closures 48 hours in advance. Closures shall be approved by ENGINEER prior to coordination with PROPERTY OWNER.

### **105-5 PARKING AND STORAGE OF EQUIPMENT AND MATERIALS**

The CONTRACTOR shall not use private property to park or store equipment, vehicles, or materials without written permission from the property owner. The CONTRACTOR shall provide the ENGINEER with a copy of the written permission and a release from the property owner upon restoration of the property to the owner's satisfaction.

### **105-6 PROTECTION OF TREES**

A CONTRACTOR working on public rights-of-way or properties shall be responsible for the prevention of damage to trees, shrubs, bushes, hedges, or other woody plants located within or infringing on the public rights-of-way and properties, including parks, and shall notify the City Forestry Department prior to beginning any construction near said trees.

The CONTRACTOR shall exercise care in driving or working on the root zone area of trees to prevent excessive compaction of the soil. Gaseous, liquid, or solid substances which are harmful to plantings shall not come into contact with any plantings. Nails, bolts, or other fastening materials shall not be imbedded into the trunk or limbs of a tree. Ropes, wires, or other hanging materials shall not be attached to a plant in such a manner that the bark may be damaged or cause undue stress to the plant structure. Materials or debris shall not be stored above the root zone of any tree which may impede the free passage of air, water, or nutrients, except by written permission of the City Forester.

Any overhanging branches or underlying roots which may be crushed, scarred, broken, or damaged in any way due to unavoidable construction activity shall be reported to the City Forester so that preventive action may be taken to minimize damage to plants. Any

## DIVISION 100 – GENERAL PROVISIONS

trees damaged without prior notification of the City Forester shall be the responsibility of the CONTRACTOR to repair or replace using a licensed tree service, upon determination by the City Forester.

If it is determined by the City Forester that ditches, tunnels, trenches, or other earthmoving operations for underground utilities construction will cause damage to the health, vigor, and stability of plants, the City Forester may require that power-driven soil augers or the power push method be used wherever possible. Where this is not possible, the City Forester must be notified to assist in determining alternate methods. If trees must be pruned, fertilized, or removed prior to construction, as determined by the City Forester, all costs using prescribed methods shall be the responsibility of the CONTRACTOR. The CONTRACTOR shall become familiar with and adhere to the Forestry Department's Standard Specifications on trenching and augering around trees.

Prior to backfilling any trench or ditch, the City Forester shall be notified to inspect any repairs made to damaged roots. All exposed roots shall be pruned or trimmed using a hand pruner or hand saw. Axe cuts will not be allowed.

Upon completion of construction, the CONTRACTOR shall notify the City Forester for a final inspection of the trees whether or not any damage occurred. Any damage found to have been due to the construction activity of the CONTRACTOR shall be the remedial responsibility of the CONTRACTOR to be corrected by a licensed tree service.

### **105-7 CITY CONDUCTOR DAMAGE**

Any cost to locate damages to CITY electrical conductors or any other components of the CITY lighting, traffic signal, or other systems will be billed to the CONTRACTOR. The CITY OF BISMARCK will bill at the current CITY rates for labor, equipment, and materials as needed. If there are any questions, contact the City of Bismarck Public Works Department at 701-355-1700.

Before any repairs are made, the damage shall be inspected by a CITY street light or traffic signal technician to determine the extent of the damage and dictate the necessary repair.

If damage causes more than two splice repairs to roadway lighting conductors in a direct-buried run between poles or to a junction box, the entire conductor run shall be replaced. Splices are not allowed on traffic signal conductors including direct-bury power supply. CONTRACTOR shall be responsible for repairs at their expense.

If damage occurs to a conductor run contained in a conduit which would require a conductor splice repair, the entire conductor run shall be replaced and the conduit must be repaired.

If damage occurs to conductors which were not located, or if due care is not exercised in exposing conductors, the entire conductor run shall be replaced.

## DIVISION 100 – GENERAL PROVISIONS

Damaged conductors shall be replaced or repaired within 24 hours of discovery, or the CITY will cause the repairs to be made and bill the CONTRACTOR. Any underground repairs shall be made in accordance with Section 1002 “Underground Splices”.

Prior to covering up any repairs, the CITY shall be notified to inspect the repair. Once repairs are accepted, the site shall be restored.

### **105-8 STREET SIGN REMOVE AND REINSTALL**

Any existing and permanent signs shall be removed and reinstalled by the CITY OF BISMARCK. The CONTRACTOR shall give the ENGINEER a three working day notice to schedule the removal at the time needed. The CONTRACTOR shall be assessed \$300 per sign for signs removed without the ENGINEER’s approval.

## **SECTION 106 – PROSECUTION AND PROGRESS**

### **106-1 TIME OF BEGINNING AND COMPLETION OF WORK**

If specified, the work on the contract shall be started on a date to be specified in the Advertisement for Bids, Special Provisions, or in a written order from the Board of City Commissioners. If a start date is not specified, the CONTRACTOR may begin work at his discretion. The work on the contract shall be completed on the date specified in the Proposal. Work shall continue without interruption until the contract is completed except for weather conditions or at the discretion of the ENGINEER. The Board of City Commissioners reserves the right to determine in what order the work shall be done, and the work shall be executed in accordance with such directions.

### **106-2 LIMITATION OF OPERATIONS**

The CONTRACTOR, unless the contract allows, shall not perform work on holidays, including Sundays, without approval from the ENGINEER a minimum of 72 hours in advance.

The CONTRACTOR perform the work in compliance with Chapter 8-10 “Noises” in the “Code of Ordinances, Bismarck, North Dakota”.

### **106-3 LIQUIDATED DAMAGES**

The CITY and the CONTRACTOR recognize that time is of the essence of the agreement. They further recognize that not only will the CITY suffer financial loss if the work is not completed within the times specified in the contract, plus any extensions thereof allowed pursuant to the terms of the contract, but also the public of the CITY OF BISMARCK will suffer damages extremely difficult to estimate.

## DIVISION 100 – GENERAL PROVISIONS

The parties recognize the delays, expense, and difficulties involved in proving the actual loss and damages suffered by the CITY and by the public of the CITY OF BISMARCK if any of the work is not completed on time.

The parties further recognize the CITY has made a reasonable endeavor to estimate the actual loss and damages which might be occasioned upon the CITY and the public of the CITY OF BISMARCK in the event of delay of completion of any of the work and that the CONTRACTOR was allowed input on this amount within five days prior to the bid opening.

Thus, both parties agree that the amounts of liquidated damages set forth herein to be assessed in the event of a delay in completion of any of the work are both reasonable in amount and reasonably related to the actual damages which the parties, through their reasonable endeavors, have estimated could occur upon delay in completion of any of the work.

Accordingly, instead of requiring any actual proof of damages in the event that the CONTRACTOR shall neglect, refuse, or fail to complete any work within the time specified in the contract, the CITY and the CONTRACTOR agree that, as liquidated damages for delay (and not as a penalty), the CONTRACTOR shall pay the CITY the amount required in the schedule set forth in this specification, the Project Proposal, Advertisement for Bids, or Special Provisions for each day that expires after the time specified in the contract that any of the work is not complete unless extensions are allowed pursuant to the terms of the contract.

Finally, the CITY and the CONTRACTOR specifically recognize that the recitals in this paragraph are conclusive presumptions, pursuant to Section 31-11-02 of the North Dakota Century Code. The decision of the ENGINEER for the non-completion of the work shall be binding upon both parties. Liquidated damages shall be based on the schedule below unless otherwise adjusted based on circumstances of the project as stated in the Advertisement or Special Provisions.

Liquidated damages shall be charged beginning the day after any interim, substantial, final or other completion date specified in the contract documents, or the day after any time extension granted by the ENGINEER. Liquidated damages shall be charged for each calendar day of delay until the project work items specified to be installed by the date(s) listed are complete.

Interim completion is a substantial completion date only for those work areas or scope items as defined in the project documents.

Substantial completion is defined as the improvement being operational and ready for use by the CITY OF BISMARCK. Water mains must be constructed, pressure tested, passing results achieved for both bacteriological tests, and conveying potable water; sewers must be constructed, tested, accepted, and conveying either storm water or sanitary sewer; streets must be constructed and open to traffic; and street lights and traffic signals must be installed, tested, and energized.

## DIVISION 100 – GENERAL PROVISIONS

The CITY will not assess liquidated damages during a period when the project is in an authorized state of suspension.

<u>Contract Amount</u>	<u>Damages Per Calendar Day</u>
\$0 to \$250,000	\$200
\$250,001 to \$500,000	\$300
\$500,001 to \$1,000,000	\$500
\$1,000,001 to \$2,500,000	\$1,000
\$2,500,001 to \$5,000,000	\$1,500
Over \$5,000,000	\$2,500

### **SECTION 107 – MEASUREMENT AND PAYMENT**

#### **107-1 GENERAL**

The quantities shown on the Plan sheets entitled "Approximate Quantities" are estimated quantities based on information available at the time of design. It is mutually understood that these quantities may change at the time of construction due to unforeseen conditions which may be encountered during construction. The Board of City Commissioners reserves the right to designate the amount of work to be completed.

The bid item list specifies the unit of measure for each contract item. Payment shall be made for the amount of work complete, in place, and accepted at unit prices specified in the contract as measured by the ENGINEER. Payment shall be full compensation for furnishing all materials, equipment, labor and incidentals required to complete the work as specified. Hauling and proper disposal of any materials or items shall be included in the unit price unless otherwise specified.

Unless otherwise specified as payment by plan quantity, the ENGINEER shall measure the actual quantity of accepted work for each contract item.

#### **107-2 ESTIMATES AND PAYMENTS**

The ENGINEER shall make a monthly approximate measurement of the work done to date and an estimate of the value of the same at the prices agreed upon in the contract. When directed by the ENGINEER, the CONTRACTOR shall measure the work completed and submit to the ENGINEER in duplicate copy form an estimate of the work completed to date and value of same at the prices agreed upon in the contract.

The ENGINEER shall retain 10 percent of the amount of each payment until 50 percent of all work in the contract documents, including change orders, has been completed and accepted by the ENGINEER. No further amount of retainage shall be withheld from payments after 50 percent of the contract has been completed unless the ENGINEER has on file any valid claims against the CONTRACTOR by the CITY OF BISMARCK or

## DIVISION 100 – GENERAL PROVISIONS

others. The ENGINEER may reduce the amount retained upon completion of 90 percent of all work in the contract documents and accepted by the ENGINEER. On completion and acceptance of a part of the work on which the price is stated separately in the Contract Documents, payment in full may be made, including retained percentages less authorized deductions. Retainage may be held until completion and acceptance of all punch-list items and submittals, as required under the contract.

Payment for materials in storage may be added to any monthly estimate. The CONTRACTOR must submit the materials invoice, and the materials must be stored on CITY lands or rights-of-way, at the site, or as directed by the ENGINEER to be eligible for payment. All materials not in storage as directed by the CITY shall be deducted from the materials invoice. No retainage will be deducted for materials stored as directed by the CITY.

**107-2.1 MATERIALS STORED.** Payment for materials in storage may be added to any monthly estimate for the invoiced cost of materials to be incorporated in the work. Materials must meet the requirements of the contract, plans and specifications. The following conditions must be met for payment of materials stored:

- a. The CONTRACTOR must submit the materials invoice.
- b. The CONTRACTOR must furnish the CITY legal title or lien waiver (free of liens or encumbrances of any kind) to the materials stored. Lien waivers shall be submitted as follows to meet this requirement:
  - i. A lien waiver from the supplier to the CONTRACTOR,
  - ii. A lien waiver from the subcontractor to the prime CONTRACTOR (when applicable), and
  - iii. A lien waiver from the prime contractor to the CITY.
- c. The materials must be stored on CITY lands or rights-of-way, at the site, or as directed by the ENGINEER. All materials not in storage as directed by the ENGINEER shall be deducted from the materials invoice.
- d. The CONTRACTOR must provide satisfactory evidence that the materials and transportation costs have been paid.
- e. The CONTRACTOR must provide satisfactory evidence that the materials are insured against loss by damage to or disappearance of such materials at any time prior to use in the work.

The transfer of title and the CITY's payment for stored materials shall in no way relieve the CONTRACTOR of their responsibility for furnishing and placing such materials in accordance with the contract, plans, and specifications.

In no case will the dollar amount or quantity paid for materials stored exceed the contract price or quantity for such materials or for the contract item in which the materials are intended to be used.

No materials stored payment will be made for stored living or perishable plant materials.

The CONTRACTOR shall bear all costs associated with providing all documentation required for payment of stored materials as per this section.

### 107-3 FINAL PAYMENT

After the work has been completed, the ENGINEER will prepare a final statement showing the quantities of each and every item of work performed by the CONTRACTOR. All estimates upon which previous payments have been based are partial estimates and are subject to correction in the final statement. The final statement showing the entire quantity and value of each and every item of work performed will be submitted to the CONTRACTOR for its approval before being processed by the CITY for payment.

**(a) Overpayment.** If the final statement shows that the total of all partial payments made exceeds the total amount due to the CONTRACTOR, the CONTRACTOR shall promptly refund to the CITY the amount of such overpayment. If such refund is not made, the CITY shall have the right to deduct the amount thereof from any moneys due to the same CONTRACTOR under any other contract, either present or future or pursue other means of repayment.

### 107-4 OIL PRICE ADJUSTMENT

The CONTRACTOR may request a bituminous seal oil price adjustment agreement for a project when seal coat is to be installed the following construction season. The agreement will only be enacted with an **increase or decrease** of seal oil prices exceeding 10%.

The request, along with invoices from the current year for the bituminous seal oil shall be provided within 21 days of the executed CITY agreement for the project. Payment for these oils used during the current construction season will be based on the unit prices bid for the project. The bid prices for these oils will be **increased or decreased the amount above or below the 10% increase or decrease** based on the difference between the current construction season oil prices and those of the following construction season. The annual adjustment will be based on the invoices for these oils submitted two weeks prior to the start of construction operations that following construction season.

### 107-5 FUEL COST ADJUSTMENT CLAUSE W/DOT ATTACHMENT

The fuel oil adjustment clause contained herein provides for a price adjustment in the form of payment to the CONTRACTOR or a rebate to the CITY for fluctuations in the cost of motor fuel (both diesel and gasoline) consumed in the performance of applicable construction work. The price adjustment provisions are applicable only to contract items if gasoline and/or diesel are used as the primary fuel in the production of the affected items. The price adjustment provisions are also applicable to these eligible pay items when the CITY adds extra work to the contract.

The provision will remain in effect throughout the duration of the contract. Enactment of the fuel oil price adjustment clause will only be considered when the **increase or decrease** in the price of motor fuel as defined herein exceeds 10 percent.

## DIVISION 100 – GENERAL PROVISIONS

The fuel oil adjustment clause is intended to reduce but not eliminate the cost effects of price uncertainty to the CONTRACTOR and the CITY for motor fuel used in the construction of this contract. It provides for sharing by the CITY in a portion of the CONTRACTOR's risk, which could result from unusual price fluctuations. The provision is not intended to compensate the CONTRACTOR for normal day-to-day fluctuations and seasonal changes or to serve as a guarantee of full compensation for motor fuel price fluctuations.

Motor and burner fuels may have cost adjustments made in accordance with NDDOT Special Provision Fuel Cost Adjustment Clause dated September 8, 2006. Substitute CITY OF BISMARCK for NDDOT as it applies.

The contract unit price shall be firm for the first month of the contract period. Thereafter, the CONTRACTOR may request a price adjustment (increase or decrease) at a minimum frequency of one month. A written request for a price adjustment must be submitted to the ENGINEER and must include justification for the proposed change.

The justification should establish a base line at the time of bidding or last approved price adjustment and current pricing. For example, a copy of an invoice for burner fuel at the time of bidding would establish the base line, and an invoice at the time of the request would indicate the increase or decrease.

The CITY will respond as follows:

- a. The request may be granted.
- b. More justification may be requested.
- c. The price paid may continue without change.

The baseline for Midwest Diesel Price shall be determined by U.S. Department of Energy weekly statistics, if it becomes a factor in justifying price increases based on material transport.

If a price adjustment is approved by the CITY, the date the adjustment will be effective along with the new unit prices will be included in the written response to the CONTRACTOR. Approval of any price adjustments renews the one month firm price period.

The CITY shall also be advised of and receive the benefit of any price decrease. The same notification and review process will apply to a decrease in cost.

## DIVISION 200

### EARTHWORK

#### SECTION 201 – CLEARING AND GRUBBING/MISCELLANEOUS REMOVALS

##### 201-1 DESCRIPTION

This item shall consist of clearing and grubbing, including the disposal of materials, for all areas within the construction limits designated on the plans or as directed by the ENGINEER.

Clearing and grubbing shall consist of clearing the ground surface of the designated areas of all trees, stumps, downed timber, logs, snags, brush, undergrowth, hedges, heavy growth of grass or weeds, fences, structures, debris, rubbish of any nature, natural obstructions, or such material which in the opinion of the ENGINEER is unsuitable for the foundation of pavements or other required structures. This shall also include the grubbing of stumps, roots, and foundations and the disposal from the project of all spoil materials resulting from clearing and grubbing.

##### 201-2 CONSTRUCTION REQUIREMENTS

**201-2.1 GENERAL.** The areas denoted on the plans to be cleared and grubbed under this item shall be staked on the ground by the ENGINEER. The clearing and grubbing shall be done at a satisfactory distance in advance of the grading operations.

Disposal of all spoil materials removed by the clearing and grubbing shall be done at an approved disposal area.

The removal of existing structures and utilities required to permit orderly progress of work shall be accomplished by local agencies, unless otherwise shown on the plans. Whenever a utility pole, pipeline, conduit, cable, sewer, roadway, or other utility is encountered and must be removed or relocated, the CONTRACTOR shall advise the ENGINEER who will notify the proper authority or Owner and attempt to secure prompt action.

**201-2.2 CLEARING AND GRUBBING.** In areas designated to be cleared and grubbed, all stumps, roots, buried logs, brush, grass, and other unsatisfactory materials shall be removed. In cases where such depths of embankments are to be made, all unsatisfactory materials shall be removed. Sound trees and stumps, except in a storm water embankment, may be cut off within six inches above the ground and allowed to remain. Roots and other projections over 1½ inches in diameter shall be grubbed out to a depth of at least 18 inches below the finished subgrade or slope elevation.

## SECTION 201 – CLEARING AND GRUBBING/MISCELLANEOUS REMOVALS

All holes remaining after the grubbing operation in embankment areas shall have the sides broken down to flatten out the slopes and shall be filled with acceptable material, dried or moistened, and properly compacted in layers to the density required in Section 202. The same construction procedure shall be applied to all holes remaining after grubbing in excavation areas where the depth of holes exceeds the depth of the proposed excavation.

Any buildings and miscellaneous structures that are shown on the plans to be removed shall be demolished or removed, and all materials therefrom shall be removed from the site. The remaining foundations, wells, cesspools, and all like structures shall be destroyed by breaking out or breaking down the materials of which the foundations, wells, cesspools, etc., are built and removing the footing and walls or as specified on the plans. Any broken concrete, blocks, or other objectionable material which cannot be used in backfill shall be removed and disposed of by the CONTRACTOR. The holes or openings shall be backfilled with acceptable material and properly compacted.

**201-2.3 TREE REMOVAL.** When the proposal indicates tree removal by individual unit basis, removal shall consist of cutting the tree down and immediate removal of the stump by routing or excavation to a point 16 inches below the ground line. The tree shall be disposed of properly.

All tree removal done within clearing and grubbing limits shall be done utilizing a CONTRACTOR licensed with the City of Bismarck's Forestry Department.

The debris associated with the stump removal shall be removed and replaced with compacted suitable material to within 4 inches of the finished surface. The CONTRACTOR shall place 4 inches of compacted topsoil, seed, and mulch the area. Removal of debris and placement and compaction of material and topsoil shall be incidental to the tree removal bid item. Seeding and Mulching shall be measured and paid by the square yard (SY) for the respective bid items.

**201-2.4 TREE ROOT CUTTING.** The CONTRACTOR shall be responsible for the prevention of damage to trees, shrubs, bushes, and hedges.

When tree roots are found larger than three inches in diameter during construction, the CONTRACTOR must contact the City of Bismarck's Forestry Department to determine if such roots shall be cut and/or if the tree shall be removed before continuing any further construction.

When the City Forester determines that the roots may be cut, all roots shall be cut cleanly to avoid jagged rough ends. A visual inspection of tree root cuts shall be made by the City Forester.

All roots greater than three inches in diameter shall be cut using a hand pruner, hand saw, power saw, or stump grinder.

## SECTION 201 – CLEARING AND GRUBBING/MISCELLANEOUS REMOVALS

**201-2.5 REPLACE TREE.** Tree replacement shall consist of furnishing and installing a freshly dug two inch diameter or larger, balled and burlapped tree which shall not show any signs of damage. All containers, wire, plastic, fabric, burlap, rope, string, twine, or any other extraneous material shall be removed from the root ball. Depth of the root ball is measured from the top of the root ball, which in all cases shall begin at the root flare. Soil above the root flare shall not be included in ball depth measurement and shall be removed. The planting hole shall be only as deep as needed, and the root flare shall be visible after planting.

The CONTRACTOR shall supply wood chip mulch. Individual trees shall be mulched with a six foot diameter circle of wood chip mulch four inches deep, leaving a 1 to 2 inch mulch-free area around the tree trunk. Staking shall consist of two stakes evenly spaced with a finished height of not less than 4 feet at installation. Tree straps placed around the tree trunk shall be a minimum of 1½ inches wide, and made of a soft material with a grommet at each end. Tree straps shall be placed at the lowest practical level on the trunk to maintain it upright. Lower trunk protection shall consist of a minimum four inch diameter corrugated plastic pipe, 12 inches in height, cut on one side for installation and removal. Care must be taken while applying to avoid injury to the bark.

The tree shall be warranted for one year from final acceptance of the project and shall be in satisfactory condition at the end of the warranty period.

**201-2.6 TREE PRUNING.** Crown raising pruning to allow for clearance of construction equipment.

All pruning shall be made in conformance with the latest version of ANSI A300 (Part 1) Pruning Standard. The CONTRACTOR is to inspect each tree at time of pruning for structural defects and/or potential hazards. Such defects or hazards must be reported to the City Forester or his agent.

No topping, pollarding, or heading back will be allowed unless specifically authorized by the City Forester.

Equipment that will damage the bark and cambium layer shall not be used on, or in, the tree. For example, the use of climbing spurs is not acceptable work practice for pruning operations on live trees.

All broken branches shall be removed.

All pruning shall be performed with consideration of the tree species' inherent growth (i.e., vase shaped, pyramidal, broad-oval, etc.). Improving and/or maintaining tree health is a critical consideration as well as clearance needs.

Sharp tools shall be used so clean cuts will be made at all times.

## SECTION 201 – CLEARING AND GRUBBING/MISCELLANEOUS REMOVALS

All cut limbs shall be removed from the crown upon completion of the pruning. All pruning including branches, chips, and rakings must be removed from the site and transported to the disposal site daily.

Driveways shall only be blocked when necessary for as short a period as possible. Vehicles and equipment may not be driven on boulevards and shall not enter upon any private property.

Minimal cuts shall be made to avoid construction damage to elm tree and other species susceptible to regional diseases between April 1st and October 1st.

Trees shall be pruned to provide:

10 feet of clearance over sidewalks, rights-of-way, and private property, including structures.

14 feet of clearance over street on residential and collector streets.

16 feet of clearance over street on arterial streets.

Live crown should not be reduced to less than 50 percent.

If, during the work, the CONTRACTOR determines that the tree possesses defects, which cause the tree to be structurally unsound, the CONTRACTOR shall notify the City Forester immediately. The City Forester shall make the final determination as to what action shall be taken.

A proposed tree listing will be provided prior to construction activities, but may not be 100% accurate. Each tree pruned is to be recorded with work date, current diameter, and additional comments as needed. Some trees may need extensive work, others very minor or no work. The CONTRACTOR will make the determination of what each tree needs based on specifications.

### **201-3 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107 and as follows:

**201-3.1 TREE REMOVAL.** When the proposal indicates measurement by individual unit basis, the trees shall be classed in accordance with the diameter size as measured at a point 54 inches above the ground level or at a designated height specified in the proposal. Trees measured at less than 2 inches shall be considered incidental to other bid items.

## **SECTION 202 - EXCAVATION AND EMBANKMENT**

### **202-1 DESCRIPTION**

This item shall consist of excavating, hauling, placement, disposal, and compaction of embankment material in accordance with these specifications and in conformity with the dimensions and typical sections shown on the plans and with the lines and grades established by the ENGINEER.

"Unstable," "Unsuitable," "Suitable," and "Unsatisfactory" soil or aggregate items shall be defined as follows:

#### **a. UNSATISFACTORY MATERIALS**

Unsatisfactory materials are those materials which have been determined to be unsuitable for subgrade foundations, including all unsuitable soils, rock, shale, hardpan, loose rock, boulders, concrete chunks or slabs, debris, tree roots, stumps and any other materials deemed unsatisfactory by the ENGINEER for use in subgrades or embankments. Unsatisfactory material shall become the CONTRACTOR's responsibility to dispose of.

All suitable material taken from excavations shall be used in the formation of embankment, subgrade, and for backfilling as indicated on the plans or as directed by the ENGINEER.

When the volume of the excavation exceeds that required to construct the embankments to the grades indicated, the excess shall be used to grade the areas of ultimate development or become the CONTRACTOR's property as directed by the ENGINEER. When the volume of excavation is not sufficient for constructing the fill to the grades indicated by the ENGINEER, at locations designated on the plans or the special provisions, the additional material required shall be identified by the ENGINEER and paid as "Borrow Excavation."

#### **b. UNSUITABLE SOILS**

Unsuitable soils are those soils which in their natural state are unsuitable for subgrade foundation due to a high organic content such as vegetation, matted roots, tree roots, peat, topsoil, or muck. Soils of these types are very susceptible to consolidation due to the decaying of this organic matter. Other unsuitable soils are those which contain decomposable debris and ashes. Frozen material will not be allowed. Unsuitable material shall become the CONTRACTOR's responsibility to dispose of.

The frozen condition of any soil or material shall not constitute a basis for a change of classification. Although frozen material shall not be allowed in the trench unless otherwise indicated, it shall be recompacted after it has thawed as directed by the ENGINEER.

**c. UNSTABLE SOILS**

Unstable soils are those soils which in their natural or existing condition require manipulation, aeration, or wetting and recompaction to obtain the required density for a suitable subgrade foundation. This condition is usually caused by too high of a moisture content for cohesive soils and too loose and/or dry for granular soils.

In the case of cohesive soils which in their natural state the moisture content exceeds optimum moisture, they begin to behave as plastic rather than solid. Scarifying and windrowing to a depth of 6 to 18 inches and recompacting the soil in 6-inch lifts to the required density/optimum moisture relationship will usually correct this condition. The other alternative is to subcut to prescribed depth and replace the cohesive material in accordance with specifications.

In the case of granular soils that are too loose, usually subcutting to a depth of 6 to 18 inches and replacing the soil in 6-inch lifts to the required density/optimum moisture relationship will correct this condition.

In either case, these soils should not have to be replaced with more desirable soils; it is merely that in their natural state they are unstable but not unsuitable for subgrade foundation.

**d. SUITABLE MATERIALS**

Suitable materials are those materials which have been determined to be satisfactory for subgrade foundations, including all stable or unstable soils and any other materials deemed satisfactory by the ENGINEER, for use in subgrades or embankments.

**202-2 CLASSIFICATION**

All material excavated shall be defined as "Unclassified Excavation" unless, in the proposal form, prices are requested and bids are taken for "Rock Excavation" and "Borrow Excavation."

"Unclassified Excavation" shall include all excavation performed under this item regardless of the material encountered.

"Rock Excavation," when provided in the proposal, shall include all solid rock in ledges, in bedded deposits, in unstratified masses, and in conglomerate deposits which are so firmly cemented they present all the characteristics of solid rock and which cannot be removed without drilling and blasting. All rock not allowed to be placed in the backfill or embankment, as directed by the ENGINEER, shall be considered "Rock Excavation."

"Borrow Excavation" shall consist of approved material required for the construction of embankments or for other portions of the work and shall be obtained from approved

## SECTION 202 - EXCAVATION AND EMBANKMENT

sources. Unless otherwise designated in the contract, the CONTRACTOR shall pay all costs involved.

The CONTRACTOR shall notify the ENGINEER in advance of opening any borrow areas so that the borrow material can be tested before being used. Sufficient time for testing the borrow shall be allowed.

### **202-3 CONSTRUCTION REQUIREMENTS**

**202-3.1 GENERAL.** The rough excavation shall be carried to the necessary depth to obtain the specific depth of subgrade compaction shown on the plans. Likewise, on embankments the depth of subgrade compaction shall be as shown on the plans. Should the CONTRACTOR through negligence or other fault excavate below the designated lines, the excavation shall be replaced with approved materials in an approved manner and condition at the CONTRACTOR's expense.

The ENGINEER shall have complete control over the excavation, moving, placing, and disposition of all material and shall determine the suitability of material to be placed in embankments. All material determined unsuitable shall be disposed of in waste areas or as directed by the ENGINEER. Topsoil shall not be used in fills or in subgrades but shall be handled and placed as directed.

The CONTRACTOR shall inform and satisfy itself as to the character, quantity, and distribution of all materials to be excavated. No payment will be made for any excavated material which is used for purposes other than those designated. All spoil areas shall be leveled to a uniform line and section and shall present a neat appearance before project acceptance. The surface elevation of spoil pile areas shall not extend above the surface elevation of adjacent or contiguous usable areas unless approved by the ENGINEER. All spoil piles approved by the ENGINEER shall be seeded and appropriate erosion control constructed.

The roadway right of way shall be graded as per Standard Detail 200-1.

The ENGINEER shall provide centerline stakes to prepare the grading. The CONTRACTOR shall be responsible for staking all other grades necessary to complete grading as per plans or specifications.

Those areas outside of the pavement areas in which the top layer of soil material becomes compacted due to hauling or to any other activity of the CONTRACTOR, shall be scarified and disked to a depth of 4 inches, as directed, to loosen and pulverize the soil.

If it is necessary to interrupt existing surface drainage, sewers, or underdrainage, conduits, utilities, or similar underground structures, or parts thereof, the CONTRACTOR shall be responsible for and shall take all necessary precautions to protect and preserve or provide temporary services. When such facilities are

## SECTION 202 - EXCAVATION AND EMBANKMENT

encountered, the CONTRACTOR shall notify the ENGINEER, who shall arrange for their removal, if necessary. The CONTRACTOR shall assume all costs to repair all damage to such facilities or structures which may result from operations of the CONTRACTOR during the period of the contract.

The CONTRACTOR shall engage an independent soils testing laboratory approved by the ENGINEER to determine the soil proctors for each soil condition to be encountered on the project and perform the required compaction testing to be determined by the ENGINEER.

The compaction control tests for this section are based on 1 individual compaction test per 200 cubic yards of fill or 750 square yards of area, whichever is greater. The CONTRACTOR shall be responsible for all retesting of failed tests. The time, locations, depths, and frequency of compaction testing shall be at the discretion of the ENGINEER during construction. Should it become necessary to conduct an additional number of initial compaction tests, over and above the number specified, the CITY OF BISMARCK shall be responsible for all costs associated with additional testing performed by an independent soils testing laboratory. The CONTRACTOR, however, will be required to assume the cost of all retesting of failed tests, regardless of the total number required during construction. Compaction testing to determine densities may be accomplished with a nuclear density testing apparatus, the sand cone method or drive cylinder. Should disputes arise concerning test results, they will be resolved by using only the sand cone method of testing.

Written reports of all test results shall be supplied to the ENGINEER and the CONTRACTOR by the testing laboratory as soon as possible.

Compaction control tests as stated above shall be incidental to the price bid for related bid items.

**202-3.2 EXCAVATION.** Excavation shall be performed as indicated on the contract plans to the lines, grades, and elevation shown or as directed by the ENGINEER, and shall be made so the requirements for formation of embankments can be followed. No excavation or stripping shall be started until the ENGINEER has taken cross-sectional elevations and measurements of the existing ground surface and has staked out the proposed work. All material encountered within the limits indicated shall be removed and disposed of as directed. During the process of excavation, the grade shall be maintained so that it will be well drained at all times. When directed, temporary drains and drainage ditches shall be installed to intercept or divert surface water which may affect the work.

If, at the time of excavation, it is not possible to place any material in its proper section of the permanent construction, it shall be stockpiled in approved areas for later use.

Rock, shale, hardpan, loose rock, boulders, or other material unsatisfactory for subgrades, streets, roads, shoulders, intermediate areas, or any areas intended for turfing shall be excavated to a minimum depth of 12 inches, or to the depth specified by

## SECTION 202 - EXCAVATION AND EMBANKMENT

the ENGINEER, below the contemplated surface of the subgrade or the designated grades. Muck, peat, topsoil, matted roots, tree roots, rock, grasses, or other yielding material, unsatisfactory for subgrade foundation, shall be removed to the depth specified to provide a satisfactory foundation. Unsatisfactory materials shall be disposed of at locations designated by the ENGINEER. All material so excavated shall be paid for at the unit price bid per cubic yard for "Unclassified Excavation" or for "Rock Excavation," as the case may be, when the classification for the last 2 items is provided in the proposal. The portion so excavated shall be refilled with suitable selected material as specified, obtained from the grading operations or borrow area, and thoroughly compacted by rolling. The necessary refilling will constitute a part of the embankment. Where rock cuts are made and refilled with selected material or where trenching out is done to provide for a course of pavement, the depths thus created shall be ditched at frequent intervals to provide drainage.

The CONTRACTOR shall make the distribution as indicated on the plans. Widening or narrowing of the section and raising or lowering of the grade to avoid haul will not be permitted. The ENGINEER reserves the right to make minor adjustments or revisions in lines or grades, if found necessary, as the work progresses due to discrepancies in the plans or to obtain satisfactory construction.

Overbreak, including slides, is that portion of any material displaced or loosened beyond the finished work as planned or authorized by the ENGINEER. The ENGINEER, whose decision shall be final, shall determine if the displacement of such material was unavoidable. All overbreak shall be removed by the CONTRACTOR and disposed of as directed; however, payment will not be made for the removal and disposal of overbreak which the ENGINEER determines as avoidable. Unavoidable overbreak will be classified as "Unclassified Excavation."

The removal of existing structures and utilities required to permit the orderly progress of work will be accomplished by local agencies unless otherwise shown on the plans. All existing foundations or footings shall be excavated by the CONTRACTOR and the material disposed of as directed. All foundations thus removed shall be backfilled with suitable material and compacted.

In cut areas, the subgrade under areas to be paved shall be compacted to the depths and to the densities and moisture as shown on the plans or as specified in the specifications, or when not otherwise shown or specified, to a minimum depth of 6 inches and to a density of not less than 90 percent of the maximum dry density with a moisture content falling within plus or minus 3 percentage points of optimum moisture as determined by the compaction control tests specified in ASTM D1557. Any unsuitable materials encountered shall be removed and paid for as specified.

No payment or measurement for payment will be made for suitable materials removed, manipulated, and replaced in order to obtain density. Any removal, manipulation, aeration, replacement, and recompaction of suitable materials necessary to obtain the required density shall be considered as incidental to the excavation and embankment

## SECTION 202 - EXCAVATION AND EMBANKMENT

operations and shall be performed by the CONTRACTOR at no additional cost to the project.

Stones or rock fragments larger than 2 inches in their greatest dimension will not be permitted in the top 6 inches of the subgrade. The finished grading operations conforming to the typical cross section shall be completed and maintained at least 400 feet (1 block) ahead of the paving operations.

In cut areas, all loose or protruding rocks on the back slopes shall be barred loose or otherwise removed to line or finished grade of slope. All cut-and-fill slopes shall be uniformly dressed to the slope, cross section, and alignment shown on the plans or as directed by the ENGINEER.

**202-3.3 BORROW EXCAVATION.** When provided for in the proposal, borrow excavation shall consist of excavation made from borrow areas outside the plan grading limits. Upon completion of borrow operations, the borrow area shall be finished to a neat and uniform grade acceptable to the ENGINEER.

The borrow excavation shall be handled and placed as specified in these specifications for excavation and embankment.

**202-3.4 DITCH EXCAVATION.** Ditch excavation shall consist of excavating for drainage ditches such as intercepting, inlet or outlet, temporary levee construction, or any other type as designated or as shown on the plans. The work shall be performed in the proper sequence with the other construction. The location of all ditches or levees shall be established on the ground. All satisfactory material shall be placed in fills; unsatisfactory material shall be placed in spoil areas as shown on the plans or removed from the project area as directed by the ENGINEER. Waste or surplus material shall be disposed of as shown on the plans or as directed by the ENGINEER. Intercepting ditches shall be constructed prior to the start of adjacent excavation operation. All necessary handwork shall be performed to secure a finish true to line, elevation, and cross section, as designated.

Ditches constructed on the project shall be maintained to the required cross section and shall be kept free from debris or obstructions until the project is accepted. Where necessary, sufficient openings shall be provided through spoil banks to permit drainage from adjacent lands. All ditches constructed shall be secured with erosion and sediment control as shown on the plans, or as directed by the ENGINEER.

Unless otherwise specified, no separate payment will be made for ditch excavation other than for the material removed which will be paid for at the unit price for "Unclassified Excavation" or "Rock Excavation," as the case may be, if the proposal includes classification of these excavated materials.

**202-3.5 EMBANKMENT FOUNDATION PREPARATION.** Immediately prior to the placing of the fill materials, the entire area upon which the embankment is to be placed, except where limited by rock, shall be scarified and broken by means of a disc harrow

## SECTION 202 - EXCAVATION AND EMBANKMENT

or plow or other approved equipment to a minimum depth of 6 inches or as specified by the ENGINEER. Scarifying shall be done approximately parallel to the axis of the fill. All roots, debris, large stones, or objectionable material that would cause interference with the compaction of the foundation or fill shall be removed from the area and disposed of as directed by the ENGINEER. A thin layer (approximately 3 inches) of all the fill material shall be spread over the scarified foundation and the whole area compacted as required in the specifications. Payment will be made for the material excavated for the embankment foundation at the unit price bid for "Unclassified Excavation."

Where embankments are to be placed on natural slopes steeper than 3-to-1, horizontal benches shall be constructed as shown on the plans or as directed by the ENGINEER. Payment will be made for the material excavated on the embankment slopes at the unit price bid for "Unclassified Excavation."

**202-3.6 STRIPPING.** All vegetation such as brush, heavy sods, heavy growth of grass, peat, topsoil, rubbish, tree roots and stumps, and any other unsuitable material within the area upon which embankment is to be placed shall be stripped or otherwise removed before the embankment is started, and in no case shall such objectionable material be allowed in or under the embankment. No direct payment will be made for stripping. The yardage removed and disposed of shall be paid for at the unit price bid per cubic yard for "Unclassified Excavation."

**202-3.7 FORMATION OF EMBANKMENTS.** Embankments shall be formed of satisfactory materials placed in successive horizontal layers of not more than 8 inches in loose depth for the full width of the cross section.

The grading operations shall be conducted and the various soil strata shall be placed to produce a soil structure as shown on the typical cross section, or as directed by the ENGINEER. All materials placed in the embankment shall be reasonably free of organic matter such as leaves, grass, tree roots, peat, and other objectionable material. Soil, granular material, shale, and any other material permitted for use in embankment shall be spread in successive layers as specified.

Earthwork operations shall be suspended at any time when satisfactory results cannot be obtained because of rain, freezing weather, or other unsatisfactory conditions of the field. The CONTRACTOR shall drag, blade, compact, or slope the embankment to provide proper surface drainage.

The material in the layers shall be of the proper moisture content before rolling to obtain the prescribed compaction. Wetting or drying of the material and manipulation when necessary to secure a uniform moisture content throughout the layer shall be required. Should the material be too wet to permit proper compaction or rolling, all work on all portions of the embankment thus affected shall be delayed until the material has dried to the required moisture content. Sprinkling shall be done with approved equipment that will sufficiently distribute the water. Sufficient equipment to furnish the required water shall be available at all times. Samples of all embankment materials for testing, both

## SECTION 202 - EXCAVATION AND EMBANKMENT

before and after placement and compaction, shall be completed as per Section 202. Based on these test results, corrections, adjustments, and modifications of methods, materials, and moisture content will be made to construct the embankment.

For all areas within the CITY right-of-way, the embankment shall be compacted to a density of not less than 90 percent of the maximum dry density with a moisture content falling within plus or minus 3 percentage points of the optimum moisture as determined by ASTM D1557 (modified proctor). On all areas outside of the pavement, curb and gutter, and sidewalk areas, no compaction will be required on the top 4 inches. On all areas outside of the right-of-way, the embankment shall be compacted to a density of not less than 85 percent of the maximum dry density with a moisture content falling within plus or minus 3 percentage points of the optimum moisture as determined by ASTM D1557. Any areas inaccessible to a roller shall be consolidated and compacted by mechanical tampers.

In the construction of embankments, starting layers shall be placed in the deepest portion of the fill. As placement progresses, layers shall be constructed approximately parallel to the finished pavement grade line.

When rock and other embankment material are excavated at approximately the same time, all rock shall be stockpiled and removed by the CONTRACTOR. Stones or fragmented rock larger than 2 inches in their greatest dimension will not be allowed in the top 6 inches of the subgrade. Rocks or boulders shall not be disposed of outside of the excavation or embankment areas, except at places and in the manner designated by the ENGINEER.

Frozen material shall not be placed in the embankment nor shall embankment be placed upon frozen material.

The CONTRACTOR shall be responsible for the stability of all embankments made under the contract and shall replace any portion which, in the opinion of the ENGINEER, has become displaced due to carelessness or negligence on the part of the CONTRACTOR. All embankments constructed shall be secured with erosion and sediment control as shown on plans.

There will be no separate measurement or payment for compacted embankment. All costs incidental to placing in layers, compacting, diking, watering, mixing, sloping, and other necessary operations of the embankments will be included in the unit price bid for excavation, borrow, or related bid items.

When stockpiling of excavated material and later rehandling of such material is directed by the ENGINEER in order to produce the specified subgrade structure, the material shall be paid for at the unit price bid per cubic yard (cy) for "Unclassified Excavation."

**202-3.8 EQUIPMENT.** The CONTRACTOR may use any type of earthmoving, compaction, and watering equipment, provided the equipment is in a satisfactory condition and is of such capacity that the construction schedule can be maintained as

## SECTION 202 - EXCAVATION AND EMBANKMENT

planned by the CONTRACTOR, and as approved by the ENGINEER, in accordance with the total days or working days bid for the construction. The CONTRACTOR shall furnish, operate, and maintain such equipment as is necessary to control uniform compaction, layers, section, and smoothness of grade.

**202-3.9 PREPARATION AND PROTECTION OF THE TOP OF THE SUBGRADE.** On areas to be paved, the specified depth in cut areas and the top of embankment shall be compacted to the density/moisture specified. The typical section for areas to be paved shall be graded such that the roadway is graded as per Standard Plate 200-1. When completed, the surface shall be true to the lines, grades, and cross section shown on the plans, or as directed by the ENGINEER. After all drains, structures, ducts, and other underground appurtenances along the edges or under the pavement have been completed, the subgrade shall be compacted to the depth specified at not less than 90 percent of the maximum dry density with a moisture content falling within plus or a minus 3 percent at the optimum moisture as determined by ASTM D1557. Any irregularities or depressions that develop during rolling shall be corrected by loosening the material at these places and adding, removing, or replacing material until the surface is smooth and uniform. Any portion of the area which is not accessible to a roller shall be compacted in lifts not to exceed 6-inches to the required density/moisture tolerances by approved mechanical tampers. The material shall be sprinkled with water during rolling or tamping, when directed by the ENGINEER.

All soft and yielding material, and material which will not compact readily when rolled or tamped, shall be removed as directed by the ENGINEER and replaced with suitable material. After grading operations are complete, all loose stones larger than 2-inches in their greatest dimension shall be removed from the surface of all proposed graded paving areas and disposed of as directed by the ENGINEER.

At all times, the top of the subgrade shall be kept in such condition that it will drain readily and effectively. In handling materials, tools, and equipment, the CONTRACTOR shall protect the subgrade from damage by laying planks when directed and shall be reshaped and recompacted to required density and moisture tolerances. Storage or stockpiling of materials on the top of the subgrade will not be permitted. Until the subgrade has been checked and approved, no aggregate base, surface course, or pavement shall be laid thereon.

**202-3.10 HAUL.** No payment will be made separately or directly for haul on any part of the work. All hauling will be considered a necessary and incidental part of the work, and its cost shall be considered by the CONTRACTOR and included in the unit price bid for the pay items of work involved.

**202-3.11 TOLERANCES.** The ENGINEER shall verify that finished grading of roadway is within 0.05 feet below to 0.15 feet above the final subgrade elevation specified, and the average grading of any 500 lineal foot section of roadway shall be within 0.1 foot above the final subgrade elevation specified.

## SECTION 202 - EXCAVATION AND EMBANKMENT

The top of the subgrade shall be of such smoothness that, when tested with a 10-foot straightedge applied parallel and at right angles to the centerline, it shall not show any deviation in excess of .10 feet.

In areas to be turfed under the project or in the future, outside the sidewalk, curb and gutter, and pavement limits, the surface shall be of such smoothness that it will not vary more than 0.10 feet from true grade as established in plans or by grade hubs.

The ENGINEER shall verify that finished grading of stormwater ponds shall be within plus/minus 0.25 foot of design grade.

If grading does not meet tolerance, the CONTRACTOR shall be responsible for regrading to meet tolerance.

### **202-4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107 and as follows:

**202-4.1 UNCLASSIFIED EXCAVATION.** Unclassified Excavation shall be measured in its original position by the method of average end areas of materials acceptably excavated and stripped as specified. Measurements shall not include the yardage of material excavated without authorization beyond normal slope lines, or the yardage of material used for purposes other than those directed. The plans shall state an assumed shrinkage factor to be used to compute embankment volume placed using "Unclassified Excavation."

**202-4.2 ROCK EXCAVATION.** All rock found in the excavation and not allowed to be placed in the backfill or embankment shall be classified as Rock Excavation and disposed of by the CONTRACTOR, or as directed by the ENGINEER.

The CONTRACTOR shall place all rocks not allowed to be placed in the backfill or embankment and less than 1 cubic yard in a pile to be measured by the ENGINEER. The total volume of the stockpile shall be reduced by 25 percent to account for voids in the rock stockpile.

All rock greater than 1 cubic yard shall be individually measured by the ENGINEER.

**202-4.3 BORROW EXCAVATION.** Borrow Excavation shall be measured in its original position. Borrow Excavation in its original position shall include an assumed shrinkage factor to be used to compute embankment volume placed. Borrow Excavation in a stockpile shall not include an allowance for shrinkage.

## **SECTION 203 – WATERING**

### **203-1 DESCRIPTION**

This item shall consist of applying CITY supplied water required in the compaction of embankments, subgrades, aggregate bases, AC base courses, and for other purposes in accordance with the requirements of these specifications, or as directed by the ENGINEER.

This item does not apply to any water required by the CONTRACTOR to meet backfill density requirements in trenching operations or required for establishment of seeding and/or sodding; water required for such operations shall be incidental to other bid items.

### **203-2 CONSTRUCTION REQUIREMENTS**

Water, when required, shall be applied at the locations, in the amounts, and during the hours, including nights, as approved by the ENGINEER. An adequate water supply shall be provided by the CITY OF BISMARCK. The equipment supplied and used by the CONTRACTOR for watering shall be of ample capacity and of such design as to assure uniform application of water in the amounts directed by the ENGINEER.

The CONTRACTOR shall furnish all fittings, hoses, and equipment used in the loading of CITY supplied water. If a water hydrant is used for furnishing water, the CONTRACTOR shall furnish a gate-type control valve, approved by the ENGINEER, to control water flow. The hydrant valve shall be fully opened and under no circumstances will the hydrant valve be used for water flow control. The CONTRACTOR shall apply for a hydrant meter supplied and installed by the City of Bismarck Public Works Department and shall pay all installation and usage fees unless waived by the contract documents.

### **203-3 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107 and as follows:

**203-3.1 WATERING.** Watering shall be measured in the vehicle at the point of delivery or by a metered invoice and supplied by the City of Bismarck Public Works Department. Each project shall be metered independently unless approved prior to project by the ENGINEER.

## **SECTION 204 – SUBGRADE PREPARATION**

### **204-1 DESCRIPTION**

This work shall consist of scarifying, shaping, compacting, and maintaining the subgrade prior to construction of an aggregate base, AC base course, or surface course and shall include excavation and/or shifting of materials resulting from rough grading, trenching, or other prior construction activities. Subgrade preparation shall include all work to the depths specified on the plans or in the special provisions. When subgrade preparation depths are not specified, the depth shall be assumed to be a minimum of 6-inches below the surface of the finished subgrade.

Prior to subgrade preparation, the ENGINEER shall verify the grading is within tolerance specified in Section 202. Work shall not begin on the subgrade preparation until the ENGINEER has approved that the grading has met the tolerances.

"Unstable," "Unsuitable," "Suitable," and "Unsatisfactory" soil or aggregate items are referred to in Section 202.

### **204-2 CONSTRUCTION REQUIREMENTS**

**204-2.1 GENERAL.** When required to achieve compaction requirements, prior to placing any of the subsequent materials, the entire subgrade surface shall be scarified to a specified depth of not less than 6-inches and meet required moisture and compaction requirements. Excess suitable excavated material shall be stockpiled and reused whenever possible in the project. Stockpiled material which is reused shall be measured in its final section and paid for as "Unclassified Excavation."

When subgrade preparation without scarification is required to achieve compaction requirements, this item will be paid for under "Subgrade Preparation (0 depth)."

Excavation of material for curb and gutter, or base course installation shall be measured by the cubic yard (CY) and paid for at the unit price bid for "Unclassified Excavation" complete and accepted by the ENGINEER.

Excavation and hauling of material from one point to another point on the roadbed or city rights-of-way to adjust the grade line and stockpiling excess material, if any, adjacent to the project shall be considered incidental to the "Subgrade Preparation" bid items.

All rocks larger than 4 inches in size and other unsuitable material shall be removed and replaced with suitable material. Any portions of the subgrade not easily accessible to machine operations, such as valley gutters, manholes, gate valves, and electrical lines shall be brought to the proper elevation and compacted by methods approved by the ENGINEER.

## SECTION 204 – SUBGRADE PREPARATION

During the course of preparing the subgrade, and until the curb and gutter and pavement courses have been constructed, it shall be the CONTRACTOR's responsibility to protect the subgrade against, and repair any damage caused by, adverse weather, public traffic, and the CONTRACTOR's operations. The subgrade shall at all times be completed for a sufficient distance ahead of hauling and spreading base or surface material to allow adequate opportunity for inspection. No materials shall be placed on the subgrade until it has been checked and approved by the ENGINEER.

**204-2.2 COMPACTION.** The subgrade shall be compacted by approved compaction equipment. Approved compaction equipment shall include sheepsfoot rollers, pneumatic packers, mechanical packers, mechanical rammers, and vibratory equipment. Subgrade preparation depths specified on the plans or special provisions or the minimum 6-inches required below the surface of the finished subgrade shall be compacted to 90 percent of maximum dry density as determined by ASTM D1557 with a moisture content falling within plus or minus 3 percentage points of the optimum moisture content as determined by said testing method. The surface after compaction shall be true to line, grade, and cross section.

Before preparations begin for application of a surface treatment or for a surface course, the CONTRACTOR shall proof roll the subgrade, including the curb line, under the supervision of the ENGINEER. The proof roll shall be performed with a minimum gross weight of 44,000 lbs. on a tandem axle truck with four tires per rear axle. Any failing areas in the subgrade shall be the responsibility of the CONTRACTOR to remove and replace, at the discretion of the ENGINEER.

The CONTRACTOR shall then engage an independent soils testing laboratory, approved by the ENGINEER, to determine the soil proctors and perform the required compaction testing to be determined by the ENGINEER.

The compaction control tests for this section are based on one individual compaction test per 750 square yards of area. The CONTRACTOR shall be responsible for all retesting of failed tests and a proctor determination to represent each soil condition to be encountered on the project. The locations and depths of compaction testing shall be at the discretion of the ENGINEER during construction. Should it become necessary to require an additional number of initial compaction tests, over and above the number specified for bidding purposes, the City of Bismarck shall be responsible for all costs associated with additional testing performed by an independent testing laboratory. The CONTRACTOR, however, will be required to assume the cost of all retesting of failed tests regardless of the total number required during construction.

Compaction testing to determine densities may be accomplished with a nuclear density testing apparatus and/or the sand cone method. Should disputes arise concerning test results, they will be resolved by using the sand cone method of testing.

Written reports of all test results shall be supplied to the ENGINEER and the CONTRACTOR by the testing laboratory as soon as possible.

## SECTION 204 – SUBGRADE PREPARATION

Compaction control tests as stated above shall be incidental to the unit price bid for related bid items.

No payment or measurement for payment will be made for suitable materials removed, manipulated, and replaced to obtain density in the specified depth of subgrade preparation. The moisture content of the subgrade materials shall fall within the range of plus or minus 4 percentage points of the optimum moisture content before any attempt is made to obtain the specified density. Any removal, manipulation, aeration, replacement, watering, and recompaction of suitable or unstable materials necessary to obtain the required density shall be considered as incidental to the subgrade preparation operation and shall be performed by the CONTRACTOR at no additional cost to the project.

If the desired compaction cannot be obtained by manipulation, wetting, or drying of the specified depth of the subgrade because the material is found to be "Unsuitable" or "Unsatisfactory," as defined in Section 202, or when the ENGINEER directs manipulation, wetting, or drying below the specified subgrade preparation depth, or when materials below the specified subgrade preparation depth must be removed because they are found to be "Unsuitable," or "Unsatisfactory," thus hampering subgrade operations, this work will be paid for in accordance with Section 104 of said construction specifications unless a "Subcut Excavation" item is included as a bid item on the proposal for the particular unit of the project.

If the instability of suitable materials below the specified subgrade preparation depth is a result of excessive moisture from rains, surface runoff, or frost action, the ENGINEER reserves the right to suspend the work to allow the materials to recover strength or to agree upon another method to use without any liability for the costs that may be claimed by the CONTRACTOR due to the suspension of work. Extension of time, however, will be granted in this case.

**204-2.3 TOLERANCES.** In those areas upon which an aggregate base or pavement is to be placed, the top of the subgrade shall be of such smoothness that, when tested with a 16-foot straightedge applied parallel and at right angles to the centerline, it shall not show any deviation in excess of 1/2 inch, or shall not be more than 0.05 of a foot from true grade established by grade hubs or pins.

The CONTRACTOR shall perform all surveying required to prepare the subgrade, to the tolerances specified, incidental to other bid items. The CONTRACTOR shall place a survey stake at the crown line on 50-foot intervals on all streets at the elevation approved by the ENGINEER. Additional staking may be required on sharp vertical and horizontal curves and at intersections and valley gutters as determined by the ENGINEER. The CONTRACTOR may use GPS equipment in lieu of staking for required surveying.

Staking shall not be the responsibility of the CONTRACTOR for curb and gutter construction.

## SECTION 204 – SUBGRADE PREPARATION

### **204-3 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107.

## **SECTION 205 – EROSION AND SEDIMENT CONTROL**

### **205-1 DESCRIPTION**

The CONTRACTOR shall be responsible for installing, maintaining, replacing, and removing all of the erosion and sediment control measures existing, as shown on the plans, or as deemed necessary by the ENGINEER, to effectively control pollution of waterways and sedimentation onto adjacent properties or into any downstream drainage facilities. Installation shall be done in accordance with the North Dakota Department of Environmental Quality, North Dakota Department of Transportation or plan details.

CONTRACTOR shall have a copy of the SWPPP, copy of the general permit, and inspection records on-site or at a location immediately available at the construction site at all times.

The CONTRACTOR shall be responsible for constructing and maintaining erosion control measures to prevent silt and loose materials such as chips, millings, etc., from entering ditches, gutter or inlets. Additionally, the CONTRACTOR shall apply for a Large Site Construction Stormwater Management Permit (CSMP) with the City of Bismarck Department of Public Works. No City permit fees for the erosion control will be required of the CONTRACTOR for a City-bid project. The Large Site CSMP permit application is available on the City of Bismarck website.

The CONTRACTOR shall abide by the provisions of the CSMP. Any tracking or sedimentation shall be removed and disposed of on a regular basis, incidental to other bid items. Stockpiles shall not be left on streets overnight. All work associated with installing and maintaining the erosion control shall be considered incidental to other bid items.

Erosion and sediment control measures shall be sufficient to contain sediments within the construction limits. If any excavation or embankment material does flow onto adjacent properties or downstream, the CONTRACTOR shall immediately rectify the problem and repair any damages.

Any failure of the erosion and sedimentation control measures shall be repaired within 48 hours of the runoff event, along with any erosion damages, at the CONTRACTOR's expense. The CONTRACTOR shall be required to maintain erosion and sediment control installations until such time as the project is accepted as complete by the ENGINEER, thence notifying and forwarding the responsibility to maintain the erosion and sediment control measures over to the next CONTRACTOR, developer, or builder/owner.

The CONTRACTOR may request additional compensation for extra clean up or erosion control items, in the event two or more rainfalls occur within 48 hours which overwhelm

## SECTION 205 – EROSION AND SEDIMENT CONTROL

the normally expected and approved control features causing excessive failures and/or erosion repairs, as directed by the ENGINEER.

If directed by the ENGINEER, the CONTRACTOR shall remove and dispose of erosion control items before the end of the warranty period. Cleanup shall be according to Section 104. All removal and cleanup items shall be considered incidental to other bid items.

**205-1.1 PROTECTION OF WATER RESOURCES.** The CONTRACTOR shall dispose of all fuels, lubricants, and other organic or inorganic wastes at locations approved by regulatory agencies. Fueling, lubricating, and overhauling of all equipment shall be accomplished at locations, and in such a manner, that contaminants can be controlled and disposed of without polluting surface or subsurface waters.

Surface drainage from cuts and fills within the project limits, whether or not complete, and from borrow and waste disposal areas, shall be held in suitable sedimentation ponds or the site shall be graded to control erosion within acceptable limits. Temporary erosion and sediment control measures such as berms, dikes, drains, silt fences, bales, wattles, fabrics, and sedimentation basins, if required to meet the above standards, shall be provided and maintained until permanent drainage and erosion control facilities are complete and operative.

The CONTRACTOR shall be required to maintain all excavations, embankments, stockpiles, haul roads, plant sites, waste areas, borrow areas, and all other work areas to be free from dust which would cause a hazard or nuisance to others. The CONTRACTOR must have sufficient, competent equipment on the job to control dust. Dust control will be performed as the work proceeds and whenever a dust nuisance or hazard occurs, or as directed by the ENGINEER.

The CONTRACTOR shall maintain all facilities constructed for pollution control for as long as the operations creating the particular pollutant are being carried out or until the materials of concern become stabilized to the extent that pollution is no longer being created.

### 205-2 MATERIALS

**205-2.1 SILT FENCE WITH WIRE BACKING.** Silt fence fabric shall conform to AASHTO M288 silt fence specification. Filter fabric shall be composed of fibers consisting of long chain synthetic polymers composed of at least 95 percent by weight of polyolefins, polyesters, or polyamides. The fibers shall be formed into a network such that the filaments or yarns retain dimensional stability relative to each other. The filter fabric shall be free of any treatment or coating which might adversely alter its physical properties after installation. The fabric shall be free of defects or flaws that affect its physical and/or filtering properties. The fabric shall have a minimum width of 36 inches. The filter fabric shall be furnished with suitable wrapping for protection against moisture and extended ultraviolet exposure prior to placement. Backing for a

SECTION 205 – EROSION AND SEDIMENT CONTROL

filter fabric silt fence shall consist of steel wire fence fabric. A woven wire fence shall conform to ASTM A116 Class 1 zinc coating for wire. The woven wire support fence shall be at least 32 inches high with a maximum opening size of 6 inches by 6 inches. The wire shall be a minimum of 14-gauge grade 60.

**205-2.2 POSTS.** Either wood or steel posts shall be used. Wood posts shall be treated (penta or green treated) and shall be a minimum of five feet long with minimum dimensions of 2 inches in diameter for round posts or 1½ by 1½ inches for rectangular posts. Steel posts shall be a minimum of 5 feet long, weigh a minimum of 1.3 pounds per square foot, and have projections to aid in fastening the wire or fabric. Steel posts shall also have a metal plate welded near the bottom such that when the post is driven to the proper depth, the plate will be below the ground level for added stability.

**205-2.3 WEIGHTED FIBER ROLL.** Weighted fiber roll shall be a photodegradable, extruded netting tube filled with wood curled excelsior and a weighted inner core. The roll diameter shall be 6 inches and the lengths shall be as required. The weight shall be a minimum of 8½ pounds per foot. An adequate number of weighted fiber rolls shall be placed around an inlet to provide complete protection.

**205-2.4 EROSION CONTROL BLANKET.** The erosion control blanket (ECB) shall be of organic biodegradable mulch material such as straw, wood curled excelsior, coconut fiber, or any combination of these materials. The ECB shall have a consistent thickness of mulch material evenly distributed over the entire area. The ECB materials must be secured on at least one side with netting. The netting must be of photodegradable polypropylene or other plastic material fused to the strand intersections. The ECB shall be a minimum width of 48 inches and shall be weed and pest free.

- A. **Wood Excelsior Blanket.** The wood excelsior blanket shall consist of a machine-produced blanket of cured wood excelsior in which 80 percent of the fibers are six inches or longer. The wood excelsior blanket shall be smolder-resistant without using additives.
- B. **Straw Blanket.** The straw blanket shall consist of a machine-produced, 100 percent weed-free, agricultural straw, certified by an accredited agency, in which 80 percent of the fibers are three inches or longer.
- C. **Straw and Coconut Blanket.** The straw and coconut blanket shall consist of a machine-produced blanket of 70 percent straw and 30 percent coconut fibers by weight in which 80 percent of the fibers are three inches or longer.

**EROSION CONTROL BLANKET**

TYPE	ECB 1		ECB 2		ECB 3		ECB 4	
	Straw	Wood	Straw	Wood	Straw/Coconut	Wood	Coconut	Wood
Material	100% Straw	100% Excelsior Fibers	100% Straw	100% Excelsior Fibers	70% Straw and 30% Coconut Fibers	100% Excelsior Fibers	100% Coconut Fibers	100% Excelsior Fibers
Fiber Length 80% Must be Greater Than	3 inches	80%> 6 inches	3 inches	6 inches	3 inches	80%> 6 inches	3 inches	80%> 6 inches
Min Mass Per Unit Area ASTM D6475	0.5 lbs/sy	0.51 lbs/sy	0.5 lbs/sy	0.51 lbs/sy	0.5 lbs/sy	0.69 lbs/sy	0.5 lbs/sy	0.88 lbs/sy

## SECTION 205 – EROSION AND SEDIMENT CONTROL

Min Thickness ASTM D6525	0.25 inch	0.25 inch	0.25 inch	0.25 inch	0.25 inch	0.25 inch	0.25 inch	0.50 inch
Net Opening Minimum	0.5x0.5 inch	0.75x0.75 inch	0.5x0.5 inch	0.75x0.75 inch	0.5x0.5 inch	0.75x0.75 inch	0.6x0.6 inch	0.75x0.75 inch
Max Shear Stress @ 0.50 inches soil loss ASTM D6460	-	1.50 lbs/sy	1.50 lbs/sy	1.75 lbs/sy	1.75 lbs/sy	2.0 lbs/sy	2.25 lbs/sy	2.25 lbs/sy
Slope Gradient Application	≤3H:1V	<3H:1V - 2H:1V	≤2H:1V	2H:1V 1.5H:1V	≤1.5H:1V	≤1.5H:1V	≤1H:1V	≤1H:1V
Net Backing Type	Rapid Photodegradable Polypropylene		Polypropylene		Polypropylene		Black UV Stabilized Polypropylene	
Functional Longevity	≤ 3 months		≤ 12 months		12 to 24 months		> 24 months	
Min Machine Direction Tensile Strength ASTM D6818	50 lbs/ft		75 lbs/ft		100 lbs/ft		125 lbs/ft	

The information in this table has been derived from information obtained from the Erosion Control Technology Council. All values must be within (+/-)10 percent of the minimums shown on the table.

U-shaped wire staples or metal geotextile pins shall be used to anchor the blanket(s) to the ground surface. Wire staples shall be a minimum thickness of 8-gauge. Metal pins shall be at least 0.20-inch diameter steel with 1½-inch steel at the head of the pin. All anchors shall be between 6 to 18 inches long and have sufficient ground penetration to resist pulling out. Longer anchors may be required for loose soils. Heavier metal stakes may be required in rocky soils.

**205-2.5 BALE DITCH CHECKS.** Bale ditch checks shall be placed in ditches with slopes not exceeding six percent. Bale ditch checks shall be constructed of wheat straw, oat straw, prairie hay, or brome grass hay that is free of weeds declared noxious by the North Dakota State Board of Agriculture.

The stakes used to anchor the bales shall be made of hardwood material with the following minimum dimensions: 2 by 2 inches square (nominal) by 4 feet long.

Twine shall be used to bind the bales. The use of wire binding is prohibited because it does not biodegrade readily.

**205-2.6 ROCK CHECKS.** Rock checks shall be placed in ditches with slopes steeper than six percent. Rock gradations and size shall be as specified in the plans or by the ENGINEER.

**205-2.7 STRAW WATTLES, 9-INCH DIAMETER.** Straw wattles shall consist of rice or wheat straw fibers as filler within a containment netting. Filler shall be certified as weed-free. Fibers must have an average length greater than three inches and shall contain ultraviolet inhibitors. The strand thickness shall be no less than 0.030 inches, the knot thickness no less than 0.0555 inches, and the netting weight no less than 0.35 ounces per foot. The entire wattle unit shall be sufficiently durable to withstand weather, construction, and installation conditions for at least 3 months, including

## SECTION 205 – EROSION AND SEDIMENT CONTROL

multiple movements and reinstallations. Wattles shall have a 9-inch diameter (1-inch tolerance) and a minimum unit weight of 1.6 pounds per square foot. Wood posts of sufficient strength to withstand installation and weather shall be used for anchoring. Stakes shall be wooden, 1½ inches thick by 30 inches long.

**205-2.8 STRAW WATTLES, 12-INCH DIAMETER.** Wattles shall consist of rice or wheat straw fibers as filler within a containment netting. Filler shall be certified as weed-free. Fibers must have an average length greater than 3 inches and shall contain ultraviolet inhibitors. The strand thickness shall be no less than 0.035 inches, the knot thickness no less than 0.0555 inches, and the netting weight no less than 0.35 ounces per foot. The entire wattle unit shall be sufficiently durable to withstand weather, construction, and installation conditions for at least three months, including multiple movements and reinstallations. Wattles shall have a 12-inch diameter (1-inch tolerance) and a minimum unit weight of 3.75 pounds per linear foot. Wood posts of sufficient strength to withstand installation and weather shall be used for anchoring. Stakes shall be wooden, 1½ inches thick by 30 inches long.

**205-2.9 DRAINAGE STRUCTURE INLET FILTER.** The drainage structure inlet filter shall be Top Guard by ERTEC, EZ-Catch or EZ-Flo by Flo-Water, or approved equivalent. The inlet filter shall include an overflow feature designed to allow full flow of water into the structure if the filter is filled with sediment. The inlet filter shall have a minimum flow rate of 130 gallons per minute per square foot.

**205-2.10 CONCRETE EROSION CONTROL BLANKET.** Prefabricated concrete erosion control blanket shall be Creflex 40F. The concrete erosion control blanket shall be a minimum 40 pounds per square foot with 7-ounce geotextile fabric backing. Concrete used to fabricate the erosion control blanket shall have a compressive strength of 4,000 pounds per square inch.

**205-2.11 EROSION CONTROL BERM.** Inlet pipes shall be 6-inch PVC and coiled pipes shall be six inch perforated pipe. Wire and/or twine shall be used to tie the pipe coils together. Wooden stakes shall be used with a minimum length of 24 inches. Riprap shall consist of rocks with diameters of 9 to 12 inches placed on a woven fabric.

### 205-3 CONSTRUCTION REQUIREMENTS

**205-3.1 GENERAL.** The CONTRACTOR shall furnish all labor, materials, and services necessary for and incidental to the completion of all work as shown on the drawings and specified herein. All machinery and equipment owned or controlled by the CONTRACTOR shall be of sufficient size to meet the requirements of the work and shall produce satisfactory work. All work shall be subject to the inspection and approval of the ENGINEER. The CONTRACTOR shall employ at all times a sufficient force of workmen of such experience and ability that the work can be completed in a satisfactory and workmanlike manner.

**205-3.2 SILT FENCE WITH WIRE BACKING.** The CONTRACTOR shall be responsible to furnish and install silt fence with wire backing as directed by the ENGINEER to effectively control erosion and sedimentation. The CONTRACTOR shall install and maintain silt fence with wire backing by the end of the work day upon notification by the ENGINEER. The CONTRACTOR shall construct silt fences as presented in Standard Detail 205-3. The reuse of silt fence materials without prior approval by the ENGINEER will not be allowed.

The CONTRACTOR shall check the operation and maintenance of the silt fence each week and within 24 hours following rainfall events of 1/2 inch or more until final acceptance of the contract. Rainfall shall be measured on site. The CONTRACTOR shall be responsible for all maintenance to silt fences. Sediment shall be maintained in such a way that it does not exceed one-third of the silt fence height.

The CONTRACTOR shall remove silt fences as directed by the ENGINEER. This shall include the removal of wire backing, silt fence fabric, and all stakes. All sediment accumulation shall be removed and all excavations shall be backfilled and properly compacted. The site shall be graded to blend with the terrain, and all disturbed areas shall be seeded.

**205-3.3 WEIGHTED FIBER ROLL.** The CONTRACTOR shall be responsible to furnish and install weighted fiber rolls as directed by the ENGINEER to effectively control erosion and sedimentation. The CONTRACTOR shall install and maintain weighted fiber rolls by the end of the work day upon notification by the ENGINEER. Approximately 3 to 6 inches shall be left between the weighted fiber rolls and the inlet. The ends shall overlap 12 inches.

When silt is one-third the height of the roll, the CONTRACTOR shall remove and dispose of the silt and debris to allow the device to function properly. The CONTRACTOR shall inspect the operation and maintenance of the weighted fiber roll each week and within 24 hours following rainfall events of 1/2 inch or more until final acceptance of the contract, incidental to the price bid for "Weighted Fiber Roll." Rainfall shall be measured on site.

The CONTRACTOR shall remove fiber rolls as directed by the ENGINEER. Removal shall include any size of fiber roll and shall include removal of all stakes. All sediment accumulation shall be removed, and all excavations shall be backfilled and properly compacted. The site shall be graded to blend with the terrain, and all disturbed areas shall be seeded.

**205-3.4 EROSION CONTROL BLANKET.** The CONTRACTOR shall be responsible to furnish and install erosion control blankets as directed by the ENGINEER to effectively control erosion and sedimentation. The CONTRACTOR shall install and maintain erosion control blankets by the end of the work day upon notification by the ENGINEER.

The area to be covered shall be properly prepared and seeded before the blanket is applied. All rocks or clods over 1½ inches in diameter and all sticks and other foreign

## SECTION 205 – EROSION AND SEDIMENT CONTROL

material shall be removed. Blankets shall be rolled out in the direction of the flow. Blanket ends shall be overlapped by a minimum of one foot where additional rolls are needed. When implementing multiple blankets, upstream/upslope blankets shall overlap downstream/downslope blankets. Wire staples and metal pins shall be driven flush to the soil surface.

The CONTRACTOR shall inspect the operation and maintenance of the erosion control blankets each week and within 24 hours following rainfall events of 1/2 inch or more until final acceptance of the contract. Rainfall shall be measured on site. Blankets damaged by construction operations shall be repaired by the CONTRACTOR and at the CONTRACTOR's expense. The area shall be restored to the proper contour, seeded and fertilized, and re-covered with the same type of erosion control blanket as the one which was damaged.

The CONTRACTOR shall allow erosion control blankets to degrade naturally, unless otherwise specified in plans or by the ENGINEER.


**205-3.5 BALE DITCH CHECKS.** The CONTRACTOR shall furnish and install bale ditch checks as directed by the ENGINEER to effectively control erosion in channels or ditches with slopes not exceeding 6 percent. The CONTRACTOR shall install and maintain the bale ditch checks by the end of the work day upon notification by the ENGINEER.

Bale ditch checks shall be placed perpendicular to the flow line of the ditch. The ditch check shall extend far enough so that the ground level at the ends of the check is higher than the top of the lowest center bale. This prevents water from flowing around the check.

The following table provides bale ditch check spacing for given ditch grades.

### Ditch Check Spacing

Ditch Grade (percent)	Check Spacing (feet)
<1.0	200
2.0	98
3.0	66
4.0	49
5.0	39
6.0	10
>6.0	Do not use bales



Perpendicular to the ditch flow line, excavate a trench 6 inches deep and a bale's width wide. Extend the trench in a straight line along the entire length of the proposed ditch check. Place soil on the upstream side of the trench to save for later use. Place the bales in the trench, making sure they are butted tightly. Two stakes shall be driven

## SECTION 205 – EROSION AND SEDIMENT CONTROL

through each bale along the centerline of the ditch check, approximately 6 to 8 inches in from the bale ends. Stakes shall be driven a minimum of 18 inches into the ground.

Once all the bales have been installed and anchored, place the excavated soil against the upstream side of the check and compact it. The compacted soil shall be no more than 3 to 4 inches deep and shall extend upstream no more than 24 inches.

The CONTRACTOR shall inspect the operation and maintenance of bale ditch checks each week and within 24 hours following rainfall events of 1/2 inch or more until final acceptance of the contract. Rainfall shall be measured on site. The CONTRACTOR shall be responsible for all maintenance to bale ditch checks. Sediment shall be maintained in such a way that it does not exceed one-third of the bale height.

The CONTRACTOR shall remove bale ditch checks appropriately after all sediment-producing areas have been stabilized. All sediment accumulation at the barrier(s) shall be removed, and all excavations shall be backfilled and properly compacted. The site shall be graded to blend with the terrain, and all disturbed areas shall be seeded.

**205-3.6 ROCK DITCH CHECKS.** The CONTRACTOR shall furnish and install rock ditch checks as directed by the ENGINEER to effectively control erosion in channels or ditches with slopes steeper than 6 percent. The CONTRACTOR shall install and maintain the rock ditch checks by the end of the work day upon notification by the ENGINEER.

Rock ditch checks shall be placed perpendicular to the flow line of the ditch. The rock ditch check shall extend far enough that the ground level at the ends of the check is higher than the lowest point on the crest of the check. This prevents water from flowing around the check. The ditch check shall be 18 to 24 inches high with side slopes not steeper than 1:1.

The following table provides rock ditch check spacing for given ditch grades.

Rock Ditch Check Spacing	
Ditch Grade (Percent)	Check Spacing (Feet)
4.0	75
5.0	60
6.0	50
7.0	45
8.0	35
9.0	33
10.0	30

The CONTRACTOR shall inspect the operation and maintenance of rock ditch checks each week and within 24 hours following rainfall events of 1/2 inch or more until final acceptance of the contract. Rainfall shall be measured on site. The CONTRACTOR

## SECTION 205 – EROSION AND SEDIMENT CONTROL

shall be responsible for all maintenance to rock ditch checks. Sediment shall be maintained in such a way that it does not exceed one-third of the rock height.

The CONTRACTOR shall remove rock ditch checks upon stabilization of the site. All sediment accumulated at the barrier(s) shall be removed, and all excavations shall be backfilled and properly compacted. The site shall be graded to blend with the terrain. All disturbed areas shall be seeded following the removal of rock ditch checks.

**205-3.7 STRAW WATTLES (9-INCH AND 12-INCH DIAMETER).** The CONTRACTOR shall be responsible to furnish and install straw wattles as directed by the ENGINEER to effectively control erosion and sedimentation. The CONTRACTOR shall install and maintain straw wattles by the end of the work day upon notification by the ENGINEER.

Trenches must be dug to a depth of 3 to 5 inches. Lay the first straw wattle snug into the trench. No daylight shall be seen under the wattles. Pack soil from trenching against the wattle on the uphill side. When installing running lengths of straw wattles, the second wattle shall be installed 9 to 12 inches from the first wattle. Do not overlap the ends. Each wattle shall have a minimum of three stakes with additional stakes spaced at a minimum of one every three feet. Stakes shall not extend more than two inches above straw wattle.

The following table provides maximum downslope spacing for various slopes.

<b>Maximum Spacing - Downslope</b>	
<b>9-Inch Diameter Straw Wattles</b>	<b>12-Inch Diameter Straw Wattles</b>
1:1 slopes = 10 feet apart	1:1 slopes = 10 feet apart
2:1 slopes = 20 feet apart	2:1 slopes = 20 feet apart
3:1 slopes = 30 feet apart	3:1 slopes = 30 feet apart
4:1 slopes = 40 feet apart	4:1 slopes = 40 feet apart

Adjustments may have to be made for the soil type with approval by the ENGINEER. For soft, loamy soils: adjust the rows closer together. For hard, rocky soils: adjust the rows farther apart.

The CONTRACTOR shall inspect the operation and maintenance of straw wattles each week and within 24 hours following rainfall events of 1/2 inch or more until final acceptance of the contract. Rainfall shall be measured on site. The CONTRACTOR shall be responsible for all maintenance to straw wattles. Sediment shall be maintained in such a way that it does not exceed one-third of the straw wattle height.

The CONTRACTOR shall remove straw wattles appropriately after all sediment-producing areas have been stabilized, or as directed by the ENGINEER. Removal shall include any size of straw wattle and shall include the removal of all stakes. All sedimentation shall be removed, and all excavations shall be backfilled and properly compacted. The site shall be graded to blend with the terrain, and all disturbed areas shall be seeded.

**205-3.8 DRAINAGE STRUCTURE INLET FILTER.** The CONTRACTOR shall be responsible to furnish and install drainage structure inlet filters as directed by the ENGINEER to effectively control erosion and sedimentation.

The CONTRACTOR shall inspect the operation and maintenance of drainage structure inlet filters each week and within 24 hours following rainfall events of 1/2 inch or more until final acceptance of the contract. Rainfall shall be measured on site. Inlet filters shall be cleaned once a week when debris has plugged the filter or as directed by ENGINEER. The CONTRACTOR shall be responsible for all maintenance to drainage structure inlet filters. Maintenance and periodic cleaning of the filter shall be incidental. Periodic removal and replacement due to large rain events may be required at the Engineer's discretion and shall be considered incidental.

The inlet filter assembly shall remain in place until removal is directed by the ENGINEER and shall include the disposal of debris or silt that has accumulated in the bag.

**205-3.9 CONCRETE EROSION CONTROL BLANKETS.** The CONTRACTOR shall be responsible to furnish and install concrete erosion control blankets to line and grade as shown on the plans or as directed by the ENGINEER to effectively control erosion and sedimentation. Each concrete erosion control blanket panel shall be butted against adjacent panels. The inslopes shall be free of debris and dressed to a smooth, firm surface.

Concrete erosion control blankets shall be anchored as follows:

- A. A six inch loop is strung around the loops of two mats that are to be anchored together. The six inch loop is strung through the eyehole of the anchor and clamped. The driven depth of the anchor shall be 36 to 42 inches deep. Drive the anchor until the top side loops are pulled down into the soil. This provides sufficient tension on the anchor, so if movement of the mats should occur, the anchor will turn and set itself.
- B. Each concrete erosion control panel shall be tied together with each adjacent panel at a maximum of eight foot spacing.

The CONTRACTOR shall inspect the operation and maintenance of concrete erosion control blankets each week and within 24 hours following rainfall events of 1/2 inch or more until final acceptance of the contract. Rainfall shall be measured on site. The CONTRACTOR shall be responsible for all maintenance to concrete erosion control blankets.

The CONTRACTOR shall remove concrete erosion control blankets appropriately after all sediment-producing areas have been stabilized or as directed by the ENGINEER. All sedimentation shall be removed and all excavations shall be backfilled and properly compacted. The site shall be graded to blend with the terrain and all disturbed areas shall be seeded.

## SECTION 205 – EROSION AND SEDIMENT CONTROL

**205-3.10 EROSION CONTROL BERM.** The CONTRACTOR shall be responsible to furnish and install erosion control berms as directed by the ENGINEER to effectively control erosion and sedimentation at curb and road ends. The CONTRACTOR shall construct erosion control berms as per Standard Detail 205-2.

The CONTRACTOR shall inspect the operation and maintenance of erosion control berms each week and within 24 hours following rainfall events of 1/2 inch or more until final acceptance of the contract. Rainfall shall be measured on site. The CONTRACTOR shall be responsible for all maintenance to erosion control berms.

The CONTRACTOR shall remove erosion control berms appropriately after all sediment-producing areas have been stabilized or as directed by the ENGINEER. All sedimentation shall be removed and all excavations shall be backfilled and properly compacted. The site shall be graded to blend with the terrain, and all disturbed areas shall be seeded.

**205-3.11 TRANSITION MAT.** Transition Mat shall be Scourstop as manufactured by Hanes Geo Components or approved equivalent. Construct transition mat as noted on the plans. CONTRACTOR shall provide and install transition mat per manufacturer's recommendations. CONTRACTOR shall abut the mats and provide and install a minimum of 8 anchors per mat. Mats shall be placed a minimum of 6-inches behind the storm pipe flared end sections and to the dimensions shown on the plans.

CONTRACTOR shall provide and install erosion control blanket (ECB) beneath the transition mat and as shown on the plans. ECB shall meet the requirements of Section 205 for ECB Type 2. Torn or punctured ECB shall not be used. ECB shall be placed a minimum of 12-inches behind the storm pipe flared end sections, or as required by the transition mat manufacturer, and to the dimensions shown on the plans. All costs for providing and installing ECB shall be incidental to the Transition Mat.

### **205-4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107 and as follows:

All erosion and sediment control contract items shall be measured based on one-time installations. All repair, maintenance, removal and re-installation at the same location, and permanent removal is incidental, unless otherwise specified.

Staples, anchors or any other material required for installation will not be measured for payment but shall be incidental to the pay item.

**205-4.1 EROSION CONTROL BLANKET.** Erosion Control Blanket shall be measured by the actual surface area covered to the nearest square yard. No allowance will be

## SECTION 205 – EROSION AND SEDIMENT CONTROL

made for overlaps and buried blankets or mats. Material that is damaged, wasted, or not properly placed will not be measured for payment.

**205-4.2 SILT FENCE REMOVAL.** Silt Fence Removal shall be measured and paid for at the unit price bid for “Silt Fence Removal.”

**205-4.3 DRAINAGE STRUCTURE INLET FILTER.** Relocation of functional filters, when approved by the ENGINEER, shall be measured and paid at the unit price of the original contract item.

**205-4.4 EROSION CONTROL BERM.** This item includes all items shown on Standard Detail 205-2.

## SECTION 302 – AGGREGATE BASE AND AGGREGATE SURFACE

### 302-1 DESCRIPTION

This item shall consist of aggregate base and aggregate surface composed of crushed, partially crushed, or uncrushed coarse aggregate bonded with either soil or fine aggregate or both. It shall be constructed on a prepared underlying course in accordance with these specifications and shall conform to the dimensions and typical cross section shown on the plans and with the lines and grades established by the ENGINEER.

### 302-2 MATERIALS

It shall be the responsibility of the CONTRACTOR to furnish material which, when compacted, will support the construction equipment without showing signs of displacement.

**302-2.1 GRADATION.** The gradation of the aggregate base and aggregate surface material shall meet the requirements of the gradations given in the following table when tested in accordance with ASTM C136.

<b>Square Mesh Sieve Size</b>	<b>Percent By Weight Passing</b>	<b>Percent By Weight Passing</b>
	<b>Class 5 Aggregate Base</b>	<b>Class 13 Aggregate Surface</b>
1"	100	100
3/4"	90-100	70-100
No. 4	35-70	38-75
No. 8	-	22-62
No. 30	16-40	12-45
No. 40	-	-
No. 200	4-10	7-15
P.I.	-	-
L.L.	-	-
% Shale & Rock in Total Sample	12	12
% L.A. Abrasion Loss	50 (max.)	50 (max.)
% Fractured Faces	10 (min.)	10 (min.)

The maximum allowable plasticity index (PI) of aggregate shall be based on the material gradation and computed by the following formula:

$$\text{Max PI} = 10 - (\text{percent passing the No. 40 sieve} \div 10)$$

## SECTION 302 – AGGREGATE BASE AND AGGREGATE SURFACE

The gradations in the table represent the limits which shall determine suitability of aggregate for use from the sources of supply. The final gradations decided on within the limits designated in the table shall be well graded from coarse to fine and shall not vary from the low limit on one sieve to the high limit on the adjacent sieves, or vice versa.

The selection of any of the gradations shown in the table shall be such that the maximum size aggregate used in any course shall not be more than two-thirds the thickness of the layer of the course being constructed.

The source from which the CONTRACTOR proposes to furnish this base material shall be approved prior to hauling to the project.

Testing for gradation shall be performed once per 1,000 tons, with a maximum of one test per day, each test shall consist of three samples, with the final result based on the average of the three samples. Testing for other properties in the above table shall be performed once every 10,000 tons.

Sampling of the final aggregate base and aggregate surface material shall be performed by an independent testing laboratory approved by the ENGINEER to test the composition of the mixtures, the mineral aggregates, and the in-place density of the mixture. Approval or disapproval of the material and reasons therefor will be by written order to the CONTRACTOR over the signature of the CITY ENGINEER.

**302-2.2 BLENDED BASE.** This item shall consist of a uniformly blended material containing up to 50 percent recycled asphalt by volume with up to 100 percent crushed concrete or Class 5 aggregate. Blended base shall be constructed on a prepared subgrade in conformity with the dimensions and typical section shown on the plans. Blended base shall meet gradation as per Section 302. The blended base shall be deposited, spread, and shaped so the moist and compacted course conforms to the required grade and cross section. The desired degree of compaction will be acceptable when the surface is tightly bound and shows no rutting or displacement under the roller operations.

**General.** All final combined materials (i.e., blended base) shall meet the following requirements:

<b>Percent by Weight Passing Sieve Size for Blended Base</b>	
1½"	100
1"	90-100
No. 4	35-85
No. 30	16-50
No. 200	0.0-12

**302-2.3 MILLING MATERIAL PATCHING.** Where an asphalt patch is required, the milling material salvaged on site may be used in conjunction with stabilized gravel base for backfill in areas of subgrade failures. The milling material in excess of 4 inches by 4 inches will not be allowed for backfilling. In areas where there are no subgrade failures, the milling material shall be stockpiled at locations in need of this material as directed by the ENGINEER.

### **302-3 CONSTRUCTION REQUIREMENTS**

**302-3.1 OPERATIONS IN PITS AND QUARRIES.** All work involved in clearing and stripping pits and quarries, including handling of unsuitable material, shall be performed by the CONTRACTOR. All material shall be handled in a manner that shall secure a uniform and satisfactory base product. The base course material shall be obtained from sources that have been approved. These operations shall be the responsibility of the CONTRACTOR at no additional cost.

**302-3.2 EQUIPMENT.** All equipment necessary for the proper construction of this work shall be on the project in proper working condition and approved by the ENGINEER before construction is permitted to start.

**302-3.3 PREPARING UNDERLYING COURSE.** The underlying course shall be checked and accepted by the ENGINEER before placing and spreading operations are started. Any ruts or soft, yielding places due to improper drainage conditions, hauling, or any other cause shall be corrected and rolled to the required density before the base course is placed thereon.

Grade control between the edges of the pavement shall be accomplished by grade stakes, steel pins, or forms placed in lanes parallel to the centerline of the pavement at intervals sufficiently close that string lines or check boards may be placed between stakes, pins, or forms.

To protect the underlying course and to ensure proper drainage, the spreading of the base shall begin along the centerline of the subgrade on a crowned section or on the high side of the subgrade with a one-way slope.

### **302-3.4 METHODS OF PRODUCTION**

**(a) Plant Mix.** When provided for in the proposal, or when selected by the CONTRACTOR and approved by the ENGINEER, the aggregate base and aggregate surface material shall be uniformly blended or mixed in an approved plant. The mixing plant shall include bins for storing and batching of the aggregate, pump and tanks for water, and batch mixers of either the pugmill or drum type. All mineral aggregates shall be batched into a mixer by weight. The agitation shall be such that a thorough dispersion of moisture is obtained. The size of the batch and the time of mixing shall be fixed by the ENGINEER and shall produce the results and requirements specified. The base course material produced by combining two or more materials from different

## SECTION 302 – AGGREGATE BASE AND AGGREGATE SURFACE

sources shall be mixed in a mixing plant described herein. The mixture material shall be at a satisfactory moisture content to obtain maximum density.

**(b) Travel Plant.** When the use of a travel plant is allowed, the plant shall blend and mix the materials to meet these specifications. It shall accomplish a thorough mixing in one trip. The agitation shall be such that the dispersion of the moisture is complete. The machine shall move at a uniform rate of speed, and this speed shall be regulated to fix the mixing time. If a windrow-type of travel plant is employed for mixing, the aggregate shall be placed in windrows parallel to the pavement centerline. The windrow volume shall be sufficient to cover exact areas planned. The windrow contents shall produce a mixture of the required gradation and bonding qualities. If a travel plant is used which is of the type that mixes previously spread aggregates in place, the material shall have been spread in such thickness and proportions as may be handled by the machine to develop a base course of the thickness of each layer and of the gradation required. With either type of equipment, the mixed material shall be at satisfactory moisture content to obtain the maximum density.

**(c) Proportioning or Blending in Place.** When the aggregate base and aggregate surface materials are to be proportioned and mixed or blended in place, the different layers shall be placed and spread with the relative proportions of the components of the mixture being designated by the ENGINEER. The aggregate base shall be deposited and spread evenly to a uniform thickness and width. Then the binder or filler shall be deposited and spread evenly over the first layer. There shall be as many layers of materials added as the ENGINEER may direct to obtain required gradation and layer thickness. When the required amount of material has been placed, they shall be thoroughly mixed and blended by means of approved graders, discs, harrows, rotary tillers, or a machine capable of combining these operations, supplemented by other suitable equipment, if necessary. The mixing shall continue until the mixture is uniform throughout and accepted by the ENGINEER. Areas of segregated material shall be corrected by the addition of needed material and by remixing. Water shall be uniformly applied, prior and during the mixing operation, if necessary, to maintain the material at the proper moisture content. When the mixing and blending have been completed, the material shall be bladed and dragged, if necessary, until a smooth uniform surface is obtained, true to line and grade.

**(d) Materials of Proper Gradation.** When the entire aggregate base and aggregate surface material from coarse to fine is secured in a uniform and well graded condition and contains approximately the proper moisture, such approved material may be handled directly to the spreading equipment. The material may be obtained from gravel pits, stockpiles, or produced from a crushing and screening plant with the proper blending. The materials from these sources shall meet the requirements for gradation, quality, and consistency. The intent of this section of these specifications is to secure materials that will not require further mixing. The base material shall be at satisfactory moisture content to obtain maximum density. Any minor deficiency or excess of moisture may be corrected by surface sprinkling or by aeration. In such instances some mixing or manipulation may be required immediately preceding the rolling to obtain the

## SECTION 302 – AGGREGATE BASE AND AGGREGATE SURFACE

required moisture content. The final operation shall be blading or dragging, if necessary, to obtain a smooth uniform surface true to line and grade.

### **302-3.5 METHODS OF SPREADING.**

(a) The aggregate base and aggregate surface material that is correctly proportioned or has been processed in a plant shall be placed on the prepared underlying course and compacted in layers of the thickness shown on the plans. The depositing and spreading of the material shall commence where designated and shall progress continuously without breaks. The material shall be deposited and spread in lanes in a uniform layer and without segregation of size to such loose depth that, when compacted, the layer shall have the required thickness. Hauling over the uncompacted base course or subgrade shall not be permitted.

(b) The aggregate base and aggregate surface material that has been processed in a traveling plant or mixed and blended in place shall be spread in a uniform layer of required depth and width and to the typical cross section. The spreading shall be by a self-powered blade grader, mechanical spreader, or other approved method. In spreading, care shall be taken to prevent cutting into the underlying layer. The material shall be bladed until a smooth, uniform surface is obtained, true to line and grade.

(c) The aggregate base and aggregate surface shall be constructed in a layer not more than 9 inches of compacted thickness. The aggregate as spread shall be of uniform grading with no pockets of fine or coarse materials. Any necessary sprinkling shall be kept within 2,000 square yards in advance of the rolling.

When more than one layer is required, the construction procedure described herein shall apply similarly to each layer.

Tests shall be made to determine the maximum density and the proper moisture content of the base material, and this information will be available to the CONTRACTOR and ENGINEER. The base material shall be at a satisfactory moisture content when rolling is started, and any minor variation prior to or during rolling shall be corrected by sprinkling or by aeration, if necessary.

During the mixing and spreading, sufficient caution shall be exercised to prevent the incorporation of subgrade, subbase, or shoulder material in the base course mixture.

**302-3.6 FINISHING AND COMPACTING.** While spreading, the aggregate shall be thoroughly compacted by rolling. The rolling shall progress gradually from the sides to the center of the lane under construction, or from one side toward previously placed material by lapping uniformly each preceding rear wheel track by one-half the width of such track. Rolling shall continue until the entire area of the course have been rolled by the rear wheels. The rolling shall continue until the aggregate is thoroughly set, the interstices of the material reduced to a minimum, and until creeping of the material ahead of the roller is no longer visible. Rolling shall continue until the aggregate base and aggregate surface material has been compacted to not less than 95 percent of the

## SECTION 302 – AGGREGATE BASE AND AGGREGATE SURFACE

maximum dry density at optimum moisture as determined by the compaction control tests specified in ASTM D1557 with a moisture content falling within plus or minus 3 percentage points of optimum moisture content. The compaction control tests for this section are based on one (1) individual compaction test per 1,500 square yards of area. The CONTRACTOR shall be responsible for all retesting of failing tests. Blading and rolling shall be done alternately as required or directed to obtain a smooth, even, and uniformly compacted base.

The course shall not be rolled when the underlying course is soft or yielding or when the rolling causes undulation in the base course. When the rolling develops irregularities that exceed 1/2 inch when tested with a 16-foot straightedge, the irregular surface shall be loosened, refilled with the same kind of material as that used in constructing the course, and rolled again as required.

In areas inaccessible to rollers, the aggregate base and aggregate surface material shall be tamped thoroughly with approved mechanical tampers.

The sprinkling during rolling, if necessary, shall be in the amount and by equipment approved by the ENGINEER.

**302-3.7 PROOF ROLL.** Before preparations begin for application of a surface treatment or for a surface course, the CONTRACTOR shall proof roll the base, under the supervision of the ENGINEER. The proof roll shall be performed with a minimum gross weight of 44,000 lbs. on a tandem axle truck with four tires per rear axle. Any failing areas in the base shall be the responsibility of the CONTRACTOR to remove and replace, at the discretion of the ENGINEER.

**302-3.8 SURFACE TEST.** After the course has been completely compacted, the surface shall be tested for smoothness and accuracy of grade and crown. Any portion lacking the required smoothness or failing in accuracy of grade or crown shall be scarified, reshaped, recompacted, and otherwise manipulated as the ENGINEER may direct until the required smoothness and accuracy are obtained. The finished surface shall not vary more than 1/2 inch from a 16-foot straightedge when applied to the surface parallel with and at right angles to the centerline.

**302-3.9 THICKNESS.** The thickness of the aggregate base and aggregate surface shall be determined by depth tests or cores taken at intervals in such manner that each test shall represent no more than 300 square yards. When the base deficiency is more than 1/2 inch, the CONTRACTOR shall correct such areas by scarifying, adding satisfactory base mixture, rolling, sprinkling, reshaping, and finishing in accordance with these specifications. The CONTRACTOR shall replace at its expense the base material where borings have been taken for test purposes.

**302-3.10 PROTECTION.** Placement of the aggregate base and aggregate surface shall not take place during freezing temperatures nor when the subgrade is wet. When the aggregates contain frozen materials or when the underlying course is frozen, the construction shall be stopped.

## SECTION 302 – AGGREGATE BASE AND AGGREGATE SURFACE

Hauling equipment may be routed over completed portions of the aggregate base and aggregate surface, provided no damage results, and provided that such equipment is routed over the full width of the base course to avoid rutting or uneven compaction. However, the ENGINEER in charge shall have full and specific authority to stop all hauling over completed or partially completed base course when in his opinion such hauling is causing damage. Any damage resulting to the base course from routing equipment over the base course shall be repaired by the CONTRACTOR at its own expense.

**302-3.11 MAINTENANCE.** Following the completion of the aggregate base and aggregate surface, the CONTRACTOR shall perform all maintenance work necessary to keep the aggregate base and aggregate surface in a condition satisfactory for priming. After priming, the surface shall be kept clean and free from foreign material. The base course shall be properly drained at all times. If cleaning is necessary, or if the prime coat becomes disturbed, any work or restitution necessary shall be performed at the expense of the CONTRACTOR.

If, during the curing period, the surface of the base dries to the extent that it becomes dusty with consequent loss of binder, it shall be kept moist by sprinkling until such time as the prime coat is applied as directed.

**302-3.12 TRUCK SCALES.** The aggregate base and aggregate surface shall be weighed on approved scales furnished by the CONTRACTOR or on public scales at the CONTRACTOR's expense. Scales shall be inspected for accuracy and sealed as often as the ENGINEER deems necessary.

### 302-4 MEASUREMENT AND PAYMENT

Measurement and payment shall be as specified in Section 107 and as follows:

**302-4.1 AGGREGATE BASE.** This price shall be full compensation for furnishing all materials and for all operations, hauling, and placing of these materials..

#### 302-4.2 BLENDED BASE.

The price shall include supplying recycled asphalt, Class 5 aggregate, crushed concrete, blending, gradation testing, loading, hauling, and placing of the material.

**302-4.3 MILLING MATERIAL PATCHING.** The milling material for patches shall be measured in place.

## **SECTION 303 – CEMENT STABILIZED SUBGRADE**

### **303-1 DESCRIPTION**

This item shall consist of stabilizing the subgrade by the addition of Portland cement, mixing, wetting and compacting the mixed material to the required density. This item applies to existing in place soils, and shall be constructed as specified herein and in conformity to the typical sections, lines and grades as shown on plans or as established by the ENGINEER.

### **303-2 MATERIALS**

**303-2.1 SOIL.** Soil shall consist of approved material free from vegetation and or other objectionable matter encountered in the existing roadbed and other acceptable material used in the preparation of the roadbed in accordance with this specification. The CONTRACTOR shall familiarize himself with the definitions of unstable, unsuitable, suitable, and unsatisfactory materials as defined in Section 202. Portland cement and water shall conform to Section 501.

**303-2.2 SOIL-CEMENT MIX DESIGN.** The CONTRACTOR shall submit a mix design as specified below. The CITY may provide a mix design for the project area. If a mix design is supplied, the CITY does not warrant the accuracy of the information. The CONTRACTOR may choose to use the mix design at their discretion.

The mix design shall be submitted by the CONTRACTOR for approval by the ENGINEER. The mix design shall be performed with representative materials to be encountered during construction of the cementitious stabilization. When the in-place materials change significantly, additional mix designs shall be performed to establish representative mixes for the entire job. Representative samples of the in-place materials shall be obtained directly from the project site. The stabilized soil mix designs shall be designed by an independent testing laboratory as required by Section 104.

The testing lab shall conduct a moisture-density test, in accordance with ASTM D 558, to determine the maximum dry density and optimum water content of the in situ soil or mixture of soil and aggregate.

The cementitious stabilizer shall be mixed with the subgrade soil at field moisture content but no more than 6 percent of optimum water content or at optimum water content plus 2 percentage points, whichever is higher, with various rates of cement. The testing lab shall perform soil-cement mixtures using estimated cement content from table below.

## SECTION 303 – CEMENT STABILIZED SUBGRADE

<b>Soil Classification</b>	<b>Initial Estimated Cement Content (Percent by Weight)</b>
GW, SW	3
GP,	4
GC, GM, SC, SM, SP	5
CL, ML, MH	6
CH	7

The samples shall be cured for seven days in a humid room before testing. Samples shall be tested using the unconfined compression test in accordance with ASTM D 1633. Passing sample shall achieve an unconfined compressive strength of 225 psi but not less than 175 psi or greater than 350 psi. The lowest cement content, with the closest unconfined compressive strength to 225 psi shall be the design cement content for that subgrade in situ soil at that moisture content.

The mix design shall be the baseline measure for the rate of cementitious stabilizer and water with the existing materials to construct the stabilized mixture. The mix design shall indicate the allowable tolerance for the stabilizer application and water so it does not jeopardize the performance of the mix, but allows the ENGINEER or CONTRACTOR to adjust the mix with the approval of the ENGINEER so that it may be placed successfully.

**303-2.3 PORTLAND CEMENT.** Portland cement shall conform to Section 501.

### **303-3 CONSTRUCTION REQUIREMENTS**

**303-3.1 GENERAL** The subgrade shall be prepared to the lines and grades shown in the plans. In irregular areas, trim the subgrade by wetting, blading and rolling. Cement stabilized subgrade operations shall not be performed when the ambient air temperature is below 40°F, or the soil is frozen. The specified depth of treatment shall be per plan detail or designated in the field by the ENGINEER. The CONTRACTOR shall have a person experienced in cement stabilization available to be on site during construction of the stabilized subgrade. All testing shall conform to Section 104.

**303-3.2 SPREADING.** The cement shall be applied using a controlled application system.

Application equipment, for dry powder cement shall be capable of providing a consistent, accurate and uniform distribution of material while minimizing dust during construction. Application equipment shall include a volume measuring device. Cement shall not be applied when conditions are such that material may be lost due to wind. The CONTRACTOR shall limit the amount of cement that is spread to that which can be incorporated into the soil within the same day. Application equipment shall meet the description as stated or an approved method by the ENGINEER.

## SECTION 303 – CEMENT STABILIZED SUBGRADE

The cement application rate shall be determined by the classification of soil and moisture content of the in situ soil. The cement shall be applied to within a tolerance of plus or minus 5 percent by weight of the rate required. Cement application shall be calculated by using the following formula:

$$(g) \times (A) \times 9(\text{SQFT/SY}) \times (D) = (C)$$

(g) Maximum dry unit weight of soil (PCF)  
(A) Cement Content (decimal)  
(D) Depth of cement stabilization (FT)  
(C) Cement Application Rate (LB/SY)

If the work is stopped due to weather or equipment failure to which the cement is exposed to the hydration process or causes the cement to be lost due to wind, the CONTRACTOR shall spread any additional cement needed at the CONTRACTOR's expense.

During the cement application process, The ENGINEER may deem it necessary to check the application rate of the cement. The CONTRACTOR shall blade a flat area in the path of the cement application and place a planar surface with an area of 1 square yard, such as a straight-sided pan, on the prepared area. The train shall be allowed to pass over the surface. The test surface shall be weighed before and after the cement application and the application rate calculated. Other methods to check the application rate may be used with the ENGINEERS approval.

**303-3.3 MIXING.** Only self-propelled, high powered, rotary mixers/reclaimers capable of mixing, in-place, to a depth of 12 inches shall be used. The cutting drum shall be fit with cutting teeth capable of trimming earth and aggregate and shall be designed to be accurately adjusted vertically and held in-place. The mixing shall continue until a homogenous layer of the required thickness has been obtained. One hundred percent of the material, excluding rock particles, shall pass a 1-inch sieve and 70% shall pass a No. 4 sieve. Gradation tests are based on one individual test per 10,000 square yards (SY) of area. The CONTRACTOR shall be responsible for all retesting of failing tests and making any necessary adjustments to achieve passing results.

Gradation Test shall be calculated using the following formula:

$$\% \text{ Pulverization} = 100 \times (A)/(B-C)$$

(A) Weight of minus #4  
(B) Weight of original sample  
(C) Weight of plus #4 Gravel

Disc harrows, bucket teeth and other equipment that does not meet the above requirements shall only be used as needed, when mixers/reclaimers can't be utilized, with approval by the ENGINEER.

The mixer/reclaimer shall be fitted with an integrated water injection system capable of introducing the water into the cutting drum during the mixing process. The metering

## SECTION 303 – CEMENT STABILIZED SUBGRADE

device shall be capable of automatically adjusting the flow of water to compensate for any variation in the amount of reclaimed material introduced into the mixing chamber. Automatic digital readings shall be displayed for both the flow rate and total amount of reclaimed material and water in appropriate units of weight and time.

Mixers/reclaimers shall meet the description as stated or an approved method by the ENGINEER.

The mixing shall be completed within 30 minutes of adding the cement to the subgrade soil.

Prior to compaction, at the location of the mix design, an unconfined compressive strength test in accordance with ASTM D 1633 and a No. 4 Sieve Gradation Test, as specified in this provision, shall be taken.

The CONTRACTOR shall target a 7-day unconfined compressive strength of 225 psi with a minimum of 175 psi and no more than 350 psi. The CONTRACTOR or ENGINEER shall adjust the cement application rate as needed to achieve the target compressive strength of 225 psi.

**303-3.4 COMPACTION.** Compaction shall begin immediately after the cement has been mixed thoroughly with the subgrade soil. Compaction testing shall conform to Section 204. The compaction operation shall be completed within 2 hours of incorporating the cement into the subgrade. If mixing, spreading, and compacting requirements are not satisfied, the CONTRACTOR shall reprocess, recompact and refinish the deficient areas.

The finish subgrade shall be compacted to 92 percent of standard proctor maximum dry density as determined by ASTM D 558. The CONTRACTOR shall be responsible for all retesting of failing tests. If failing tests are still present after 72 hours the CONTRACTOR shall perform an extensive proof roll in the area of concern according to the specifications below.

**303-3.5 ASPHALT PULVERITZATION.** All areas of reconstruction with cement stabilized subgrade shall utilize pulverization. This work shall consist of pulverizing and blending the existing asphalt and subgrade materials for cement stabilized subgrade.

Pulverization shall be done with a self-propelled, high-powered, rotary mixer/reclaimer capable of mixing, in-place, to a depth as specified in plans. The cutting drum shall be fit with cutting teeth capable of trimming earth and aggregate and shall be designed to be accurately adjusted and held in place vertically.

The existing asphalt and subgrade material shall be pulverized to a depth as per plans and special provisions. The mixing shall continue until a homogenous layer of the required thickness has been obtained.

## SECTION 303 – CEMENT STABILIZED SUBGRADE

After pulverization and prior to pulverization excavation the CONTRACTOR shall take one field moisture test for every 750 LF of the centerline of reconstructed roadway. The moisture content prior to cement stabilization shall not be more than six percentage points above optimum moisture. The ENGINEER shall determine prior to pulverization excavation if additional material shall be excavated and replaced with blended base.

**303-3.6 FINISHING.** After compaction of the stabilized subgrade, the surface shall be trimmed to the specified lines and grades. Lightly scarify and blade the surface to eliminate equipment imprints while performing final rolling.

**303-3.7 CURING.** The CONTRACTOR shall allow a minimum of 72 hours before covering the subgrade with gravel or bituminous asphalt and before it is subjected to freezing. If the finished stabilized subgrade is not covered with a lift of bituminous asphalt or aggregate base and is subjected to freezing, the ENGINEER will determine if any of the subgrade needs to be reworked at the CONTRACTOR's expense.

The CONTRACTOR shall protect the finished subgrade against drying for 5 days after completion, or until the subgrade is covered with a base. The finished subgrade shall be protected from drying by spraying with water to maintain a continuous moist condition. The CONTRACTOR may apply an asphalt prime coat instead of keeping the finished surface moist with water. If this option is chosen, apply SS-1, CSS-1, or MC-250 at the rate of 0.22 gallons per square yard to achieve minimum of 0.13 gallons per square yard residue. Multiple light applications may be necessary to obtain the specified rate of application without run-off.

**303-3.8 PROOF ROLL.** Prior to covering the subgrade with gravel or bituminous asphalt and before it is subjected to freezing, the CONTRACTOR shall proof roll the subgrade, under the supervision of the ENGINEER. The proof roll shall be performed with a minimum gross weight of 44,000 lbs. on a tandem axle truck with four tires per rear axle. Any failing areas in the subgrade shall be the responsibility of the CONTRACTOR to remove and replace with gravel, at the discretion of the ENGINEER.

### **303-4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107 and as follows:

**303-4.1 ADDITIONAL EXCAVATION.** Any additional excavation shall be paid for at unit price bid for Unclassified Excavation as per Section 202.

**303-4.2 ADDITIONAL BLENDED BASE.** Any additional blended base shall be paid for at the unit price bid for Blended Base as per Section 302.

## DIVISION 400

### FLEXIBLE PAVEMENT

#### SECTION 401 – ASPHALTIC CONCRETE PAVEMENT

##### 401-1 DESCRIPTION

This item shall consist of an AC patch, leveling, base course and/or surface course composed of mineral aggregate and bituminous material, mixed in a central mixing plant and placed on a prepared subgrade, aggregate base or AC base course in accordance with these specifications and in conformity with the dimensions and typical cross sections shown on the plans and with the lines and grades established by the ENGINEER.

The AC base course shall be constructed as shown on the plans in lifts not to exceed 3 inches in thickness. The AC patch, leveling, and/or surface course shall be constructed as shown on the plans in lifts not to exceed 2½ inches in thickness. The maximum lift thickness will be waived if the CONTRACTOR is able to demonstrate by means of a test section that compaction, texture, and surface tolerance can be obtained for a thicker lift. If the result of the test is satisfactory, the ENGINEER will authorize the CONTRACTOR in writing to construct the thicker lift.

All NDDOT tests per this specification shall follow the NDDOT Field Sampling and Testing Manual with the following exceptions: all testing procedures shall be done by an independent testing laboratories per Section 104 and testing frequency shall be as described in the following specifications.

##### 401-2 MATERIALS

**401-2.1 AGGREGATE.** The aggregate shall consist of crushed stone, crushed gravel, gravel, sand gravel, sand, crushed sand, or other natural granular and approved material which has essentially the same qualities and meets all requirements when combined within the limits for gradation.

The aggregate shall be tough, durable, sound, and shall consist of angular fragments reasonably uniform in density and quality. The aggregate shall be free of soil, roots, and other organic matter. The physical characteristics and quality of the materials shall be conditionally approved by the ENGINEER, in stockpile, at the plant site.

Aggregate (fine and coarse) shall be sampled in accordance with NDDOT ND T 27 for Sieve Analysis of Fine and Coarse Aggregate and NDDOT ND T 11 for Materials Finer than No. 200 Sieve in Mineral Aggregates by Washing.

## SECTION 401 – ASPHALTIC CONCRETE PAVEMENT

The final gradations decided on within the limits designated in the table shall be well graded from coarse to fine and shall not vary from the low limit on one sieve to the high limit on the adjacent sieves or vice versa. Aggregate shall meet the following requirements.

Sieve Size	1/2 Inch Nominal Maximum Aggregate Size <sup>1</sup> Percent Passing	
	Min.	Max.
5/8 Inch	100	100
1/2 Inch	90	100
#4	40	70
#30	15	35
#200	2.0	7.0
<sup>1</sup> Nominal aggregate size is defined as one sieve size larger than the first sieve to retain more than ten percent.		

Test Method	Test Name	Criteria
NDDOT ND T 176	Plastic Fines in Graded Aggregates and Soils by Use of the Sand Equivalent Test	40% min.
NDDOT ND D 4791	Test Method for Flat Particles, Elongated Particles, or Flat Elongated Particles in Coarse Aggregate	10% max.
AASHTO T 96	Standard Method of Test for Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine	40% max.
NDDOT ND T 113	Lightweight Pieces in Virgin Aggregate	5.0% max.

**401-2.2 BITUMINOUS MATERIAL.** Unless otherwise specified, the bitumen shall be PG 58-28 or PG 58S-28 performance-graded asphalt cement or as approved by the ENGINEER. A certificate of asphalt cement material shall be submitted for each mixture supplied, for each load of asphalt cement delivered to the hot mix plant.

The percent by weight for the bituminous material shall be within the limits given. The bituminous content of the mixture shall be calculated on a percentage basis by weight of the total mix. The percentage of bituminous material by weight to be added to the aggregate shall be on the basis of preliminary laboratory tests and field sieve analysis.

The asphalt cement shall conform to ASTM D946 and shall be mixed at a temperature falling within the range of 250°F to 325°F.

**401-2.3 SUPERPAVE MIX PROPERTIES.** The superpave mix properties shall meet the following requirements. The fine aggregate angularity (FAA) shall be based on the designation of the bid item.

SECTION 401 – ASPHALTIC CONCRETE PAVEMENT

Property	FAA 40	FAA 41	FAA 42	FAA 43	FAA 44	FAA 45
Fractured Particles in Coarse Aggregate Angularity (min)	75%	75%	75%	75%	85%	85%
Fine Aggregate Angularity (min)	40%	41%	42%	43%	44%	45%
Gyratory Effort, # of Gyration	$N_{ini} = 7, N_{des} = 75, N_{max} = 115$					
Voids filled with Bitumen	65-78%	65-78%	65-78%	65-78%	65-75%	65-75%
%G <sub>mm</sub> @ N <sub>ini</sub> (max)	90.5%	90.5%	89%	89%	89%	89R

<b>Methods for Determining Superpave Mix Properties</b>	
Test Method	Property
NDDOT 4	Fractured Particles in Coarse Aggregate Angularity
NDDOT ND T 304	Fine Aggregate Angularity
AASHTO R 35	Gyratory Effort, # of Gyration
AASHTO M 323, NDDOT T 166	Voids filled with Bitumen
AASHTO M 323, NDDOT T 166	%G <sub>mm</sub> @ N <sub>ini</sub>

**401-2.4 RECYCLED ASPHALT PAVEMENT.** Bituminous mixture shall allow reclaimed or recycled asphalt pavement (RAP) up to 20 percent of the mixture. A mix design shall be submitted for approval prior to use of each mixture supplied for the project. At least 70 percent of the total asphalt binder in the AC surface course shall be virgin material. Maximum particle size on RAP introduced into the cold feed shall be 1½ inches. Undesirable particles such as joint sealant or marking tape shall be removed from the pavement. The quantity of the asphalt binder in RAP, incorporated into the mix, will be included in the quantity of asphalt binder used. Any cost for virgin oil shall be included in the bid price of the mixture.

**401-2.5 MIX DESIGN.** The CONTRACTOR shall submit, for the ENGINEER's written approval, a mix design for each mixture to be supplied for the project a minimum of 10 calendar days before beginning paving operations. The mix design with the allowable tolerances shall be within the master range specified for the particular type of bituminous material. The job mix formula for each mixture shall establish a single percentage of aggregate passing each required sieve size and a single percentage of bituminous material to be added to the aggregate.

When making the blend determinations for the mix design, the average of the production samples values for each sieve from each stockpile shall be used.

The mix design shall be based on the criteria specified in the following table and developed in accordance with the standards outlined below.

SECTION 401 – ASPHALTIC CONCRETE PAVEMENT

Test Method	Property/	Criteria
AASHTO M 323 NDDOT ND T 166	Voids in Mineral Aggregate	14.0 min. for 1/2 inch nominal maximum aggregate
AASHTO M 323 NDDOT ND T 166	% $G_{min}$ @ $N_{max}$	98.0 Maximum
AASHTO M 323 NDDOT ND T 166	Dust/Effective Asphalt Ratio	0.6 – 1.3 (AC Surface coarse) 0.6 – 1.4 (AC Base coarse)
AASHTO T 283 AASHTO R 30	Desired Moisture Sensitivity, min. % Strength Retention <sup>1, 2</sup>	70 @ 7.0 ± 1% Air Voids
Determined by ND DOT mix design program	Asphalt Film Thickness <sup>1</sup> (microns)	7.5 – 13
<sup>1</sup> Desired value, the Department will make a final determination based on the mix design		
<sup>2</sup> Only required when specified on the Plans		

Test Method	Test Name
NDDOT ND T 312	Preparing and Determining the Density of Hot Mix Asphalt (HMA) specimens by Means of the Superpave Gyratory Compactor
AASHTO R 35	Practice for Superpave Volumetric Design for Hot Mix Asphalt
AASHTO R 30	Mix Conditioning of Hot Mix Asphalt (HMA)
AASHTO M 323	Specification for Superpave Volumetric Mix Design
NDDOT ND T 166	Bulk Specific Gravity of Compacted Bituminous Mixtures using Saturated Surface-Dry Specimens
NDDOT ND T 209	Theoretical Maximum Specific Gravity and Density of Hot Mix Asphalt

The tabulated composition limits shall govern, but a closer control appropriate to the job materials will be required for the specific project in accordance with the established mix design. The following mix design tolerances shall be applied to the mix design to establish a target value control limit.

Test/Assessment		Test Target Value Control Limit
Asphalt cement (based on totalizer reading)		±0.30
NDDOT ND T 11 and ND T 27	Sieve Analysis of Fine and Coarse Aggregates (control Sieves)	
	1/2 Inch	±6
	#4	±6
	#30	±5
	#200	±2.0
NDDOT ND T 209 and ND T 166	Percent Air Voids	2% to 6%
NDDOT ND T 113	Lightweight Pieces in Virgin Aggregate	Not more than the maximum specified

## SECTION 401 – ASPHALTIC CONCRETE PAVEMENT

NDDOT 4	Fractured Particles in Coarse Aggregate Angularity	Not less than the minimum specified
NDDOT ND T 304	Fine Aggregate Angularity	Not less than the minimum specified
NDDOT ND D 4791	Test Method for Flat Particles, Elongated Particles, or Flat Elongated Particles in Coarse Aggregate	Not more than the maximum specified
NDDOT ND T 176	Plastic Fines in Graded Aggregates and Soils by Use of the Sand Equivalent Test	Not less than the minimum specified

Should a change be made in sources of materials, a new mix design shall be established prior to any new materials being used. Should unsatisfactory results or unforeseen conditions make it necessary, a new mix design may be established at the discretion of the ENGINEER.

The mix design for each mixture shall be in effect until modified in writing by the ENGINEER.

The aggregate shall be accepted in stockpile at the plant site. The bituminous material shall be conditionally accepted at the source. The plant mixed material shall be accepted after blending and mixing at the plant.

When directed by the ENGINEER, the gradation of aggregates for AC leveling course, one inch or less in thickness, shall have of 100 percent passing the 1/2-inch sieve.

### 401-4 EQUIPMENT

**401-4.1 EQUIPMENT AND ORGANIZATION.** All methods and equipment tools, plants, and machinery used for handling materials and executing any part of the work shall be subject to the approval of the ENGINEER before the work is started. If unsatisfactory, they shall be changed and improved as required.

**401-4.2 BITUMINOUS MIXING PLANT. GENERAL.** Adequate storage space shall be provided to prevent intermingling of the stockpiles containing separated aggregate sizes until the aggregates are delivered into the plant. The various units of the plant shall be designed and coordinated to permit uniform, uninterrupted production under normal operating conditions. The plant shall be provided with means for readily obtaining representative samples and for calibrating and checking the proportions of each ingredient used in the mixture.

**(a) Requirements for all Plants.** Mixing plants shall be of sufficient capacity and coordinated to adequately handle the proposed bituminous construction.

**(1) Plant Scales.** Scales shall be accurate to within 0.5 percent of the required maximum load. Poles shall be designated to be locked in any position to prevent

## SECTION 401 – ASPHALTIC CONCRETE PAVEMENT

unauthorized change of position. In lieu of plant and truck scales, the CONTRACTOR may provide an approved automatic printer system to print the weights of the material delivered, provided the system is used in conjunction with an approved automatic batching and mixing control system. Such weights shall be evidenced by a weigh ticket for each load. Scales shall be inspected and sealed as often as the ENGINEER may deem necessary to assure their continued accuracy. The CONTRACTOR shall have on hand not less than ten 50-pound weights for testing the scales.

**(2) Equipment for Preparation of Bituminous Material.** Tanks for the storage of bituminous material shall be equipped to heat and hold the material at the required temperatures. Heating shall be accomplished by steam coils, electricity, or other approved means so that flame(s) will not contact the tank. The circulating system for the bituminous material shall be designed to assure proper and continuous circulation during the operating period. Provision shall be made for measuring and sampling storage tanks.

**(3) Feeder for Dryer.** The plant shall be provided with accurate mechanical means for uniformly feeding the aggregate into the dryer to obtain uniform production and temperature.

**(4) Dryer.** The plant shall include a dryer(s) which continuously agitates the aggregate during the heating and drying process.

**(5) Screens.** Plant screens, capable of screening all aggregate to the specified sizes and proportion and having normal capacities in excess of the full capacity of the mixer, shall be provided.

**(6) Bins.** The plant shall include storage bins of sufficient capacity to supply a mixer operating at full capacity. Bins shall be arranged to assure separate and adequate storage of appropriate fractions of the mineral aggregates. When used, separate dry storage shall be provided for filler or hydrated lime, and the plant shall be equipped to feed such material into the mixer. Each bin shall be provided with overflow pipes of such size and at such location to prevent backup of material into other compartments or bins. Each compartment shall be provided with its own individual outlet gate constructed to prevent leakage. The gates shall cut off quickly and completely. Bins shall be so constructed that samples may be obtained readily. Bins shall be equipped with adequate telltale devices which indicate the position of the aggregates in the bins at the lower quarter points.

**(7) Bituminous Control Unit.** Satisfactory means, either by weighing or metering, shall be provided to obtain the specified amount of bituminous material in the mix. Means shall be provided for checking the quantity or rate of flow of bituminous material into the mixer.

## SECTION 401 – ASPHALTIC CONCRETE PAVEMENT

**(8) Thermometric Equipment.** Dual armored thermometers of adequate range shall be fixed in the bituminous feed line at a suitable location near the charging valve of the mixer unit.

The plant shall also be equipped with an approved thermometric instrument placed at the discharge chute of the dryer to indicate the temperature of the heated aggregates. The ENGINEER may require replacement of any thermometer by an approved temperature recording apparatus for better regulation of the temperature of aggregates.

**(9) Truck Scales.** The bituminous mixture shall be weighed on an approved scale furnished by the CONTRACTOR or on public scales at the CONTRACTOR's expense. Scales shall be inspected and sealed as often as the ENGINEER deems necessary to assure their accuracy.

**(b) Cold Feed Control.** The CONTRACTOR may elect to operate the hot plant without plant screens. The basic requirements of this method of operation are to remove all plant screens with the exception of the scalping screen. Permission to continue under this option may be rescinded upon failure to maintain production within the specified gradation limits.

The volume or tonnage placed in each of the two or more stockpiles shall be such a significant portion of the whole tonnage produced as to enable adequate control of the gradation within the job mix formula.

Each individual aggregate shall be fed through a separate feeder that has a positive feed and that can be easily and accurately calibrated. The feed shall be quick adjusting and shall maintain a constant and uniform flow throughout the range of its calibration.

**(c) Batch Plants and Continuous Mix Plants.** The point of acceptance for the physical properties of the aggregates will be in the stockpiles at the plant site. Acceptance testing for aggregate gradation will be performed just prior to the addition of bituminous material to the mixture.

In batch mix plants, a surge bin shall be provided between the dryer and the batch plant, and the discharge into the weigh hopper shall be from one bin only which shall discharge into the center of the weigh hopper. The amount of aggregate stored in the bin at any one time shall not exceed one batch in weight and shall be fed into the bin in a manner that will prevent sloughing and segregation.

In continuous mix plants, a surge bin and mechanical feeder shall be provided. The storage in each bin used shall be limited in amount so that sloughing and segregation will not occur. If more than one bin is used, separation shall be accomplished in such a manner as to ensure flow to each bin and preclude segregation of the total material as obtained from the individual bins.

**(d) Dryer Drum Plants.** An approved dryer drum mixing process will be permitted in lieu of pugmill mixing. The system shall provide positive weight control of the cold aggregate feed by use of a belt scale or other device which will automatically regulate the feed gate and permit instant correction of variations in load. The cold feed flow shall be automatically coupled with the bitumen flow to maintain the required proportions. Proportioning shall be within the tolerances specified in the job mix formula. The system shall be equipped with automatic burner controls and shall provide for temperature sensing of the bituminous mixture at discharge.

The moisture contents of the bituminous mixture at discharge from the mixer shall not exceed three percent. The temperature of the bituminous mixture at discharge from the mixer shall not exceed 300°F. The temperature of the mix at laydown shall be not less than 225°F. The actual mixing temperature shall be adjusted as directed by the ENGINEER within the allowable limitations to best suit construction conditions.

**401-4.3 HAULING EQUIPMENT.** Trucks used for hauling bituminous mixtures shall have tight, clean, smooth metal beds which have been lightly coated with a minimum amount of paraffin oil, lime solution, or other approved material to prevent the mixture from adhering to the beds. In adverse weather, each truck shall have a suitable cover to protect the mixture.

**401-4.4 BITUMINOUS PAVERS.** Bituminous pavers shall be self-contained, power-propelled units, provided with an activated screed or strike-off assembly, heated if necessary. It shall be capable of spreading and finishing courses of bituminous plant mix material which will meet the specified thickness, smoothness, and grade. The paver shall be capable of spreading and finishing courses of bituminous plant mix material in lanes not less than 10 feet in width and shall be capable of operating at forward speed consistent with satisfactory laying of the mixture.

The paver shall have a receiving hopper of sufficient capacity for a uniform spreading operation. The hopper shall be equipped with a distribution system to place the mixture uniformly in front of the screed.

The screed or strike-off assembly shall effectively produce a finished surface of the required evenness and texture without tearing, shoving, or gouging the mixture.

**401-4.5 ROLLERS.** Rollers shall be in good condition, capable of reversing without backlash, and shall operate at slow speeds to avoid displacement of the bituminous mixture. The number, type, and weight of rollers used shall be sufficient to compact the mixture to the required density while the mixture is still in a workable condition. The use of equipment which results in excessive crushing of the aggregate will not be permitted.

## **401-5 CONSTRUCTION REQUIREMENTS**

**401-5.1 WEATHER AND SEASONAL LIMITATIONS.** The bituminous mix shall be constructed only when the surface is dry, the atmospheric temperature is above 40°F

## SECTION 401 – ASPHALTIC CONCRETE PAVEMENT

for AC surface lift or above 30°F for AC base lifts, and the weather is not foggy or rainy. The temperature requirement may be waived, but only when so directed by the ENGINEER.

**401-5.2 PREPARATION OF BITUMINOUS MATERIAL.** The bituminous material shall be heated to the mixing temperature specified in Section 401-2 in a manner that will avoid local overheating and provide a continuous supply of the bituminous material to the mixer at a uniform temperature at all times.

**401-5.3 PREPARATION OF MINERAL AGGREGATE.** The aggregate for the mixture shall be dried and heated at the paving plant before entering the mixer. When introduced into the mixer, the combined aggregate shall not contain more than 0.5 percent moisture. Water in the aggregate shall be removed by heating to the extent that there is no subsequent foaming in the mixture prior to the placing of material. The aggregate shall be heated to a temperature as designated by the mix design within the job tolerance specified. The maximum temperature and rate of heating shall be such that no permanent damage occurs to the aggregates. Particular care shall be taken that aggregates high in calcium or magnesium content are not damaged by heating. The aggregate shall be screened to specified sizes and conveyed into separate bins ready for mixing with bituminous material.

**401-5.4 PREPARATION OF BITUMINOUS MIXTURE.** Before delivery, the aggregate shall be mixed with the bituminous material at a central mixing plant. The mixture shall be prepared at a temperature as shown in Section 401-2.

The dry aggregates, prepared as specified in Section 401-5.3, shall be combined in the plant in proportionate amounts of each fraction of aggregate required to meet the specified gradation. The quantity of aggregate for each batch shall be determined, measured, and conveyed into the mixer. In case of volumetric proportioning, the size of the grate openings shall be determined and the gates locked in position.

The bituminous material shall be measured by weight or volume and introduced into the mixer at the specified temperature using the lowest range possible for adequate mixing and spreading. For batch mixers, all mineral aggregates shall be in the mixer before the bituminous material is added.

**401-5.5 TRANSPORTATION AND DELIVERY OF THE MIXTURE.** The mixture shall be transported from the mixing plant to the point of use in hauling equipment as per Section 401-4.

The mixture shall be placed at a minimum temperature of 225°F. When mixture is being placed during warm weather, and the ENGINEER has determined that satisfactory results can be obtained at lower temperatures, he may direct that the mixture be mixed and delivered at the lower temperatures.

Loads shall not be sent out so late as to interfere with spreading and compacting the mixture during daylight unless artificial light satisfactory to the ENGINEER is provided.

## SECTION 401 – ASPHALTIC CONCRETE PAVEMENT

The mixture shall be delivered at a temperature within the tolerance specified in the approved mix design.

### **401-5.6 SPREADING AND LAYING**

**(a) Preparation for Placing.** Immediately before placing the bituminous mixture, the existing underlying course shall be cleaned of loose or deleterious materials and tacked in accordance with Section 402.

The mixture shall be laid only upon an approved underlying course which is dry and only when weather conditions are suitable. No mixture shall be placed when air temperature away from the artificial heat is 30°F or lower for AC base course or 40°F or lower for AC surface course, unless so directed by the ENGINEER. The ENGINEER may, however, permit work of this character to continue when overtaken by sudden rains up to the amount which may be in transit from the plant at the time provided the mixture is within the temperature limits specified.

Hauling over material already placed shall not be permitted until the material has been thoroughly compacted as specified and allowed to cool to atmospheric temperature.

**(b) Machine Spreading AC Leveling Course.** The AC leveling course material that has been processed in a plant shall be placed on the prepared underlying course and compacted in layers of the thickness shown on the plans. The depositing and spreading of the material shall commence where designated and shall progress continuously without breaks. The material shall be deposited and spread in lanes in a uniform layer and without segregation of size to such loose depth that when compacted, the layer shall have the required thickness.

The leveling course material shall be spread in a uniform layer of required depth and width and to the typical cross section. The spreading shall be by a self-powered blade grader, mechanical spreader, or other approved method. In spreading, care shall be taken to prevent cutting into the underlying layer. The material shall be bladed until a smooth, uniform surface is obtained, true to line and grade.

When a self-powered blade grader is used, the policy is to not permit the application of the AC leveling course when the atmospheric temperature is less than 75°F. The self-powered blade grader must also be equipped with radial or smooth tires when used for the application of the AC leveling course.

When the depth leveled is greater than one inch, AC surface course shall be applied to a depth within 1 inch or less of finished grade and the remaining portion filled with AC leveling course. The AC leveling course material as spread shall be of uniform grading with no pockets of fine or coarse materials. The material, unless otherwise permitted by the ENGINEER, shall not be spread more than 1,000 square yards in advance of the rolling. Any necessary sprinkling shall be kept within these limits.

## SECTION 401 – ASPHALTIC CONCRETE PAVEMENT

When more than one layer is required, the construction procedure described herein shall apply similarly to each layer.

**(c) Machine Spreading AC Base and Surface Course.** Upon arrival, the AC base or surface course shall be dumped into an approved bituminous paver and immediately spread to the full width required. It shall be struck off in a uniform layer of such depth that when the work is completed, it will have the required thickness and will conform to the grade and surface contour required. The speed of the paver shall be regulated to eliminate the pulling and tearing of the bituminous mat.

The mixture shall be placed in strips of a minimum width of 10 feet. After the first strip or width has been compacted, the second width shall be placed, finished, and compacted in the same manner as the first width. After the second strip has been placed and rolled, a 10-foot straightedge shall be placed across the longitudinal joint to determine if the surface conforms to grade and contour requirements.

Exposed vertical edges of paved strips shall be free of all accumulations of dirt or other foreign material before any mixture is spread in an adjacent lane. If joint faces become dry or dusty, the contact surfaces shall be given a brush coat of asphalt. In lieu of painting the contact surfaces, the CONTRACTOR may use a joint heater approved by the ENGINEER. If the spreading machine should drift from an adjacent lane during construction, the unfilled space shall be carefully filled with fresh hot mixture obtained from trucks or the hopper of the spreading machine. Stealing mixture from that already spread to fill up these areas shall not be permitted.

In limited areas, where due to irregularities or unavoidable obstacles, the use of mechanical spreading and finishing equipment is not practical, the mixture may be hand spread.

When hand spreading is permitted, the mixture shall be dumped on approved dump sheets outside the area upon which it is to be spread and then distributed into place immediately using hot shovels. It shall be spread with hot rakes in a uniformly loose layer to the full width required and of such depth that when the work is completed, it will have the required thickness and will conform to the grade and surface contour shown on the plans.

**(d) AC Patch.** AC patch cuts will be designated and marked by the ENGINEER. The CONTRACTOR shall make all cuts with a saw or other approved method so as to obtain a vertical face on the remaining asphalt. The cuts shall be made to a depth so as not to disturb the remaining asphalt during removal of the patch area. All sawing, milling, asphalt removal and bituminous tack coat shall be incidental to the unit price bid for "AC Patch".

The type of failure shall be determined after the asphalt has been removed and the aggregate base or subgrade is inspected. After the aggregate base or subgrade has been inspected, the CONTRACTOR may be required to enlarge the cut area if the aggregate base or subgrade conditions warrant doing so.

## SECTION 401 – ASPHALTIC CONCRETE PAVEMENT

Areas of AC pavement, aggregate base or subgrade failures shall be repaired to the following dimensions per Standard Detail 400-1.

### **AC Pavement Surface Failure**

The CONTRACTOR may be required to remove the surface course only in areas of surface failures to a maximum depth of two inches or as directed by the ENGINEER. Removal of the pavement failure shall be done by means of a pavement milling machine and in accordance with Section 406. Milling Pavement Surface shall be incidental to the unit price bit for “AC Patch”.

### **AC Pavement Failure**

- A minimum of 4½ inches deep or the depth of the existing pavement (whichever is greater) or as directed by the ENGINEER.
- Pavement removed shall be done in accordance with Section 408 “Asphalt Removal” and disposed of by the CONTRACTOR. Asphalt removal shall be incidental to the unit price bid for “AC Patch”. Replacement of the patch area shall be done as per Standard Detail 400-1 “AC Pavement Failure” in accordance with Section 401-6 “AC Patch” and shall be paid for at the unit price bid for “AC Patch”.
- Replacement of the milled area shall be done in accordance with Section 401-6 “AC Patch” and shall be paid for at the unit price bid for “AC Patch”

### **Subbase/Subgrade Failure**

- Pavement removed shall be made in accordance with Section 408 “Asphalt Removal.” Asphalt removal shall be incidental to the unit price bid for “AC Patch”.
- Excavate to 12 inches minimum or 36 inches maximum depth.
- The excavation shall be done as per Standard Detail 400-1 “Subbase Failure” in accordance with Section 202 “Excavation and Embankments”. The cost of Unclassified Excavation shall be paid for at the unit price bid for “Unclassified Excavation”.
- After excavating the subbase/subgrade failure, the area shall be backfilled with aggregate base, as specified under Section 302, within the pavement thickness to finished grade. Aggregate base shall be paid for at the unit price bid for “Blended Base” or “Class 5 Aggregate Base”.
- The remaining portion of the excavation shall be filled with a minimum of 4½ inches asphalt mix, or the depth of the existing pavement or as directed by the ENGINEER and paid for at the unit price bit for “AC Patch”.

**Utility Cut Patch**

- Pavement removed shall be made in accordance with Section 408 “Asphalt Removal.” Asphalt removal shall be incidental to the unit price bid for “AC Patch”.
- The excavation shall be done as per Standard Detail 400-1 “Utility Cut Patch” in accordance with Section 801.3. The cost of Unclassified Excavation shall be incidental to related bid items.
- After excavating and backfill of utility trench per Section 801-3, the area shall be backfilled with a minimum of 12 inches of aggregate base, as specified under Section 302, within the pavement thickness to finished grade. Aggregate base shall be paid for at the unit price bid for “Blended Base” or “Class 5 Aggregate Base”.
- The remaining portion of the excavation shall be filled with a minimum of 6 inches of asphalt mix, or the depth of the existing pavement or as directed by the ENGINEER and paid for at the unit price bid for “AC Patch”.

The asphalt pavement of streets which have an asphalt overlay on a concrete base shall be repaired in accordance with AC Pavement Failure to a minimum depth of overlay. When the concrete base requires repair, removal shall be done in accordance with Section 602 “Driveway Removal.” Replacement of the concrete shall be done in accordance with Section 602 “6-Inch Concrete Driveway.” The replacement depth shall be equal to the existing concrete pavement thickness with a minimum thickness of 4 inches.

**401-5.7 COMPACTION OF MIXTURES.** After spreading, the mixture shall be thoroughly and uniformly compacted with power rollers. Rolling of the mixture shall begin as soon after spreading as it will bear the roller without undue displacement or micro checking.

Initial rolling shall be done longitudinally. The rollers shall overlap on successive trips. Alternate trips of the roller shall be of slightly different lengths, and cross rolling shall not exceed more than one-half the width of the pavement or crowned sections. The speed of the roller shall at all times be slow to avoid displacement of the hot mixture. Any displacement occurring as a result of reversing the direction of the roller or from any other cause shall be corrected at once by rakes and fresh mixture.

Sufficient rollers shall be furnished to handle the output of the plant. Rolling shall continue until all roller marks are eliminated, the surface is of uniform texture and true to grade and cross section, and a density of at least 91 percent of the maximum theoretical density specified in the mix design per Section 401-2 is obtained.

To prevent adhesion of the mixture to the roller, the wheels shall be kept properly moistened, but excessive water will not be permitted.

## SECTION 401 – ASPHALTIC CONCRETE PAVEMENT

In areas not accessible to the roller, the mixture shall be thoroughly compacted with hot hand tampers, vibratory plate compactors or approved method.

Any mixtures which become loose and broken, mixed with dirt, or in any way defective prior to the application of the finish coat shall be removed and replaced with fresh hot mixture and immediately compacted to conform with the surrounding area. This shall be done at the CONTRACTOR's expense.

### 401-5.8 JOINTS

**(a) General.** The mixture at the joints shall comply with the surface requirements and present the same uniformity of texture, density, smoothness, etc., as other sections of the course. In the formation of all joints, provision shall be made for proper bond with the adjacent course for the specified depth on the course. Joints shall be formed by cutting back on the previous day's run to expose the full depth of the course. The exposed edge shall then be given a coat of tack oil as required by the ENGINEER and the fresh mixture raked against the joint, thoroughly tamped with tampers, and rolled.

**(b) Transverse.** The placing of the course shall be as continuous as possible. The roller shall pass over the unprotected end of the freshly laid mixture only when discontinuing the laying of the course.

**(c) Longitudinal.** The placing of the course shall be as specified and in such a manner that the joint is exposed for the shortest period possible. The joint shall be placed so that it will not coincide with that in the AC base course, binder, or existing surface course by at least one foot.

**401-5.9 SHAPING EDGES.** While the surface is being compacted and finished, the CONTRACTOR shall carefully trim the outside edges of the pavement to the proper alignment. The edges so formed shall be beveled while still hot with the back of the rake or a smoothing iron and thoroughly compacted by tampers or by other satisfactory methods.

**401-5.10 SURFACE TESTS.** Tests for conformity with the specified crown and grade shall be made by the CONTRACTOR immediately after initial compression. Any variation shall be corrected by the removal or addition of materials and by continuous rolling.

The finished surface shall not vary more than 3/8 inch when tested with a 10-foot straightedge applied parallel with or at right angles to the centerline. The surface tolerance for blade laying shall be 3/8 inch in 10 feet.

After the completion of final rolling, the smoothness of the course shall again be tested; the humps or depressions exceeding the specified tolerances or that retain water on the surface shall be corrected immediately as directed by the ENGINEER; this shall be done at the CONTRACTOR's expense.

**401-5.11 DENSITY AND TESTING REQUIREMENTS FOR BITUMINOUS**

**PAVEMENTS.** The CONTRACTOR shall engage an independent testing laboratory approved by the ENGINEER to test the composition of the mixtures, the mineral aggregates, and the in-place density of the mixture.

**(a) Density.** AC Superpave shall be compacted to 91 percent of the maximum theoretical density specified in the mix design per Section 401-2. The density of the compacted bituminous pavement shall be determined in sublots of 1,500 square yards per each lift.

Each day's haul will be considered a "lot," and each "lot" shall be divided into acceptance sublots not to exceed 1,500 square yards, unless the control strip method outlined below is used. Densities per subplot will be taken at random with a minimum of one nuclear density per subplot, and the mean density in each subplot shall equal or exceed the specified density. Sublots for AC patch shall not exceed 150 square yards for areas that are a minimum of 4 feet by 4 feet in size. For areas less than 4 by 4 feet in size, sublots shall not exceed 75 square yards. Density tests shall be required for AC surface course when the depth leveled is greater than one inch. Frequency of tests shall be one per 250 tons AC surface course.

Densities shall be taken by a Nuclear Gauge Tester in accordance with ASTM D2950.

Compaction methods and equipment used shall be approved by the ENGINEER.

During the course of bituminous pavement construction, it may be deemed necessary by the ENGINEER to verify pavement composition and/or the results obtained by the Nuclear Density Tester. This will be accomplished by removing samples of suitable size from the completed pavement. The CONTRACTOR shall remove the samples and replace the pavement at no extra charge. If the pavement is deficient in composition, compaction, or thickness, satisfactory correction shall be made immediately.

Should the CONTRACTOR require any of the above verification sampling, he may do so provided he agrees to assume all costs incurred including the testing of the sample.

**(b) Control Strip Method.** If the ENGINEER determines that, through the CONTRACTOR's efforts and the test results, the specified percent of the mix design density cannot be obtained, a control strip shall be used to establish the density criteria for the particular pavement area involved.

The aggregate base or subgrade on which the control strip is to be constructed shall be approved by the ENGINEER prior to the construction of said strip. The ENGINEER may abandon the control strip criteria or require a new control strip when a change in materials or a change in construction methods is observed.

The control strip shall be constructed with blended materials meeting Specifications and approved by the ENGINEER. The control strip shall cover not less than 300 square

## SECTION 401 – ASPHALTIC CONCRETE PAVEMENT

yards at the specified pavement depth and shall remain in place as part of the completed work.

Compaction of the control strip shall begin as soon as possible after the mixture is placed. Compaction shall be uniform over the entire surface. During compaction, pavement densities will be determined by the CONTRACTOR with a portable nuclear device. When the ENGINEER determines density increases less than 1 pound per cubic foot per roller pass, the rolling shall cease provided a minimum of three roller coverages have been completed. Roller or rollers shall be approved by the ENGINEER. The mean density shall be determined by 10 random density tests within the control strip. The control strip density determination shall be the responsibility of the CONTRACTOR.

The remainder of the work in which the control strip is to govern shall be divided into acceptance strips containing no more than 1,500 square yards. The density of each acceptance strip shall be obtained by the results of five nuclear densities, the mean density of which shall not be less than 98 percent of the control strip density accepted by the ENGINEER. No individual test shall be less than 95 percent of the control strip density.

If the mean density of the acceptance strip does not conform to the requirements stated herein, or if an individual test value does not meet the requirements stated herein, the CONTRACTOR shall continue its compactive effort until the required density is obtained.

It is intended that acceptance density testing will be accomplished while the bituminous mixture is hot enough to permit further densification if such is shown to be necessary.

After the required density has been attained in the acceptance strips, further finish rolling may be necessary to remove roller marks or other surface irregularities.

The ENGINEER reserves the right to require testing of individual areas which are apparently defective based upon visual examination and to reject any area that does not have at least 95 percent of the mean density of the control strip.

All other testing shall be in accordance with the standard specifications, the special provisions contained herein, and the project plans.

**(c) Testing of Aggregate and Bituminous Mixture.** One dry belt sample shall be taken in accordance with NDDOT ND T 2 for each increment of 1,000 tons of bituminous pavement produced with a minimum of one sample per project.. The dry sample shall be tested for gradation per NDDOT ND T 27 and fine aggregate angularity per NDDOT ND T 11 in accordance with Section 401-2 of the Standard Specifications. One dry belt sample and one bituminous mixture sample shall be taken and tested for each increment of 150 tons of AC patching material produced and one for each increment of 100 tons of AC leveling course produced, with a minimum of one per project on each material produced.

## SECTION 401 – ASPHALTIC CONCRETE PAVEMENT

One bituminous mixture sample shall be taken in accordance with NDDOT ND T 2 for each increment of 1,000 tons of bituminous pavement produced with a minimum of one sample per project. The bituminous mixture shall be tested in accordance with Section 401-2 for Theoretical Maximum Specific Gravity NDDOT ND T 209, Bulk Specific Gravity per NDDOT T 116 and Air Voids. The bituminous mixture shall also be tested to determine the bitumen content by extraction in accordance with ASTM D2172. The gradation of the mineral aggregate shall also be determined after the extraction is made. One bituminous mixture sample shall be taken for each increment of 150 tons of AC patch and one for each increment of 100 tons of AC leveling course.

The CONTRACTOR must keep track of daily tonnages of each material produced and a total tonnage to date quantity. The testing laboratory must be notified at least one hour prior to any paving activities. If the CONTRACTOR's paving activities extend beyond 5:00 p.m., the CITY and the testing laboratory shall be notified prior to 4:00 p.m. that day, and not later than 4:00 p.m. on Friday for any anticipated work on the weekend.

**(d) Payment and Reports.** The cost of all said testing shall be considered incidental to other bid items.

The time, locations, depths, and frequency of testing shall be at the discretion of the ENGINEER during construction. Should it become necessary to require an additional number of initial tests over and above the frequency specified herein, the CITY OF BISMARCK will assume the responsibility to perform said additional testing, except as outlined herein under "Compaction."

The CONTRACTOR, however, will be required to assume the cost of all testing to determine the limits of an area not meeting specifications and subsequent retesting of said area after corrections have been completed.

Written reports of all results shall be supplied to the ENGINEER and the CONTRACTOR by the testing laboratory as soon as possible. To expedite construction progress, it is necessary that the CONTRACTOR and ENGINEER be furnished with the results of all tests as soon as testing is completed.

The availability of the independent testing laboratory when needed and speed of testing and reporting are to be considered the responsibility of the CONTRACTOR.

**401-5.12 BITUMINOUS AND AGGREGATE MATERIAL CONTRACTOR'S RESPONSIBILITY.** Samples of the bituminous and aggregate materials that the CONTRACTOR proposes to use, together with a statement of their source and character, shall be submitted to the ENGINEER; approval must be obtained before the use of such material begins. The CONTRACTOR shall require the manufacturer or producer of the bituminous and aggregate materials to furnish material subject to this and all other pertinent requirements of the contract. Only those materials that have demonstrated performance under the proposed design requirements will be accepted.

## SECTION 401 – ASPHALTIC CONCRETE PAVEMENT

The ENGINEER or his authorized representative shall have access at all times to all parts of the paving plant for the purpose of inspecting equipment, conditions, and operation of the plant for verification of weights or proportions and character of materials and to determine temperature maintained in the preparation of the mixtures.

The CONTRACTOR shall furnish vendor's certified test reports for each tanker, carload, or equivalent of bitumen shipped to the project. The report shall be delivered to the ENGINEER before permission is granted for use of the material. The furnishing of the vendor's certified test report for the bituminous material shall not be interpreted as a basis for final acceptance. All such test reports shall be subject to verification by testing samples of material received for use on the project.

**401-5.13 AC TRANSVERSE CRACK LEVELING.** The AC transverse crack leveling is to be applied only to displaced or settled transverse cracks that require leveling. The ENGINEER will mark locations for AC transverse crack leveling. The crack leveling will be completed only after the crack sealing or filling operations are completed. The leveling course shall be applied along the entire crack (if required) with a minimum width of 2 feet or the width of the existing settlement, whichever is greater. A bituminous tack coat must be applied prior to the transverse crack leveling. The material used for AC transverse crack leveling shall be AC leveling course and paid for by "AC Leveling Course".

### **401-6 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107 and as follows:

**401-6.1 AC LEVELING COURSE.** No deduction will be made for the weight of the asphalt cement in the mixture.

**401-6.2 AC SUPERPAVE.** No deduction will be made for the weight of the asphalt cement in the mixture.

**401-6.3 AC PATCH.** No deduction will be made for the weight of the asphalt cement in the mixture.

## SECTION 402 – BITUMINOUS PRIME AND TACK COAT

### 402-1 DESCRIPTION

This item shall consist of supplying and applying bituminous material to a previously prepared, bonded, and/or bituminized binder, leveling, or aggregate base course, AC superpave lift or existing pavement in accordance with these specifications and to the width shown on the typical cross section on the plans.

### 402-2 MATERIALS

**402-2.1 QUANTITY OF MATERIAL.** The approximate amount of bituminous material per square yard for prime or tack coat shall be as provided in the following table. The exact amount shall be as ordered by the ENGINEER.

Material	Amount
Bituminous Prime Coat	0.25 to 0.05 Gal/SY
Bituminous Tack Coat	0.05 to 0.20 Gal/SY

**402-2.2 BITUMINOUS MATERIAL.** The types, grades, controlling specifications, and application temperatures for the bituminous materials are shown in the following table. The specific material to be used shall be designated by special provision or by the ENGINEER. The supplier of the bituminous material shall supply asphalt viscosity charts for the material delivered.

PRIME COATS		
Type and Grade	Specification	Application Temperature
MC-30	ASTM D2027 (MC)	85°F - 140°F
MC 70	ASTM D2027 (MC)	120°F - 175°F

TACK COATS		
Type and Grade	Specification	Application Temperature
SS-1h	ASTM D977	75°F - 130°F
CSS-1h	ASTM D2397	50°F - 130°F

### 402-3 CONSTRUCTION REQUIREMENTS

**402-3.1 WEATHER LIMITATIONS FOR PRIME COAT.** The prime coat shall be applied only when the existing surface is dry or contains sufficient moisture to get uniform distribution of the bituminous material when the pavement temperature is above

## SECTION 402 – BITUMINOUS PRIME AND TACK COAT

60°F and when the weather is not foggy or rainy. The temperature requirements may be waived, but only when so directed by the ENGINEER.

**402-3.2 WEATHER LIMITATION FOR TACK COAT.** The tack coat shall be applied only when the existing surface is dry, the weather is not foggy or rainy, and the atmospheric and existing mat temperature is above 40°F. The temperature requirements may be waived, but only when so directed by the ENGINEER with the use of an approved alternate bituminous material.

**402-3.3 EQUIPMENT.** The equipment used by the CONTRACTOR shall include a self-powered pressure bituminous material distributor and equipment for heating bituminous material.

The distributor shall have pneumatic tires of such width and number that the load produced on the surface shall not exceed 650 pounds per inch of tire width and shall be designed, equipped, and operated so that bituminous material at even heat can be applied uniformly on variable widths of surface at readily controlled rates from 0.05 to 0.5 gallons per square yard. The material shall be applied within a pressure range from 25 to 75 pounds per square inch and with an allowable variation from any specified rate not to exceed 5 percent. Distributor equipment shall include a thermometer for reading temperatures of tank contents, a tachometer, pressure gauges, and volume measuring devices.

**402-3.4 APPLICATION OF BITUMINOUS MATERIAL.** Immediately before applying the tack or prime coat, the full width of surface to be treated shall be swept with a power broom to remove all loose dirt and other objectionable material.

The application of the bituminous material shall be made by means of a pressure distributor at the pressure, temperature, and in the amounts directed by the ENGINEER.

During all applications, the surfaces at adjacent structures shall be protected in such a manner as to prevent their being spattered, marred, or tacked.

Tack coat shall be applied to all cold joints including concrete edges prior to asphaltic pavement construction.

Following the application, the surface shall be allowed to cure without being distributed for such period of time as may be necessary to permit drying out and setting of the tack or prime coat. This period shall be determined by the ENGINEER. The surface shall then be maintained by the CONTRACTOR until the next course has been placed. Suitable precautions shall be taken by the CONTRACTOR to protect the surface against damage during this interval, including any sand necessary to blot up excess bituminous material.

**402-3.5 BITUMINOUS MATERIAL CONTRACTOR'S RESPONSIBILITY.** Samples of the bituminous material that the CONTRACTOR proposes to use, together with a statement as to its source and character, must be submitted and approved before use

## SECTION 402 – BITUMINOUS PRIME AND TACK COAT

of such material begins. The CONTRACTOR shall require the manufacturer or producer of the bituminous material to furnish material subject to this and all other pertinent requirements of the contract. Only satisfactory materials so demonstrated by service tests shall be acceptable.

The CONTRACTOR shall furnish vendor's certificate test reports for each carload or equivalent of bituminous material shipped to the project. The report shall be delivered to the ENGINEER before permission is granted for use of the material. The furnishing of the vendor's certified test report for the bituminous material shall not be interpreted as a basis for final acceptance. All such test reports shall be subject to verification by testing samples of material received for use on the project.

**402-3.6 FREIGHT AND WEIGH BILLS.** Before the final estimate is allowed, the CONTRACTOR shall file with the ENGINEER receipted bills when railroad shipments are made, and certified weight bills when materials are received in any other manner of the bituminous materials actually used in the construction covered by the contract.

Copies of the freight bills and weigh bills shall be furnished to the ENGINEER during the progress of the work.

### **402-4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107 and as follows:

**402-4.1 BITUMINOUS PRIME COAT.** Bituminous Prime Coat shall be measured by weight and converted to gallons at 60°F based on the unit weight shown on the certified analysis report on each car.

**402-4.2 BITUMINOUS TACK COAT.** Bituminous Tack Coat shall be measured by weight and converted to gallons at 60°F based on the unit weight shown on the certified analysis report on each car.

## **SECTION 403 – BITUMINOUS SEAL**

### **403-1 DESCRIPTION**

This work shall consist of a bituminous surface treatment as a wearing course composed of single or multiple applications of bituminous material and aggregate cover placed on the prepared and primed base or properly cured wearing surface in accordance with these Specifications and shall conform to the dimensions and typical cross section shown on the Plans and with lines and grades established by the ENGINEER.

### **403-2 MATERIALS**

**403-2.1 QUANTITY OF MATERIAL.** The amounts of bituminous material, aggregates, and blotter sand per square yard for the bituminous seal shall be determined by the CONTRACTOR as necessary to obtain a finished product in conformity with the plans and specifications.

**403-2.2 COVER AGGREGATE.** This material shall consist of sound, durable particles of gravel and sand, either crushed or uncrushed or a combination of both, and shall be in accordance with the requirements for gradation as per NDDOT Table 816-02 for Class 43.

The aggregate shall be flushed with clear water but not so wet that free water will be draining from aggregate or truck bed before applying.

The sieve analysis will be determined by a wash screening in accordance with ASTM C136.

If bituminous material is changed during construction, the CONTRACTOR shall perform another coating and stripping test prior to utilizing a different cover aggregate blend.

**403-2.3 BITUMINOUS MATERIAL.** The types, grades, and controlling specifications for the bituminous materials are given below. The bituminous material shall be CRS-2P.

All bituminous materials shall meet the requirements of the latest version of the North Dakota Department of Transportation Standard Specifications for Road and Bridge Construction, Section 818. The CONTRACTOR may submit a bituminous material not contained in the above list to the ENGINEER, and the ENGINEER may approve or deny the use of the proposed bituminous material.

### **403.3 CONSTRUCTION REQUIREMENTS**

**403-3.1 WEATHER LIMITATIONS.** Bituminous material shall not be applied to a wet surface or during sand or dust storms.

The CONTRACTOR shall not apply any bituminous material when the pavement surface temperature is less than 60°F and not be anticipated to drop below 35°F within

## SECTION 403 – BITUMINOUS SEAL

the 24 hour cure time, unless approved by the ENGINEER. The CONTRACTOR must delay the application of bituminous material until the atmospheric and pavement surface conditions are satisfactory. No bituminous material shall be placed which cannot be cared for during daylight hours. Materials not placed in compliance with this section will not be paid for.

**403-3.2 EQUIPMENT AND ORGANIZATION.** Each unit required in the execution of these specifications shall be under the continuous supervision of a competent superintendent thoroughly experienced in this type of work. Experienced operators will be required on all equipment used in hauling and applying bituminous material and aggregates.

All equipment necessary to perform this work properly shall be on the project in proper working condition before construction is permitted to start. The CONTRACTOR shall furnish, while applying the seal coat, all barricades, lights, flagmen, or other traffic control devices as necessary to protect crews, equipment, and the public from damage.

The following equipment will be the minimum required for this type of construction, and additional machinery shall be secured if in the opinion of the CONTRACTOR it is necessary to fulfill the conditions of these specifications or to complete the item within the time specified:

(a) The distributor shall have pneumatic tires of such width and number that the load produced on the pavement surface shall not exceed the legal gross vehicle weight, and it shall be designed and operated so that bituminous material at even heat may be applied uniformly on variable widths of surface at readily controlled rates from 0.05 to 2.0 gallons per square yard.

(b) The mechanical spreader shall be capable of depositing the designated amount of aggregate in a smooth, uniform layer or on the freshly deposited bitumen and in such a manner that the wheels of the equipment will not contact any bitumen which has not been covered by the aggregate. The rate of aggregate discharge shall be uniform over the full application width, and whenever necessary, cut-off plates or other approved means shall be provided to reduce the width of spread in suitable increments to meet the job requirements. The spread shall be so adjusted by individual gates over the wheel tracks to allow additional aggregate to be deposited to prevent tracking by the spreader and the trucks.

(c) The blotter sand spreader shall be capable of spreading a thin, uniform layer of sand such as a mechanical truck-mounted type.

(d) The self-propelled pneumatic roller shall consist of pneumatic tires arranged in a manner to provide a satisfactory compacting unit. The roller shall have an effective rolling width of at least 60 inches and shall give a compression of at least 275 pounds per inch of tread width when fully loaded. The wheels shall be staggered on the front and rear axles to provide complete coverage of the area over which the roller travels.

## SECTION 403 – BITUMINOUS SEAL

The CONTRACTOR shall have a minimum of two self-propelled pneumatic rollers available. The rollers shall be the self-propelled type capable of starting, stopping, and reversing direction smoothly, without jerking or backlash, and shall be equipped with positive, accurate steering control.

(e) A power broom or power blower, broom dragging equipment, and equipment for heating aggregate shall be included, when needed.

The CONTRACTOR shall supply such auxiliary equipment as needed.

Bituminous binder and aggregate shall not be spread over a greater yardage than can be rolled and finished in one day's operation.

**403-3.3 APPLICATION OF BITUMINOUS MATERIAL.** Bituminous material shall be applied upon the properly prepared surface at the rate and temperature selected by the CONTRACTOR using a distributor to obtain uniform distribution at all points. The yardage over which the binder is spread in advance of placing the aggregate shall be as determined by the CONTRACTOR. During all applications, the surfaces of the adjacent structures, including curbs, shall be protected in such a manner as to prevent their being splattered, marred, or damaged in any other manner. Splatters shall be removed and mars repaired at the CONTRACTOR's expense. Coverage shall be complete, uniform, and free of "drilling" or "streaking."

The bituminous material shall not be applied to a dusty surface. If normal sweeping methods do not remove dust, the surface shall be flushed with water incidental to this bid item. If water is taken from CITY hydrants, see Section 203. All water shall be incidental to the bituminous seal coat.

A construction joint shall be placed at the start or stop of seal operations which will be continued from or to the joint. This also includes at concrete valley gutters. After the asphalt is applied, the building paper shall be removed and disposed of by the CONTRACTOR.

Aggregates and bituminous mat shall not be allowed to cover any appurtenances such as manhole covers, valve box covers, and valley gutters.

The spray bar shall be shut off instantaneously at each intersection joint to ensure a straight line and the full application of asphalt binder up to the joint.

A hand spray shall be used to apply asphalt binder necessary to touch up all spots missed or inaccessible by the distributor.

The longitudinal joint between the asphalt and the concrete gutter must be included when the bitumen is applied. A maximum overspray of 1 inch will be allowed on the concrete gutter. All vegetation and loose debris shall be removed from the longitudinal joint prior to the bitumen application.

## SECTION 403 – BITUMINOUS SEAL

The bitumen shall be applied so that when covered, transverse and longitudinal joints of successive applications will not result in ridges or depressions and will be smooth and consistent with the adjacent surface of the completed treatment.

**403-3.4 APPLICATION OF AGGREGATE MATERIAL - GENERAL METHODS.** The CONTRACTOR shall determine when to place the cover aggregate on the applied bituminous material. The timing of when the cover aggregate is placed on the applied bituminous material varies with the type and grade of bituminous material. The CONTRACTOR shall perform test strips and include this timing parameter. Cover aggregate shall be spread uniformly over the bituminous material with the aggregate equipment specified. Trucks spreading aggregate shall be operated backward so that the bituminous material will be covered before the truck wheels pass over it. The aggregate shall be spread in the same width of application as the bituminous material and shall not be applied in such thickness as to cause blanketing. Backspotting or sprinkling of additional aggregate material and spraying additional bituminous material over areas that show up having insufficient cover of bitumen shall be done by hand whenever necessary. Additional spreading of aggregate material shall be done by means of a broom drag or other approved method.

Pneumatic rollers shall be used immediately after the aggregate is spread. The blotter sand shall be applied as necessary, and rolling shall be continued until no more aggregate material can be worked into the surface. Further brooming and rolling on the strip being placed on adjacent strips previously placed shall be done as often as necessary to keep the aggregate material uniformly distributed. These operations shall be continued until the surface is evenly covered and cured. Roller shall not be of such weight which crushes the aggregate particles.

Succeeding applications shall not be applied until the preceding application has set and excess aggregate has been removed. If dust, dirt, or other foreign matter accumulates on the surface between the applications, the CONTRACTOR shall be required to sweep and clean the surface as specified herein. The bituminous material and the aggregate shall be spread upon the clean and properly cured surface and handled as required. Extreme care shall be taken in all applications to avoid brooming or tracking dirt or any foreign matter on any portion of the pavement surface under construction. Traffic shall be signed for a restricted speed limit of 15 miles per hour during the rolling and for 24 hours after the rolling has been completed. The CONTRACTOR may sign the streets for No Parking provided the City of Bismarck Traffic Engineer approved signs are placed 24 hours or more prior to the beginning of operations. The CONTRACTOR must document daily which streets are signed and during what time period. The CONTRACTOR must also notify the Police Department, Fire Department, and ambulance service prior to street closures.

It shall be the CONTRACTOR's responsibility to contact the Police Department regarding vehicles in violation of parking restrictions.

## SECTION 403 – BITUMINOUS SEAL

Coordination between the CONTRACTOR and the Police Department is essential. The CONTRACTOR shall notify the Police Department at least two hours before vehicles need towing, so the Police Department has adequate time to make arrangements.

No towing of vehicles shall be permitted unless authorized by the Police Department.

Signs shall be removed within 24 hours after rolling is complete or whenever construction operations cease for more than 24 hours, except as directed by the ENGINEER. A recommended No Parking sign is on file at the Engineering Department.

A small crew and proper equipment shall be available to control bleeding of seal oil for a period of 30 days after the date of application. If bleeding occurs during the maintenance period and after final sweeping, the CONTRACTOR shall control bleeding by spreading light coats of blotter sand, which will be paid for under Section 403-4 "Blotter Sand." Blotter sand shall not be applied in anticipation of bleeding, but only after bleeding actually occurs. The crew and equipment for controlling bleeding shall be available during the 30-day period at all times, including weekends and nights.

Alternate materials, approved by the ENGINEER, may be used as a substitute in lieu of blotter sand to control the bleeding.

All surplus aggregate shall be swept off the surface and removed prior to acceptance of the work. The removal of excess cover aggregate shall be accomplished by the CONTRACTOR using a pickup-type sweeper. Appurtenances such as manhole covers, valve box covers, and valley gutters shall not be covered with the bituminous seal. Any appurtenance covered shall be cleaned to the satisfaction of the ENGINEER prior to acceptance of the project.

Removal of excess cover aggregate shall begin within 24 hours of application. Removal operations shall not dislodge embedded aggregate. The CONTRACTOR may salvage and reuse the clean aggregate at the discretion of the ENGINEER.

The cover aggregate picked up shall become the property of the CONTRACTOR and shall be removed from the project site by the end of each work day. The CONTRACTOR's responsibility for adherence of an acceptable amount of the aggregate in the bituminous material shall not be waived at any time.

**403-3.5 CORRECTION OF DEFECTS.** Any defects, such as raveling, low centers, lack of uniformity, or other imperfections shall be corrected to the satisfaction of the ENGINEER.

All defective materials resulting from overheating, improper handling, or application shall be removed by the CONTRACTOR and replaced with approved materials as provided for in these specifications.

Damage by a third party, such as vehicle tracking or skidding after the seal coat has been applied and appropriate traffic control measures including flag persons are in

## SECTION 403 – BITUMINOUS SEAL

place, shall be corrected to the satisfaction of the ENGINEER at the cost of the CITY. All replacement sealing must be done by August 15 of any calendar year except by written permission by the ENGINEER. The replacement of Bituminous Seal Coat damaged by a third party shall be measured in place and paid for by the square yard at unit price bid for “Bituminous Seal Coat.” The cost of the original damaged bituminous seal coat will also be paid by the square yard at the unit price for “Bituminous Seal Coat.”

**403-3.6 BITUMINOUS MATERIAL CONTRACTOR'S RESPONSIBILITY.** Samples of the bituminous materials that the CONTRACTOR proposes to use, together with a statement as to their source and character, shall be submitted to the ENGINEER.

The CONTRACTOR shall furnish vendor's certified test reports for each carload, or equivalent, of bitumen shipped to the project. The report shall be delivered to the ENGINEER before permission is granted for use of the material. The furnishing of the vendor's certified test report for the bituminous material shall not be interpreted as a basis for final acceptance nor shall it relieve the CONTRACTOR from responsibility for any failures in the project. All such test reports shall be subject to verification by sample testing. Tests shall be by an approved independent testing facility. The CONTRACTOR shall provide aggregate gradations for each type of aggregate provided for each 500-ton lot or portion of lot provided for the project. Tests shall be performed by an approved independent testing facility.

**403-3.7 TEST SECTION.** The CONTRACTOR shall determine an area of suitable size within the project to use to calibrate the equipment and determine the best method of rolling. It shall be anticipated to have some delays in the operation at this point to evaluate the results. There shall be no additional compensation for these delays.

**403-3.8 ACCEPTANCE OF SEAL COAT - WARRANTY.** The CONTRACTOR warrants a completed seal coat project that complies with the specifications and that remains in place and performs as intended at the time of acceptance and during the one year warranty period. Compliance with these specifications and/or acceptance of the completed bituminous seal coat for final payment as being constructed in accordance with these specifications does not relieve the CONTRACTOR from the responsibility to repair any portions where the bituminous seal coat has failed or not remained in place during the term of the contract and its one year warranty period. The warranty provided by the CONTRACTOR shall be a “performance warranty” and shall guarantee a completed project in accordance with the plans and specifications at the time of acceptance and final payment and for one year after the time of acceptance and final payment. The CONTRACTOR shall provide this warranty regardless of fault or the cause of such failure except for damage caused by a third party through no fault of the CONTRACTOR. The ENGINEER’s representative and a representative of the CONTRACTOR shall review this project prior to the one year warranty period expiration and determine any areas to be repaired. Acceptance of the project shall be deemed to be “final” at the expiration of the warranty period.

## SECTION 403 – BITUMINOUS SEAL

### **403.4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107 and as follows:

**403-4.1 BITUMINOUS SEAL COAT.** Bituminous material and cover aggregate shall be measured and paid as "Bituminous Seal Coat" complete, in place, and accepted by the ENGINEER.

## SECTION 404 – SCRUB SEAL

### 404-1 DESCRIPTION

The work shall consist of furnishing all materials, equipment, labor, and preparation necessary for the application of the polymer modified rejuvenating emulsion (PMRE) scrub seal. The applied material shall completely seal the pavement surface and provide a uniform textured surface suitable for placement of an aggregate cover material in accordance with these specifications and shall conform to the dimensions and typical cross section shown on the plans and with lines and grades established by the ENGINEER.

### 404-2 MATERIALS

**404-2.1 BITUMINOUS MATERIAL.** The types, grades, and controlling specifications for the bituminous materials are given below. The bituminous material shall be CRS-2P.

All bituminous materials shall meet the requirements of the latest version of the North Dakota Department of Transportation Standard Specifications for Road and Bridge Construction, Section 818. The CONTRACTOR may submit a bituminous material not contained in the above list to the ENGINEER, and the ENGINEER may approve or deny the use of the proposed bituminous material.

**404-2.2 COVER AGGREGATE.** Cover aggregate shall conform to Section 403.

**404-2.3 POLYMER MODIFIED REJUVENATING EMULSION (PMRE).** The PMRE for scrub seal shall meet the requirements of the following table and shall be composed of a polymer modifier, a petroleum based rejuvenating agent, and asphalt.

The CONTRACTOR shall submit certifications that the PMRE meets the requirements of this specification. Certifications and test results on the emulsion must be submitted and approved by the ENGINEER prior to supplying material. The ENGINEER will not accept test results dated more than 90 days prior to the date of bid opening.

Test on Emulsion	Test Method	Specification
Viscosity @ 50°C (SFS)	AASHTO T59	50-400
pH	ASTM E70	< 4.0
Sieve, w%, max.	AASHTO T59	0.1
Residue, w%, min.	AASHTO T59	65
Oil distillate, w%, max. <sup>(1)</sup>	AASHTO T59	0.5
<b>Test on Residue from Distillation</b>		

## SECTION 404 – SCRUB SEAL

Penetration @ 4°C, dmm, min.	AASHTO T49	20 to 70
Elastic Recovery @ 25°C, %, min.	AASHTO T301	65
Toughness @ 25°C, N-m (in-lbs)	ASTM 5801	8.2 (75)
Tenacity @ 25°C, N-m (in-lbs)	ASTM 5801	5.6 (50)
Ductility @ 4°C, 5cm/min, cm, min.	AASHTO T51	30
<b>Test on Rejuvenating Agent:</b>		
Viscosity, 140°F, CST	ASTM D2170	50-175
Flash Point, F, COC, min.	ASTM D92	380
Saturate, % by wt., max.	ASTM D2007	30
Asphaltenes, %, max.	ASTM D2007	1.0
<b>Test on Rejuvenating Agent RTFOT Residue</b>		
Weight Change, %, max.	ASTM D2872	4.0
Viscosity Ratio, max.	ASTM D2170	3.0

**Notes:**

1. Distillation temperature is 177°C (350°F). Following Table 2, AASHTO T59 section 6.4.5. Elastic Recovery @ 10°C (50°F): Hour glass sides, pull 20 cm hold 5 minutes then cut, let sit one (1) hour.

**404-2.4 BLOTTER SAND.** Blotter sand shall conform to Section 403.

### 404.3 CONSTRUCTION REQUIREMENTS

**404-3.1 PREPARATION FOR SCRUB SEAL.** All required asphalt patching, concrete repairs, and weed eradication, paid for by the respective bid items, shall be completed prior to scrub seal operations. Concrete and asphalt crack sealing operations shall be determined by the ENGINEER

Before scrub seal operations, each random cracks shall be thoroughly blown out to a depth of ½ inch of all dust, dirt, debris, or other foreign matter using a high-velocity jet of compressed air with a minimum airflow of 185 cfm and 120 psi at the air nozzle. The nozzle shall be no less than ½ inch inside diameter utilizing a commercial grade air compressor. A leaf blower shall NOT be an acceptable substitute for compressed air. The crack shall be clean and dry during scrub seal operations.

The CONTRACTOR shall remove all existing thermoplastic and preformed patterned striping, legends, and raised pavement markers within the scrub seal limits no more than seven (7) days prior to scrub seal operations.

## SECTION 404 – SCRUB SEAL

Before placing the scrub seal, the pavement surface shall be cleaned by sweeping, flushing or other means necessary to remove all loose particles of paving and all dirt and all other extraneous material that cannot be removed during the final sweeping.

Prior to the scrub seal operation, all drain inlet covers, manhole casting covers, gate valve covers and all other utility covers shall be protected from the CONTRACTOR's scrub seal operations by applying a sheet of plastic over the exposed facilities, or other methods approved by the ENGINEER. All traces of plastic, residual emulsion and aggregate shall be removed from covered objects after the application of the scrub seal and/or prior to final inspection of the project.

Immediately prior to the scrub sealing operations, the CONTRACTOR shall sweep the entire pavement surface with vacuum assisted pick-up brooms, or approved method.

**404-3.2 WEATHER LIMITATIONS.** PMRE shall not be applied to a wet surface or during sand or dust storms.

The PMRE shall be applied when mat temperature is 60 degrees Fahrenheit and rising. The PMRE shall not be placed if the ambient temperature during the 24-hour curing period is expected to be below 35 degrees Fahrenheit. The termination time of application shall be determined by the ENGINEER. No PMRE shall be placed which cannot be cared for during daylight hours. PMRE not placed in compliance with this section will not be paid for.

Scrub seals shall not be applied after September 1 of any calendar year except by permission by the ENGINEER.

**404-3.3 EQUIPMENT AND ORGANIZATION.** Equipment and organization shall conform to Section 403 with the following additions:

**Scrub Broom:** A scrub broom as described herein shall be used to scrub the emulsion after application. The scrub broom frame shall be constructed of metal. The scrub broom shall be attached to and towed by the distributor truck. The scrub broom shall be equipped with a means of mechanically raising and lowering the entire scrub broom assembly at designated points of startup and completion. It shall be towable in the elevated position to the next area of construction. The weight of the broom assembly shall be such that it does not squeegee the emulsion off the roadway surface, but carries a head of emulsion in front of the broom.

The main body of the scrub broom shall have a minimum frame size of 6 feet 9 inches wide and 8 feet long but not to exceed a maximum of 8 feet wide and 10 feet long. The scrub broom frame members nearest and furthest, parallel to the back of the distributor truck, and diagonal frame members shall be equipped with street brooms. The nearest and furthest members, parallel to the back of the distributor truck, shall have broom heads angled at 10 to 15 degrees off the centerline of the supporting member. The diagonal members shall cross at the centerline of the main body and shall have broom

## SECTION 404 – SCRUB SEAL

heads attached in line with the centerline of the supporting member. Each individual street broom attached to the frame members shall be a minimum of 3.5 inches wide x 6.5 inches high x 16 inches long and have stiff nylon bristles. Bristle height shall be maintained at a minimum of five (5) inches. The scrub broom shall be equipped with a minimum of two hinged wing assemblies attached to the main body, not to exceed 4.5 feet per side, with parallel and diagonal members in line with the main body members and equipped with street brooms. The purpose of the maximum rigid frame width and the hinged wing extensions is to provide an overall maximum width of 16 feet and maintain the scrubbing process evenly as contours and cross-sections change across the existing road surface.

The CONTRACTOR must supply a scrub broom as described herein for the purpose of scrubbing the PMRE. If the CONTRACTOR fails to supply the scrub broom as specified, the project shall be shut down until such time that the proper equipment is supplied. Shut downs resulting from the failure to provide the specified equipment shall not excuse the CONTRACTOR from the provisions of contract working days or completion dates.

**404-3.4 APPLICATION OF PMRE.** The PMRE for scrub seal shall be applied in conformance with these special provisions and Section 403.

The PMRE shall be applied to the pavement surface by a distributor truck at a rate of 0.30 to 0.45 gallons per square yard. The recommended applications rate shall be 0.40 gallons per square yard. The PMRE application rate may be adjusted up or down. The exact application rate shall be determined by the pavement surface condition and aggregate used and recommended by the CONTRACTOR and approved by the ENGINEER. The asphalt emulsion for scrub seal when applied shall be of temperature of 110°F to 180°F or per manufacturer's recommendation. For smaller areas the emulsion may be applied with a wand.

The PMRE shall be applied up to the lip of the gutter with a maximum overspray of one (1) inch on the concrete gutter. The scrub broom shall pass zero (0) inches to four (4) inches from the lip of the gutter. The edges of the limits of the scrub seal application on both sides of the street shall be maintained in a neat and uniform line. Scrub seal shall not be applied on curb and gutters, driveways, or valley gutters. All cleanup shall be the responsibility of the CONTRACTOR with no additional compensation. Immediately following the application of the PMRE to the road surface, the material shall be scrubbed with a scrub broom for the purpose of forcing the emulsion into the existing surface and distributing the emulsion evenly over variable road surface contours.

The application of the PMRE shall cease prior to the end of the road section or intersection. The remaining PMRE carried by the scrub broom shall be dragged out to the end of the section. Any remaining PMRE required to complete the road section shall be applied by the distributor to ensure the entire road section receives the specified PMRE rate required for cover aggregate retention.

**404-3.5 APPLICATION OF AGGREGATE MATERIAL - GENERAL METHODS.**

Application of aggregate material shall conform to Section 403 with the following additions:

The application rate shall be between 20 to 35 pounds per square yard. The recommended application rate shall be 30 pounds per square yard. The cover aggregate application rate may be adjusted up or down so that no “bleed through” occurs during rolling or as recommended by the CONTRACTOR and approved by the ENGINEER. The application of cover aggregate shall immediately follow the application of the PMRE.

The CONTRACTOR shall provide aggregate gradations for each type of aggregate provided for each 500-ton lot or portion of a lot provided for the project. Tests shall be performed by an approved independent testing facility.

Removal of excess cover aggregate shall be done within twenty-four (24) hours after the scrub seal has been applied unless approved or directed by the ENGINEER. During the sweeping process the CONTRACTOR shall use a backpack blower to clear driveways, gutters, and sidewalk of excess aggregate. The excess cover aggregate shall be removed and become the property of the CONTRACTOR.

Stockpiles shall not be allowed within the project limits or City right of ways. Arrangements for stockpile sites shall be the responsibility of the CONTRACTOR.

**404-3.6 CORRECTION OF DEFECTS.** Correction of defects shall conform to Section 403.

**404-3.7 PMRE MATERIAL CONTRACTOR'S RESPONSIBILITY.** The furnishing of the vendor's certified test report for the PMRE shall not be interpreted as a basis for final acceptance nor shall it relieve the CONTRACTOR from responsibility for any failures in the project.

**404-3.8 TEST SECTION.** Test section shall conform to Section 403.

**404-3.9 ACCEPTANCE OF SEAL COAT - WARRANTY.** Acceptance and warranty shall conform to Section 403.

**404.4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107 and as follows:

**404-4.1 SCRUB SEAL SITE PREPARATION.** Bid item shall be measured and paid per plan quantity by measuring from edge of asphalt to edge of asphalt. Site preparation shall include crack cleaning, covering of inlets, manholes, and gate valve castings, sweeping, and all other items as required for preparation for scrub seal.

## SECTION 404 – SCRUB SEAL

**404-4.2 SCRUB SEAL COVER AGGREGATE.** Bid item shall be measured and paid per plan quantity.

## SECTION 405 – FOG SEAL

### 405-1 DESCRIPTION

This work shall consist of furnishing asphalt emulsion, surface preparation, and sealing surfaces by means of a bituminous distributor.

### 405-2 MATERIALS

**405-2.1 QUANTITY OF MATERIAL.** The approximate amount of bituminous material per square yard for fog seal shall be as provided in the following table. The exact amount shall be as determined by the ENGINEER.

#### Material Amount

Material	Residual Rate Gal/yd <sup>2</sup>
Bituminous Fog Seal	0.08 to 0.12

**405-2.2 BITUMINOUS MATERIAL.** Bituminous materials for fog seal shall be as per the following table, unless otherwise approved by the ENGINEER. The supplier of the bituminous material shall supply asphalt viscosity charts for the material delivered.

Fog Seals		
Type and Grade	Specification	Application Temperature
CSS-1h	ASTM D2397	50°F - 130°F

**405-2.3 BLOTTER SAND.** Blotter sand shall be as per section 403.

### 405.3 CONSTRUCTION REQUIREMENTS

**405-3.1 APPLICATION.** Application of Fog Seal shall conform to Sections 402-3.3 through 3.6.

**405-3.2 FOG SEAL WEATHER LIMITATIONS.** Application of bituminous fog seal material shall be applied immediately after performing the final sweeping and when the surface is dry, the weather is not foggy or rainy, and the atmospheric and existing mat temperature is at 60°F and rising. Application of the fog seal shall only occur during daylight hours and shall be completed at least 2 hours before sunset. Fog seal operations shall be suspended prior to probable rainfall and shall not be applied during inclement weather. Sustained winds shall be less than or equal to 10 miles per hour.

**405-3.3 FOG SEAL TRAFFIC REQUIREMENTS.** During fog seal operations traffic control measures shall take place to protect the freshly applied emulsion until it is cured to safe condition to prevent tracking. Traffic volume should determine the type and

## SECTION 405 – FOG SEAL

extent of traffic control that shall be required. Traffic shall be maintained on all roadways unless approved by ENGINEER with the following exception: the CONTRACTOR may utilize flaggers, or other approved methods. Traffic may be reduced to one lane with approval from the ENGINEER. Flaggers shall conform to section 1211. Traffic shall only be allowed on a bitumen treated surface after the bitumen has penetrated and dried. All labor, materials, and equipment necessary required for traffic control shall be included in price bid for “Traffic Control”.

### **405.4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107 and as follows:

**405-4.1 FOG SEAL.** Bid item shall be measured by the undiluted weight of bituminous material, which shall then be converted to gallons at 60°F based on the certified analysis report on each car.

## **SECTION 406 – MILLING PAVEMENT SURFACE**

### **406-1 DESCRIPTION**

This work consists of improving the profile, cross slope, and surface texture of an existing pavement surface.

### **406-2 EQUIPMENT**

The equipment for milling and texturing the pavement shall be a power-operated, self-propelled planer or grinder capable of removing pavement surface to the required depth, profile, cross slope, and surface texture. The machine shall be capable of accurately establishing profile grades by reference to the existing pavement or from an independent grade control, and shall positively control the cross slope. The machine shall be of size, shape, and dimensions which do not interfere with safe traffic passage adjacent to the work. The milling head shall have a minimum width of 8 feet. The machine shall have a control system to automatically control the elevation and transverse slope of the milling head. A 15-foot minimum length skid, rolling straightedge, or other approved device shall be used to establish the grade reference for control of the milling head. The system shall permit the grade preference device to operate on either side of the milling machine and shall maintain the desired transverse slope regardless of changes in the elevation of the milling head.

Conveyors capable of side, rear, or rear on front loading shall be provided with the necessary equipment to transfer the milled material from the roadway to a truck.

### **406-3 CONSTRUCTION REQUIREMENTS**

The milling shall be started at the centerline of the pavement and proceed on a longitudinal line parallel to the centerline. Succeeding passes shall progress toward the outer edge of the pavement unless a different sequence of operation is permitted by the ENGINEER. The CONTRACTOR shall make every effort to complete the milling operations on the full width of each street so that it is open to traffic at the end of each day, unless otherwise approved by the ENGINEER. The milled depth shall be gradually tapered to the original pavement surface prior to opening to traffic. Before overlaying, the gradual taper to the original pavement surface shall be milled out transversely to produce a vertical cut.

The completed milled surface shall be free from transverse and longitudinal irregularities exceeding 1/4 inch when measured with a 10-foot straightedge.

## SECTION 406 – MILLING PAVEMENT SURFACE

The CONTRACTOR shall clean the milled surface by brooming and remove all equipment and materials prior to opening to traffic.

Millings shall become property of the CONTRACTOR and removed from the site. All equipment necessary for removal of milled material will be furnished by the CONTRACTOR.

Machine exhaust shall not damage or scorch any parts of trees.

The CONTRACTOR shall mill around appurtenances such as manhole and valve box castings without removing those appurtenances. If any asphalt remains on the face of the exposed curb and gutter section or radii around appurtenances, it must be removed to a depth of the milled surface. Appurtenances in the driving lanes shall be wedged with asphalt millings which shall be removed prior to the overlay. Appurtenances not wedged shall be marked with a Type II barricade. The measurement and payment will be in conjunction with the milling pavement surfacing.

### **406-4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107 and as follows:

**406-4.1 MILLING PAVEMENT SURFACE.** Milling Pavement Surface shall be measured to the nearest 0.1 ton of material weighed and placed in an approved stockpile complete, in place, and accepted by the ENGINEER. Loading, hauling, and stockpiling will not be measured and will be considered incidental. The labor, equipment, brooming, and cleaning before and after milling, water used in milling, and deposit of the milled material in a hauling unit will not be measured for payment and shall be included in the price bid.

## SECTION 407 – CRACK TREATMENTS

### 407-1 DESCRIPTION

This work shall consist of applying a crack sealant material into or above existing cracks to prevent the intrusion of water and incompressible material into the cracks and to reinforce the adjacent pavement. There are two methods of crack treatments: crack sealing and crack filling. The ENGINEER shall determine which cracks are candidates for which method of crack treatment.

### 407-2 METHODS

**407-2.1 CRACK SEALING.** This method of crack treatment shall be utilized when the crack shows significant signs of vertical or horizontal movement, or where crack edges may exhibit edge deterioration or displacement.

**407-2.2 CRACK FILLING.** This method of crack treatment shall be utilized when the crack shows very little sign of vertical or horizontal movement.

### 407-3 MATERIALS

The types of materials essentially comprise three material groups according to their composition and manufacturing process. The principal material groups and types are as follows:

- a. Cold-applied thermoplastic bituminous materials.
  1. Liquid asphalt (emulsion).
  2. Polymer-modified liquid asphalt.
- b. Hot-applied thermoplastic bituminous materials.
  1. Asphalt cement.
  2. Fiberized asphalt.
  3. Rubberized asphalt.
  4. Low-modulus rubberized asphalt.
- c. Chemically cured thermosetting materials.
  1. Self-leveling silicone.

Asphalt cutbacks, mineral-filled asphalts, and sand-asphalt mixtures will not be accepted.

The following table shows the material types that possess most of the above properties. It also shows the recommended application methods and requirements for each type of material used.

## SECTION 407 – CRACK TREATMENTS

Material Type	Applicable Specifications	Recommended Application
Asphalt Emulsion	ASTM <sup>b</sup> D977, AASHTO <sup>c</sup> M140, ASTM D2397, AASHTO M208	Filling
Asphalt Cement	ASTM D3381, AASHTO M20, AASHTO M226	Filling
Fiberized Asphalt	Manufacturer's recommended specs	Filling
Polymer-Modified Emulsion	ASTM D977, AASHTO M140, ASTM D2397, AASHTO M208	Filling
Asphalt Rubber	State specs, ASTM D5078	Sealing
Rubberized Asphalt	ASTM D1190, AASHTO M173, Fed SS-S-164	Sealing
Low-Modulus Rubberized Asphalt	State-modified ASTM D3405 specs	Sealing
Self-Leveling Silicone	ASTM D5893	Sealing

- a. Emulsion and Asphalt Cement Sealants.  
This material shall be placed flush in an unrouted, non-working crack.
- b. Rubberized Asphalt Sealants.  
This material shall be placed flush or overbanded in routed, working cracks.
- c. Self-Leveling Silicone Sealants.  
This material shall be placed recessed in routed, working cracks.
- d. Fiberized Asphalt Sealants.  
This material shall be placed overbanded in unrouted, working cracks.

### 407-4 PLACEMENT CONFIGURATION

Sealant and filler materials can be placed in numerous configurations. These placement configurations are grouped into six categories.

**(a) Flush Fill.** This configuration places the material into the existing unrouted crack and the excess material is struck off. Standard Detail 400-2(A) illustrates the flush fill method.

**(b) Reservoir.** This configuration places the material only within the confines of the routed crack. The material placed is either flush with or slightly below the pavement surface. Standard Details 400-2(C) and 400-2(E) illustrate the reservoir-type method.

**(c) Overband.** This configuration places the material into and over an unrouted crack. The excess material shall then be squeegeed to straddle the crack to a minimum width of 1½ inches on either side. Standard Detail 400-2(B) illustrates the overband method.

## SECTION 407 – CRACK TREATMENTS

**(d) Combination (Reservoir and Overband).** This configuration places the material into and over a routed crack. The excess material shall then be squeegeed to straddle the crack to a minimum width of 1½ inches on either side. Standard Details 400-2(D) and 400-2(F) illustrate the combination method.

**(e) Bond Breaker Material.** If the crack continues below the routed crack, a bond breaker material, nonabsorbent closed cell, such as polyethylene foam backer rod, shall be placed at the reservoir bottom of a working crack prior to the sealant application. The backer rod prevents the sealant material from running down into the crack during application. The backer rod material must be a minimum of 25 percent wider than the width of the crack reservoir for it to maintain its vertical position and to provide shape for the material. Standard Details 400-2(E) and 400-2(F) illustrate the placement of the backer rod material.

**(f) Routed/Sawn Cracks.** Working cracks that are relatively straight and are accompanied by edge deterioration are candidates for crack cutting. Crack cutting shall be performed in such a manner so as not to create any additional damage to the existing pavement. High-production machines that follow cracks well and produce minimal spalls or fractures shall be equipped with controls for varying the depth of the cut and the width settings. Standard Details 400-2(C) through 400-2(F) illustrate crack cutting dimensions.

### 407-5 MATERIAL HANDLING

The crack sealant compound shall be packaged in sealed containers. Each container shall be clearly marked with the name of the manufacturer, the trade name of the sealant, the type of sealant, the weight, the manufacturer's batch and lot number, the pouring temperature, and the safe heating temperature.

Prior approval of any specific sealant material shall be required before it can be used on the project.

A copy of the manufacturer's recommendations pertaining to the heating and application of the joint sealant material shall be submitted to the ENGINEER before the commencement of work. These recommendations shall be adhered to and followed by the CONTRACTOR. The temperature of the sealer in the field application equipment shall not exceed the safe heating temperature recommended by the manufacturer. Any given quantity of material shall not be heated at the pouring temperature for more than six hours and shall never be reheated. Material shall not be placed if the temperature is below the manufacturer's recommended minimum application temperature.

Mixing of different manufacturers' brands or different types of sealant shall be prohibited.

Sealant materials may be placed during a period of rising temperature after the air temperature in the shade and away from artificial heat has reached 40°F and indications

## SECTION 407 – CRACK TREATMENTS

are for a continued rise in temperature. During a period of falling temperature, the placement of sealant material shall be suspended when the air temperature in the shade and away from artificial heat reaches 40°F. Sealants shall not be placed when the weather or roadbed conditions are unfavorable.

### 407-6 CRACK TREATMENT PROCEDURES AND EQUIPMENT

The following table shows the required crack treatment equipment characteristics and recommendations.

Operation	Type of Equipment	Recommendations
Crack Cutting (if required)	Vertical-Spindle Router	Use only with sharp carbide-tipped or diamond router bits
	Rotary-Impact Router	Use only with sharp carbide-tipped router bits
	Random Crack Saw	Use only on fairly straight cracks Diamond blade saw, 200-mm maximum diameter
Crack Cleaning/ Drying	Blowers (Backpack & Power-Driven)	<b>Not recommended</b> - Insufficient blast velocity (60 to 100 m/s)
	Air Compressor	Equipped with oil and moisture filters Pressure - 690 kPa minimum Flow - 0.07 m <sup>3</sup> /s minimum Velocity - 990 m/s minimum
	Hot-Air Lance	Velocity - 610 m/s minimum Temperature - 1370°C minimum No direct flame on pavement <u>Highly Recommended</u> Velocity - 915 m/s minimum Temperature - 1650°C minimum
	Sandblaster	Acceptable air compressor (minimum 690 kPa pressure and 0.07 m <sup>3</sup> /s flow) Minimum 25-mm-inside-diameter lines and 6-mm-diameter nozzle
	Wirebrush	Do not use with worn brushes Not recommended for cleaning previously-treated cracks as there is a tendency to smear material
Material Installation	Pour Pots	Not recommended for production operations
	Asphalt Distributor	Not suitable for fiber- or rubber-modified asphalt materials
	Melter-Applicator	Direct-heat kettles not suitable for fiber- or rubber-modified asphalt materials Indirect-heat kettles should be equipped with: * Double-boiler, mechanical agitator with

## SECTION 407 – CRACK TREATMENTS

		separate automatic temperature controls for oil and melting chamber * Sealant heating range to 230°C * Full-sweep agitator * Accurately calibrated material and heating oil temperature gauges
	Backer Rod Installation Tools	Maintains proper recess Does not damage backer rod
	Silicone Pump & Applicator	Flow Rate - 0.25 L/s minimum Hose line with Teflon; all seals and packing made from Teflon
Material Finishing	Squeegee	Heavy-duty, industrial U- or V-shaped
Blotting (if required)	Paper Wand	To prevent tracking

If tracking of the sealant is present, blotting or tissinging will be required. Blotting may consist of sand limestone dust or crusher dust placed directly on top of the treatment material.

### **407-7 TRAFFIC CONTROL**

The CONTRACTOR shall be responsible for all traffic control devices needed for the completion of the crack treatment operation. Traffic control shall conform to Section 1211.

An approved traffic control plan shall be submitted 3 days prior to its use. Traffic control plan and devices shall be considered incidental to other bid items. The CONTRACTOR shall broom off the excess debris and remove the traffic control devices after the crack treatment operations are completed.

### **407-8 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107.

## **SECTION 408 – ASPHALT REMOVAL**

### **408-1 DESCRIPTION**

This work consists of removing and disposing of existing AC pavement surfacing.

### **408-2 EQUIPMENT**

The CONTRACTOR shall use a saw, milling wheel, or asphalt cutting wheel to make all pavement cuts. The CONTRACTOR shall furnish all equipment for cutting, removing, loading, and hauling removed asphalt to the designated unloading site.

### **408-3 CONSTRUCTION REQUIREMENTS**

All asphalt cuts shall be made to maintain a vertical face on the remaining asphalt which shall be maintained until the pavement is replaced and accepted by the ENGINEER. Pavement cuts shall be as designated on plans or as marked by the ENGINEER. Any removal and replacement beyond the area specified on plans or marked by the ENGINEER shall be the responsibility of the CONTRACTOR to replace.

Pavement removed shall become the property of the CONTRACTOR. The CONTRACTOR shall be responsible for disposal of and transporting material from the site.

Protection of adjacent pavements shall be the responsibility of the CONTRACTOR. A mutual inspection of the surrounding pavements shall be made, and any damages shall be repaired by the CONTRACTOR at no additional cost.

### **408-4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107 and as follows:

**408-4.1 ASPHALT REMOVAL.** Bid item shall include proper disposal. Replacement shall not be part of this bid item.

**DIVISION 500**

**RIGID PAVEMENT**

**SECTION 501 – PORTLAND CEMENT CONCRETE PAVEMENT**

**501-1 DESCRIPTION**

This work shall consist of a pavement composed of air-entrained portland cement concrete, with or without reinforcement as specified, constructed on a prepared subgrade or aggregate base course in accordance with these specifications, and in conformity with the lines, grades, thicknesses, and typical cross sections shown on the plans or established by the ENGINEER.

**501-2 MATERIALS**

**501-2.1 GENERAL.** Prior to construction, the CONTRACTOR shall submit for approval by the ENGINEER a certified analysis of materials listed in Sections 501-2.2, 501-2.2(a), 501-2.7, 501-2.8, 501-2.9, 501-2.10, 501-2.12, and 501-2.13.

**501-2.2 PORTLAND CEMENT.** The portland cement used in the work shall be Type IL, Type II, or Type II A, meeting the requirements of ASTM C150 and C595.

**501-2.2a FLY ASH.** The CONTRACTOR shall have the option of substituting fly ash for portland cement in the concrete mixture up to a maximum of 35 percent by weight. Each source of fly ash shall be approved by the ENGINEER prior to use. Fly ash shall conform to the requirements of ASTM C311, ASTM C618, and ASTM C684, Class C fly ash, or Class F fly ash. Class C and Class F fly ash chemical and physical specifications shall be as follows:

<b>Chemical Requirements</b>		
	<b>Class C</b>	<b>Class F</b>
Silicon dioxide (SiO <sub>2</sub> ) plus aluminum oxide (Al <sub>2</sub> O <sub>3</sub> ) plus iron oxide (Fe <sub>2</sub> O <sub>3</sub> ), min %	50.0	66.0
Sulfur Trioxide (SO <sub>3</sub> ), max %	5.0	5.0
Moisture content, max %	3.0	3.0
Loss on ignition, max %	5.0	5.0

SECTION 501 – PORTLAND CEMENT CONCRETE PAVEMENT

<b>Physical Requirements</b>		
	<b>Class C</b>	<b>Class F</b>
Fineness: Amount retained with wet sieve (No. 325 sieve), max %	34.0	34.0
Pozzolanic activity index: With Portland Cement, at 28 days, min, percent of control	75.0	75.0
Water requirement, max %	105.0	105.0
Uniformity requirements: The specific gravity and fineness of individual samples shall not vary from the average established by the 10 preceding test, or by all preceding tests if the number is less than 10, by more than: Specific gravity, max variation from average, %	5.0	5.0
Percent retained on (No. 325) wet sieve, max variation from average	5.0	5.0

<b>Supplementary Optional Physical Requirements</b>		
	<b>Class C</b>	<b>Class F</b>
Increase of drying shrinkage of mortar bars at 28 days, max %	0.03	0.03
Uniformity requirements: In addition when air-entraining concrete is specified, the quantity of air-entraining agent required to produce an air content of 18.0 Vol % of mortar shall not vary from the average established by the 10 preceding tests or by all preceding tests if less than 10, by more than, 1%	20.0	20.0
Reactivity with Cement Alkalies: Mortar expansion at 14 days, mix %	100	100

Fly ash that fails to meet the requirement of the tests shall not be used unless specified otherwise by the ENGINEER.

A complete chemical and physical analysis must be submitted to the ENGINEER for approval 14 days prior to use.

A test result of loss on ignition and amount retained on No. 325 wet sieve must accompany every 25 tons delivered, and these results must be on file at the ready-mix producer's office. Random checks and samples shall be taken to ensure testing accuracy. Any extensive error in test results could cause the material's use to be discontinued.

## SECTION 501 – PORTLAND CEMENT CONCRETE PAVEMENT

No fly ash will be allowed which contains oil residue or chemical pollution control contaminants.

Each source of fly ash shall be approved by the ENGINEER prior to use. If more than one source of fly ash is used on a project, each shall be stored and used separately.

The ENGINEER shall have the right to sample and test the fly ash as deemed necessary during the course of the construction season. The fly ash shall be tested in accordance with ASTM C311.

**501-2.3 AGGREGATE.** The CONTRACTOR shall notify the ENGINEER of the source of the coarse and fine aggregate which is proposed for use on the contract. Sufficient time shall be allowed so that sampling and testing can be completed prior to the beginning of construction. During the construction period, the CONTRACTOR shall at all times make available to the ENGINEER the sampling of aggregate. All aggregate shall meet the requirements of these specifications.

**501-2.4 COARSE AGGREGATE.** Except as noted herein, the coarse aggregate used shall conform to the requirements of ASTM C33, Class 4M. Coarse aggregate shall consist of gravel or broken stone composed of strong, hard, durable, uncoated pebbles or rock fragments washed clean and free from injurious amounts of shale, coal, clay lumps, soft fragments, dirt, glass, organic, or any other deleterious substances.

Coarse aggregate shall be graded from coarse to fine within the limits in the following table, when tested in conformity with ASTM C136. If the coarse aggregate size is not designated in the contract, either gradation may be used, but once adopted, no change in gradation will be made during the course of the work.

COARSE AGGREGATE SIZE		
Sieve Size	Percent by Weight Passing	Percent by Weight Passing
1½"	100	–
1"	95-100	100
¾"	–	90-100
½"	25-60	–
⅜"	–	20-55
No. 4	0-10	0-10
No. 8	0-5	0-5
No. 200	0-1	0-1
Shale	1*	1*
Iron Oxide, Coal, and Soft particles	5*	5*

\*Max. percent by weight of the plus No. 4 fraction.

**501-2.5 FINE AGGREGATE.** Except as noted herein, the fine aggregate shall conform to the requirements of ASTM C33. Fine aggregate shall be natural sand, consisting of

SECTION 501 – PORTLAND CEMENT CONCRETE PAVEMENT

hard, strong, sharp, uncoated grains, free of dust, lumps, mica, shale, organic matter, or other deleterious substances.

Fine aggregate shall be graded within the limits of the following table when tested in conformity with ASTM C136.

FINE AGGREGATE SIZE			
Mortar Sand		Concrete Sand	
Square Mesh Sieve Size	Percent by Weight Passing	Square Mesh Sieve Size	Percent by Weight Passing
No. 4	100	3/8"	100
No. 8	95-100	No. 4	95-100
-	-	No. 16	45-80
-	-	No. 50	10-30
No. 100	25 (max.)	No. 100	0-10
No. 200	10 (max.)	No. 200	0-3

The quality, sampling, and testing of mortar sand for use in cement mortar shall conform to ASTM C144.

**501-2.6 WATER.** Water used in mixing concrete shall be clean and shall not contain deleterious amounts of acids, alkalis, or organic materials. Water shall be subject to test and approval by the ENGINEER.

**501-2.7 ADMIXTURES.** Substances other than cement, water, aggregates, and air-entraining agents shall be approved by the ENGINEER for use in concrete.

Unless otherwise provided in the plans or special provisions, no reduction will be made in the specified cement content of the concrete mixture by reason of using any admixtures. Admixtures containing calcium chloride must be preapproved and conform to ASTM D98. No admixture shall be used which interferes with proper control of the entrained air content of concrete. Permission to use any admixtures may be withdrawn at any time if the properties of the admixture are not uniform or if satisfactory results are not being obtained.

Should the CONTRACTOR request and obtain permission to use admixtures for its own benefit, no additional compensation will be allowed for the cost of furnishing the admixtures and incorporating them into the concrete mixture.

Should the ENGINEER direct the CONTRACTOR to use admixtures when their use is not required by these specifications or by the plans or special provisions, furnishing the admixtures and incorporating them into the concrete mixture will be paid for as extra work as per Section 104.

## SECTION 501 – PORTLAND CEMENT CONCRETE PAVEMENT

Air-entraining admixtures shall conform to ASTM C260.

Retardant admixtures shall conform to ASTM C494 Type B. Retardant admixture submittals shall include specifications and a dosage calculation chart of the admixture. The use of any retardant admixture shall not change the concrete discharge specification found in 501-3.6. The maximum dosage rate shall not exceed a maximum of 2 hours of additional working time. Additional retarder admixtures to achieve over 2 hours of working time shall be approved by the ENGINEER prior to use.

**501-2.8 EXPANSION JOINT MATERIAL.** Pre-molded bituminous fiber expansion joint material shall be used in expansion joints and shall consist of preformed strips of one continuous piece per joint which have been formed from cane or other suitable fibers of cellular nature securely bound together and uniformly impregnated with a suitable asphaltic binder. Said joint materials shall conform to ASTM D1751 (pre-molded material). Closed cell polyethylene expansion joint filler shall conform to ASTM D1056. Expansion joint filler shall be ProFlex vinyl expansion joints from Oscada Plastics, Nomaflex polypropylene joint filler from Nomaco, or approved equivalent, and shall conform to ASTM D1752. The cost for all expansion joint material shall be considered incidental.

**501-2.9 JOINT SEALING MATERIAL.** Joint sealing material shall conform to the following:

Type of Sealant	ASTM
Hot-poured	D6690 Type I, II, and IV
Cold applied elastomeric	C920
Preformed polychloroprene elastomeric	D2628 (6 celled)
Silicone sealant	D5893 Type SL or NDDOT 826.02B Type 5

The cost for joint sealing shall be considered incidental.

**501-2.10 REINFORCEMENT STEEL AND DOWEL BARS.** Reinforcing steel, except as otherwise specified, shall be Grade 60 or Grade 40 deformed bars epoxy coated (meeting ASTM A775) rolled from take out billet stock and shall conform to the requirements of ASTM A615. Reinforcing steel shall consist of tie bars and steel used in structural concrete slabs.

Dowel bars shall be intermediate grade plain bars epoxy coated (meeting ASTM A775) rolled from take out billet stock and shall conform to the requirements of ASTM A663 or A675.

Bar supports and spacers shall be constructed of steel and of suitable design and strength to hold reinforcement accurately in place before and during the placing of concrete. Hy-chairs shall be of welded steel construction, and all spacers, bar supports,

## SECTION 501 – PORTLAND CEMENT CONCRETE PAVEMENT

and chairs shall be approved by the ENGINEER. The cost for all Reinforcement Steel shall be considered incidental.

Tie wire shall be No. 16-gauge annealed wire.

**501-2.11 SELECT BACKFILL.** The material furnished under this item shall be “Subcut Gravel” in accordance with Section 801, class 5 gravel, blended base or crushed concrete and shall be mechanically tamped in place in layers not exceeding 6 inches in depth.

**501-2.12 CURING COMPOUNDS.** Curing compounds shall conform to ASTM C309, Type 2 white pigmented. Additionally, Aquapel Plus™ has been approved for use in CITY rights-of-way.

### 501-3 CONSTRUCTION REQUIREMENTS

**501-3.1 GENERAL.** The CONTRACTOR shall furnish all labor, materials, and services necessary for and incidental to the completion of all work as shown on the drawings and specified herein. All machinery and equipment owned or controlled by the CONTRACTOR shall be of sufficient size to meet the requirements of the work and shall produce satisfactory work. All work shall be subject to the inspection and approval of the ENGINEER. The CONTRACTOR shall employ, at all times, a sufficient force of workmen of such experience and ability that the work can be completed in a satisfactory and workmanlike manner.

The CONTRACTOR shall identify an acceptable concrete washout area(s). Dumping concrete or concrete waste within the CITY’s right-of-way or easements including the storm water system or on adjacent properties is prohibited without the written consent of the CITY or the affected property owner.

#### 501-3.2 MATERIALS STORAGE

**(a) Portland Cement.** Portland cement shall be stored as specified in ASTM C150. The portland cement shall be stored in such a manner as to permit easy access for proper inspection and identification of each shipment and in a suitable weather-tight building that will protect the portland cement from becoming damp and minimize warehouse set. Storage shall be of such capacity to provide ample space for consignments of cement as may be required to carry on the work in accordance with approved progress schedules.

**(b) Aggregates.** Aggregates shall be stored in such a manner as to afford good drainage, prevent the intrusion of foreign matter, and preserve the gradation. Any material which has deteriorated, or which has been damaged shall not be used for concrete.

## SECTION 501 – PORTLAND CEMENT CONCRETE PAVEMENT

To avoid changes in consistency, the aggregates shall be obtained from a source which will ensure uniform quality and grading during any single day's operation, and they shall be delivered to the work and handled in such manner that variations in moisture content will not interfere with the steady production of concrete of uniform quality and consistency.

**(c) Fly Ash.** Fly ash shall be stored in weather-tight facilities to be approved by the ENGINEER.

**501-3.3 ADVANCE DESIGN OF CONCRETE MIXES.** Designs and tests for each concrete mix to be used under the contract shall be made using aggregates which have been approved for this work. Except as otherwise specified, mixes shall be designed in accordance with ACI 613 to attain the required strengths using the various slumps (including the maximum allowable), the various size aggregates expected to be used in the work, and the admixtures as called for by the ENGINEER. The concrete mixes shall be designed by an independent testing laboratory as required per Section 104 of these specifications or otherwise approved by the ENGINEER and shall be incidental to other items.

Standard concrete mix shall contain 550-600 pounds of portland cement per cubic yard (CY). High early strength concrete shall contain 650-700 pounds of portland cement per cubic yard (CY).

Advance tests of each of the proposed mixes shall be made in accordance with ASTM C192. A set of six standard 6-inch diameter or a set of six standard 4-inch diameter compression test cylinders shall be made for each mix design. Three cylinders per set shall be tested for compressive strength at 7 days and three cylinders per set shall be tested for compressive strength at 28 days. The high early strength concrete mix design shall have nine standard 6-inch or 4-inch diameter compression test cylinders. Three shall be tested at 3 days, three shall be tested at 7 days, and three shall be tested at 28 days. Concrete tested shall contain all required and/or proposed admixtures and in addition to the testing required by ASTM C192 shall be tested for air content by ASTM C231.

The advance mix designs and the results of tests on cylinders made from advance mix designs are required before work of concrete placing is started. Tests for aggregates as required in Section 501-2 may be made a part of these tests if suitably referenced on the reports which shall be issued at 7 and 28 days.

Two additional aggregate samples are to be submitted throughout the construction season to an independent testing laboratory and shall be in accordance with Sections 501-2

The CONTRACTOR shall pay for all advance design and testing as required per this section, including tests for aggregates and flexural strength.

## SECTION 501 – PORTLAND CEMENT CONCRETE PAVEMENT

The above tests shall be repeated, if necessary, due to changes in materials or unsatisfactory results. The mix design and the advance testing of aggregates specification may be waived at the request of the CONTRACTOR and with the ENGINEER's approval if a mix design approved by the CITY OF BISMARCK is being produced by an established ready mix plant with suitable records of mixes and testing. The CONTRACTOR shall submit the following items for approved historical mix designs.

1. Copy of the originally approved mix design, performed by a certified testing lab.
2. Current material data sheet for admixtures, cement, fly ash, etc.
3. Verification of aggregate source.
4. New course and fine aggregate gradation and physical properties shall be taken at the yard of dispatch, performed by a certified testing lab.
5. 5 different concrete compressive strength test, performed by a certified testing lab dated within the past year for the plant at the yard of dispatch. Reports shall include mix identification number that match approved mix designs. Compressive strength test shall include 7 day and 28 day test results, if the mix design is for high early concrete a 3 day compressive strength test results is required as well.

**501-3.4 FIELD QUALITY CONTROL.** The CONTRACTOR shall engage an independent testing laboratory approved by the ENGINEER to test consistency, proportioning, and strength of the concrete mixture. The CONTRACTOR shall be responsible for scheduling the testing firm. The time and location of testing shall be at the discretion of the ENGINEER. The independent testing laboratory personnel testing in the field shall be responsible for immediately notifying the CONTRACTOR and the ENGINEER in the field of failures. If any tests have not met the specifications, testing shall continue on all batches until the specific ranges have been met and the limits of the area not meeting the requirements are established.

Aggregate samples shall be taken from stockpile at the yard of dispatch.

The cost of testing, including retesting of failed tests, shall be considered incidental. All tests requested by the ENGINEER, other than frequencies specified below, shall be considered extra items.

For construction of new concrete pavements, tests shall be taken for each 120 cubic yards (CY).

For new and repaired driveways, sidewalks and valley gutters tests shall be taken every 60 cubic yards (CY), and no less than one per week or less than 60 cubic yards (CY) utilized.

The concrete test shall be taken for each 75 cubic yards of concrete pavement repair material placed, and no less than one per week

Where less than 1,000 linear feet (LF) of new curb and gutter is placed, one concrete test shall be taken for each side of the street.

## SECTION 501 – PORTLAND CEMENT CONCRETE PAVEMENT

Where more than 1,000 linear feet (LF) of new curb and gutter is placed, one test shall be taken for each 1,000 LF of new curb and gutter placed on each side of the street.

A set of three standard 6-inch diameter compression test cylinders shall be cast in the field in accordance with ASTM C31 and C172 for each sample taken. The cylinders cast from the given standard concrete mixtures sample shall be tested in the laboratory, one at 7 days and the remaining two at 28 days with the required minimum strength of the concrete being 4,000 pounds per square inch at 28 days.

If the testing firm chooses to use 4-inch diameter cylinders, a set of four standard four inch diameter compression test cylinders shall be cast in the field in accordance with ASTM C31 and C172 for each sample taken. The cylinders cast from the given standard concrete mixtures sample shall be tested in the laboratory, one at 7 days and the remaining three at 28 days with the required minimum strength of the concrete being 4,000 pounds per square inch at 28 days.

High early strength concrete mixtures shall be tested in the laboratory, one at 3 days, one at 7 days, and the remaining one at 28 days for 6-inch cylinders and two at 28 days for four inch cylinders.

One additional test cylinder shall be taken during cold weather construction as defined in Section 501-3.10. This cylinder shall be cured on the job site under the same conditions as the concrete it represents and tested in the laboratory after 28 days. Each sample taken or cylinders shall also be tested for slump in accordance with ASTM C143 and air content in accordance with ASTM C231.

The maximum allowable slump of the concrete mixture shall be 4 inches unless otherwise approved by the ENGINEER. The air content shall fall within the range of 5 percent to 8 percent. Concrete test specimens for flexural strength shall be made at the discretion of the ENGINEER according to ASTM C31.

Construction and public traffic shall not be allowed on newly placed concrete pavement until the concrete has attained an initial cure.

Initial cure shall be defined as reaching a minimum compressive strength of 3,000 psi or a minimum flexural strength of 450 psi.

Concrete not meeting required specifications for slump or air content during placement may be accepted or rejected at the discretion of the ENGINEER.

Written reports of all tests shall be supplied to the ENGINEER and the CONTRACTOR by the testing laboratory as soon as possible. To expedite construction, it is necessary that the CONTRACTOR and ENGINEER be furnished with the results of all tests as soon as testing is completed.

## SECTION 501 – PORTLAND CEMENT CONCRETE PAVEMENT

The availability of the independent testing laboratory when needed and speed of testing and reporting are to be considered the responsibility of the CONTRACTOR.

During the course of concrete construction, it may be deemed necessary by the ENGINEER to verify concrete composition and/or thickness. This will be accomplished by coring the completed and in place concrete. The CONTRACTOR shall remove and replace the samples at no extra charge. If the concrete is deficient in composition, compaction, or thickness, satisfactory correction shall be made immediately.

Should the CONTRACTOR require any of the above verification sampling, the CONTRACTOR agrees to assume all costs incurred, including the testing of the sample.

The pavement shall not be opened to traffic prior to 7 days after construction and not before flexural strengths of 450 psi or compressive strengths of 3,000 psi are attained. Pavement shall not be opened to traffic without approval by the ENGINEER.

**501-3.5 PROPORTIONING MATERIALS.** Concrete shall be composed of portland cement, fly ash, fine aggregate, coarse aggregate, admixtures, and water as specified. The mix shall be designed in accordance with Section 501-3.3 of these specifications.

The amount of water specified shall include the surface moisture carried by the aggregates at the time of mixing. This amount of water shall be determined by tests made by the CONTRACTOR, and the quantity of mixing water to be added to the batch shall be added to that found to be carried by the aggregates to total the rate specified. The number of tests required and the consequent changes in the amount of mixing water to be added will depend on the control exercised in the gradation and moisture contents of the aggregate.

The amount of water shall also include that liquid added to the batch in the form of admixtures.

The amounts and proportions of fine and coarse aggregates to be used in each mix shall be such as to produce a plastic, workable mix, free from harshness, which can be readily placed into the corners and angles of the forms and around reinforcement and other embedded work without undue accumulation of water laitance on the surface, and such that there will be no honeycombing in the structure.

Proportions of fine and coarse aggregates shall be such that the ratio for the coarse to the fine aggregate shall not be less than one nor more than two. On all work under these specifications, a cubic yard of concrete shall contain not less than six sacks (564 lbs.) of cement or cement and fly ash mixture.

**501-3.6 BATCHING AND MIXING CONCRETE.** Mixing of concrete shall be done in a rotary batch mixer of a type acceptable to the ENGINEER. The volume of the mixed material for each batch shall not exceed the manufacturer's rated capacity of the mixer.

## SECTION 501 – PORTLAND CEMENT CONCRETE PAVEMENT

The batch materials shall be delivered to the mixer measured accurately to the required proportions and shall be mixed continuously for not less than 1½-minutes after all materials including water are in the mixer during which time the mixer shall rotate at the speed recommended by its manufacturer. The entire batch shall be discharged before recharging the mixer. The mixer shall be cleaned as required to ensure adequate and complete mixing.

In lieu of jobsite mixing, ready mixed concrete meeting the requirements specified herein and all applicable requirements of ASTM C94 may be approved provided the quantity and rate of delivery of materials will be such as to permit unrestricted progress of the work in accordance with the placing schedule. When the air temperatures are above 90°F, the concrete shall be discharged within one hour. When air temperatures are below 90°F, the concrete shall be discharged within a maximum of one and 1½-hours. Mixing shall not be less than 60 revolutions nor more than 300 revolutions of the drum after the introduction of the mixing water to the cement and aggregates. Truck mixers shall be equipped with a means by which the number of revolutions of the drum, blades, or paddles may be readily verified.

Two copies of complete data concerning mixing and transportation methods shall be submitted to the ENGINEER for approval.

**501-3.7 SUBGRADE/BASE COURSE.** Subgrades or aggregate base for placing concrete shall be prepared in accordance with Section 200 "Earthwork" or Section 300 "Base Courses" and shall be damp but not wet before the concrete is placed. Hand tamping of subgrades/bases will not be permitted. Approved mechanical type shall be used.

The CONTRACTOR shall engage an independent testing laboratory as required per Section 104 of these Specifications, or otherwise approved by the ENGINEER, to perform subgrade/base compaction tests. Subgrade/base compaction tests in accordance with ASTM D1557 shall be performed and reported at the following frequencies:

- a. One for each 12 lots of new sidewalks, driveways, and/or driveway widenings.
- b. One for each 20 repairs of sidewalks, driveways, curb and gutters, and valley gutters.
- c. One for each 400 square feet (SF) of full-depth pavement repair.
- d. Two for each new construction unit where 1,000 linear feet (LF) or less of curb and gutter is constructed.
- e. One for each valley gutter placed.
- f. One for each 750 square yards (SY) of concrete pavement placed.

Note: (a.) and (b.) from above may only be required when in situ subgrade is found to be of questionable suitability as determined by the ENGINEER.

## SECTION 501 – PORTLAND CEMENT CONCRETE PAVEMENT

Should it become necessary to require an additional number of initial compaction tests, over and above the number specified, the ENGINEER will consider additional testing as extra work.

**501-3.8 FORMS.** After the subgrade and aggregate base course, if required, have been graded and compacted, the forms shall be set and secured in such a manner as to retain line and grade when poured and tamped with concrete. Forms shall be metal, wood or alternative material approved by the ENGINEER. The top edge of each form shall be true and straight and when set and secured shall conform to the grade of the finished pavement. All forms shall be clean and coated with oil or other approved material before the concrete is placed. Forms shall have a depth not less than the depth of the concrete to be constructed, wood forms may be of nominal board width equal to the depth of the concrete.

**501-3.9 PLACING CONCRETE.** The subgrade/base shall be lightly watered immediately prior to placing of concrete. The concrete shall be placed on the moist subgrade/base and spread uniformly to the required depth with as little handling as possible and shall be mechanically vibrated to the forms or header boards to prevent voids and honeycombed surfaces. The concrete shall be consolidated so as to produce a uniformly dense concrete and so as to flush sufficient mortar to the surface to permit a proper finish without additional water added to the surface. Excessive water, laitance, or other inert material shall be floated from the surface.

**501-3.10 COLD WEATHER.** When the temperature remains below 40°F for more than 3 days prior to placement, or when the temperature is forecasted to fall below 40°F during the initial cure period, as defined in Section 501-3.4, following placement, special provisions shall be taken. Except as otherwise specified, mixing, placing, and protection shall be in accordance with the latest edition of the Portland Cement Association Manual entitled *Design and Control of Concrete Mixtures*. Curing shall be specified in Section 501-3.13.

Concrete poured outside of specification shall be immediately removed upon direction of the ENGINEER and replaced with new concrete at no expense to the Owners.

In order to maintain the temperatures specified, the concrete shall be entirely enclosed with concrete insulating blankets, or other methods approved by the ENGINEER. Suitable heating equipment and the necessary labor and supervision shall be furnished. Unvented heaters shall not be used. The CONTRACTOR shall be responsible for the protection of the work with no additional compensation, any extra work needed to protect concrete due to weather conditions shall be considered incidental. Cover shall remain in place through the duration of the initial cure period or until temperatures reach and are forecasted to remain above 40°F.

At the discretion of the ENGINEER, during freezing weather, temperature records shall be kept by the CONTRACTOR and furnished to the ENGINEER daily. Records shall show the temperature at four hour intervals of the: (a) outside air, (b) concrete as it is

## SECTION 501 – PORTLAND CEMENT CONCRETE PAVEMENT

placed, (c) air in the coldest part of the enclosure near the concrete, and (d) concrete in place at such points as the ENGINEER may direct.

**501-3.11 HOT WEATHER.** Concrete materials shall be placed at the lowest practicable temperature except as specified in Section 501-3.10 for cold weather. When hot weather conditions exist that would seriously impair the quality and strength of the concrete, the concrete shall be placed in accordance with the latest edition of the Portland Cement Association Manual entitled *Design and Control of Concrete Mixtures*, except as otherwise specified herein.

During hot weather conditions, the temperature of the concrete immediately before it is placed in the forms shall be between 50°F and 90°F.

Shaved ice may be used in the mixing water to reduce the temperature of the concrete at the mixer, but there shall be no ice in the concrete when it is discharged from the mixer.

The CONTRACTOR shall be responsible for the protection of the work with no additional compensation, any extra work needed to protect concrete due to weather conditions shall be considered incidental.

**501-3.12 SURFACE FINISH.** Concrete pavement surfaces shall be floated to a true and even plane. The CONTRACTOR shall provide factory-made straightedges, 10 feet in length for use in checking forms and final finish of all pavement sections. The maximum allowable deviation from a true plane shall be 1/8 inch in 10 feet on the top and face of forms and all exposed surfaces of the finished pavement section.

**New Pavements.** After surface irregularities have been removed, and before the concrete attains an initial set, a seamless strip of stiff-fiber artificial grass carpet shall be dragged longitudinally along the full width of the pavement. The surface texture shall be uniformly roughened leaving corrugations in the surface that are uniform in appearance. The width of material in the drag shall be in contact with the full width of the pavement. The drag shall be operated off a string line with its leading edge attached to bridge riding on the forms or adjacent slabs. The drag shall be maintained clean and free from encrusted mortar. A drag that cannot be cleaned shall be replaced with new fabric.

**Repaired Pavements.** After the irregularities have been removed and before the concrete attains an initial set, a broom shall be drawn transversely across the pavement. The brooming shall be sufficient to leave significant marking in the pavement.

**501-3.13 PROTECTION AND CURING.** All concrete work shall be carefully protected from sun, wind, storms, and travel until thoroughly set, and the CONTRACTOR will be held responsible and must make good at the CONTRACTOR's expense any damage from any cause until approved and accepted by the ENGINEER.

## SECTION 501 – PORTLAND CEMENT CONCRETE PAVEMENT

A chemical curing agent shall be used at all times, applied immediately after installation in accordance with the manufacturer's specifications and Section 501-2.

During the curing period, only equipment necessary for curing and for sawing joints will be allowed on the concrete.

Immediately after placement, protect concrete from premature drying, excessively hot or cold temperatures, and mechanical injury.

Maintain concrete with minimal moisture loss at relatively constant temperature for periods necessary for hydration of cement and hardening of concrete.

Grade site to maintain positive drainage away from new concrete.

If the ambient temperature falls below 40°F, maintain the concrete surface temperature between 40°F and 90°F for the duration of the curing period.

If high-early strength concrete is used, maintain the surface temperature between 50°F and 90°F.

Conduct heating operations to avoid sudden temperature changes in the concrete. Before removing any enclosures, decrease the concrete's surface temperature to the air temperature at a rate not to exceed 15°F per hour.

Submit a detailed temperature maintenance plan before placing concrete if the ambient temperature is expected to drop below 40°F within the curing period.

**501-3.14 CONCRETE STAMPS.** The CONTRACTOR shall mark in each 500 linear feet of new pavement, either by stamping or inlaying, an approved metal plate, with CONTRACTOR's name, address, and year in which the pavement was constructed. The stamped letter shall be 1 inch high and 1/4 inch deep. If a metal plate is used, the top of the plate shall be flush with the top of the pavement. CONTRACTOR's stamp must be approved by the ENGINEER prior to beginning of the construction year. CONTRACTOR shall be responsible for changing the date on the stamp each year.

**501-3.15 CONCRETE WASTE DISPOSAL.** The disposal area(s) for this item shall be within a 9-mile radius of the project when said area is specified on the plans, in the special provisions, or by the ENGINEER. When a disposal area is not specified, the CONTRACTOR shall be required to either provide such an area which shall be approved by the ENGINEER or haul to the City of Bismarck Solid Waste Facility and pay the required disposal fees.

**501-3.16 SAWING CONCRETE.** All concrete sawing designated on the plans and/or as directed by the ENGINEER, shall have a minimum depth equal to one third the thickness of the concrete.

## SECTION 501 – PORTLAND CEMENT CONCRETE PAVEMENT

Prior to sawing, an inspection of the adjacent slab shall be made to determine if any micro cracks exist. If any micro cracks exist, the saw cut line may be positioned so the cracked area may be removed.

**501-3.17 SELECT BACKFILL.** The material furnished under this item shall be “Subcut Gravel” in accordance with Section 801; class 5 gravel, blended base or crushed concrete and shall be mechanically tamped in place in layers not exceeding 6 inches in depth.

**501-3.18 BACKFILL.** The newly constructed concrete pavement shall be backfilled within 14 days and compacted in accordance with Section 202.

**501-3.19 JOINTS.** Joints in concrete pavement shall be of the design specified and shall be constructed at the spacings and locations shown. The CONTRACTOR shall be responsible to establish joint locations as approved by the ENGINEER.

**(a) Transverse Contraction Joints.** The contraction joints shall consist of weakened planes created by either sawing, inserting preformed inserts, or forming grooves in the pavement surface on small areas. The location of the grooves to be formed or sawed shall be clearly and accurately marked on the plastic concrete surface by the CONTRACTOR. When specified, the contraction joints shall include a load transfer device.

Sawed contraction joints shall be cut to the required dimensions with proper equipment. Concrete saws shall be adequately powered and furnished with suitable blades to effectively cut pavement joints to required dimensions. Each blade of multiple-blade saws shall be maintained in accurate alignment to the other blades. A device shall be provided to guide the saw along the required joint alignment. Manual guidance of the saw will be permitted if specified results are obtained. A sufficient amount of sawing equipment shall be available to maintain required progress and provide prompt replacement in case of breakdown. Adequate artificial lighting shall be provided for night sawing.

The time and sequence of sawing shall be adjusted so all joints are cut before uncontrolled cracking occurs and to permit sawing without excessive raveling. Joints shall be sawed within 24 hours to prevent uncontrolled cracking. Uncontrolled cracking that occurs shall be routed, cleaned, and sealed according to Section 501-3.23, at the CONTRACTOR’s expense. Immediately after sawing, the joint shall be flushed with water under sufficient pressure to remove residue left by the sawing operation. If an uncontrolled crack occurs within 3 feet of a proposed joint location before or during sawing, the joint shall be omitted and sawing of the joint discontinued. Any joint sawed within 3 feet of an uncontrolled crack shall be repaired at the CONTRACTOR’s expense. When sawing is performed before removing side forms, the initial saw cut shall extend to within 1/2 inch or less of the side forms. If the forms have been removed, the saw cut will be extended to the edges of the slab. Any curing media removed during sawing shall be immediately replaced.

## SECTION 501 – PORTLAND CEMENT CONCRETE PAVEMENT

**(b) Formed Contraction Joints.** A formed contraction joint shall be constructed by installing an approved, preformed insert into the plastic concrete before final surface finishing. The inserts shall be vibrated into place or installed in a groove formed by a vibrating cutting bar. The inserts' top edges shall be flush with the concrete surface. Any voids, depressions, or ridges of concrete caused by installing inserts shall be filled or removed by hand-finishing methods, and the surface across the joint shall be straight edged according to Section 501-3.12. The groove formed by the inserts shall be perpendicular to the pavement surface, true to the required alignment, and continuous along the full length of the joint. Inserts, except those designed to remain, shall be removed without damage to adjacent concrete.

When specified for use with transverse contraction joints, the dowel bars shall be held in the specified position parallel to the slab surface and to the centerline within a tolerance of 1/8 inch per foot vertically and horizontally. The dowel bar assembly shall be an approved metal supporting device securely staked to the roadbed and shall hold the dowel bars at the correct spacing, alignment, and elevation. The position of these load transfer devices shall be accurately marked with steel pins, or other precise methods, to locate the transverse joint over the center of the dowels.

Dowel bars shall have a uniform coat of Tectyl 506 applied by the manufacturer, or a thin, uniform coat of multipurpose lithium grease, NLGI Grade 2, shall be used as the release agent. Multipurpose lithium grease shall be applied to the entire length of the dowel bars within 2 hours of being covered with concrete.

**(c) Transverse Construction Joints.** A transverse construction joint shall be installed at the end of each day's pour and whenever the elapsed time between placement of successive batches or loads of concrete exceeds 45 minutes.

The transverse construction joint shall be formed by installing an approved dowel splicer bar basket assembly. The assembly shall hold the dowel splicer bars parallel to the centerline and slab surface. The dowel splicer bars shall be placed with a tolerance of 1/8 inch per foot vertically and horizontally. The assembly shall be staked perpendicular to the centerline and marked. The CONTRACTOR shall pave over the assembly far enough to maintain the elevation of the top of the slab. A full-depth saw cut shall be made to expose the dowel splicer bar, the excess concrete shall be disposed of, and the threaded dowel extension bar shall be installed.

After the adjacent slab is placed, the construction joint shall be sawed and sealed as specified.

**(d) Other Concrete Joints.** Other concrete joints shall be formed by an approved header shaped to conform to the cross section of the slab being placed. The header shall be rigid and secure to prevent bulging or displacement while adjacent concrete is being placed and finished. The face of the header in contact with the concrete shall be perpendicular to the pavement surface and shall be at right angles to the pavement centering. A two-piece or other approved header shall be designed to accommodate

## SECTION 501 – PORTLAND CEMENT CONCRETE PAVEMENT

proper placement of any dowel bars or reinforcement extending across the joint and to allow removal without damage to the concrete.

The concrete adjacent to the header shall be thoroughly consolidated by an internal vibrator or other approved methods. Segregated or improperly consolidated concrete shall be removed after the pavement has been finished, and the surface adjacent to the header shall be edged to the specified radius.

**(e) Longitudinal Weakened Plane Joints.** Planes of weakness for longitudinal joints shall be created by sawing grooves in the pavement surface. Grooves shall be sawed to meet dimensions shown and shall be true to the required alignment of the joint.

**(f) Longitudinal Construction Joints.** The longitudinal joint between adjoining, separately constructed lanes of pavement shall be constructed as shown on the plans. Tie bars across longitudinal construction joints shall be at the locations, spacing, and depth shown. Tie bars may be bent at right angles against the form to the first lane constructed and straightened into final position before the concrete of the adjacent lane is placed. The tie bars may be inserted through small, accurately positioned holes in the side forms. Two-piece connectors may also be used, if approved by the ENGINEER.

All dowel bars, drilled in dowels, dowel bar baskets, tie bars, headers, dowel bar basket assemblies, and sawing of longitudinal and transverse joints shall be considered incidental to concrete pavements placed or repaired and accepted by the ENGINEER.

**501-3.20 EXPANSION JOINTS.** Expansion joints, which are specified to be sealed, shall be constructed with the top of the expansion joint material 1/2 inch to 3/4 inch lower than the adjacent concrete or form.

**501-3.21 SEALING OF JOINTS.** All joints specified herein or in the standard details shall be sealed within 14 days of the construction and prior to opening to public traffic.

Just before sealing, each joint shall be thoroughly cleaned of all foreign material, including membrane-curing compound. Joint faces shall be dry when sealant is applied. Material for sealant applied hot shall be stirred during heating to prevent localized overheating.

Joints shall be sealed within 1/4 inch of the surface. The joint filling shall be done without spilling material on the exposed surface of the concrete. Any excess material on the surface of the concrete shall be removed immediately and the concrete surface cleaned. The use of sand or similar material to cover the seal shall not be permitted. Joint sealing material shall not be placed when the air temperature does not meet manufacturer's recommendations, unless approved by the ENGINEER.

**501-3.22 DRILLED IN DOWEL AND TIE BARS.** Dowels shall be drilled into widened, existing, or repaired concrete pavements. Transverse dowels shall be 1¼ inches by 18 inches long smooth epoxy coated or #9 by 18 inches deformed (reinforcing bar) epoxy coated.

Holes drilled for dowels shall be located at mid-depth of the slab and spaced at 12 inches on center or as directed by the ENGINEER. Holes drilled for dowels shall use a rigid frame mounted drill rig. The holes shall be a maximum diameter of 1 3/8 inches. Transverse doweled holes shall be air blown clean to the back of the hole. For smooth dowels, inject high-viscosity epoxy (meeting AASHTO M 235 Type 4, Grade III) into the back of the hole with a pressurized caulking apparatus. Insert 1¼ inches by 18 inches smooth dowel to allow air to escape and ensure completely filled holes with bars permanently fastened to the existing concrete. Apply a small form to face of hole to keep epoxy from flowing out and remove it prior to placing concrete. Align smooth dowel bars with the pavement direction parallel to the plane of the surface. Lightly coat the end of the smooth dowels extending into the concrete with grease.

Longitudinal tie bars shall be #6 by 18 inches deformed bars (grade 40) and shall be installed at 3 feet on center. Drills shall be mounted on a rigid frame to provide proper position and alignment. The holes shall be a maximum diameter of 7/8 inch. Tie bars shall be located at mid-depth of the slab and spaced as indicated on the details, or as directed by the ENGINEER. The cost for drilled in tie bars shall be considered incidental.

**501-3.23 RANDOM CRACK SEALING.** Random cracks in existing portland cement pavement and curb and gutter that are not settled or displaced shall be sealed as directed by the ENGINEER. Before sealing, each crack shall be thoroughly cleaned mechanically of all dust, dirt, concrete scale, existing sealant or other foreign matter and followed with a high-velocity jet of compressed air with a minimum airflow of 185 cfm and 120 psi at the air nozzle. The nozzle shall be no less than 1/2 inch, inside diameter, utilizing a commercial grade air compressor. A leaf blower shall NOT be an acceptable substitute for compressed air. The crack shall be clean and dry when sealed. Random cracks shall not be sealed when the air temperature does not meet manufacturer's recommendations, unless approved by the ENGINEER.

Random cracks narrower than 1/4 inch shall be widened to 3/8 inch and sealed with silicon sealant according to Section 501-2. All other random cracks shall be sealed with hot pour in accordance with Section 501-2.

Random cracks shall be sealed within 1/4 inch of the surface.

**501-3.24 SAW AND SEAL.** Repaired working joints and random cracks on existing portland cement pavements and curb and gutters shall be sawed and sealed as follows:

Saw and seal any single, transverse, uncontrolled crack that penetrates the full slab length.

## SECTION 501 – PORTLAND CEMENT CONCRETE PAVEMENT

All uncontrolled cracking and repaired working joints shall be sawed and sealed to the following dimensions:

Sawed Joint Width, Inches	Sealant Bead Thickness, Inches	Backer Rod Diameter, inches	Minimum Sawed Joint Depth, Inches	Backer rod Placement Depth, Inches
1/2	1/4	5/8	1 1/4	1/2
5/8	5/16	3/4	1 1/2	9/16
3/4	3/8	1	1 3/4	7/8
7/8	7/16	1	1 3/4	1 1/16
1	1/2	1 1/4	2	3/4

Joints shall be sawed to the nearest 1/8 inch in width and to the nearest 1/4 inch in depth.

The joint shall be cleaned of any materials such as rocks, dirt, oil, asphalt, paint, and rust, and blown out with compressed air immediately prior to installing sealant. Backer rod, if utilized, shall be 25 percent larger than joint width and installed full width of joint repair. Sealant shall be installed from inside the joint with an approved mechanical device. Sealant shall be filled to 1/4 inch below pavement surface. Sealant shall conform to Section 501-2. Joints to be sealed by this method will be marked by the ENGINEER.

Compression joint material within 1/2 inch from surface of pavement shall be removed and sealed, which will be paid at the unit price bid for joint and crack sealing.

**501-3.25 CASTING ADJUSTMENTS.** Construction materials, methods, and measurements and payments shall conform to Section 1206.

**501-3.26 WRAPPED UTILITY BOXES.** Construction materials, methods, and measurements and payments shall conform to Section 1206.

**501-3.27 CONCRETE REMOVAL.** All concrete removed shall be to the nearest joint, unless otherwise directed by the ENGINEER. Removed concrete materials shall become property of the CONTRACTOR, removed from site, and disposed of at CONTRACTOR's expense, unless otherwise specified.

**501-3.28 UNCONTROLLED CRACKING.** When uncontrolled cracking occurs within 2 years of acceptance of new roadway concrete:

- If single crack in panel, CONTRACTOR may route and seal if:
  - Crack is not parallel to and within 6 inches of a joint.
  - Total cracked panels do not exceed 2% of total panels on a project.
- When CONTRACTOR route and seals cracks, end of cracks shall be drilled out with a 2" diameter hole completely through the concrete and sealed.

## SECTION 501 – PORTLAND CEMENT CONCRETE PAVEMENT

- If panel(s) has more than one crack or the total number of panels cracked exceeds 2% of the total panels on a project, all cracked panel(s) shall be removed and replaced.
- If cracking occurs prior to final acceptance of the project, a deduct of 10% of the bid cost for cracked panels will be applied to all panels that are route and sealed.

All crack repairs and/or panel replacement shall be at CONTRACTOR's expense. CONTRACTOR may elect to remove and replace panels, at own expense, in lieu of route and seal.

This specification does not apply to sidewalks, driveways or curb and gutter.

### 501-4 MEASUREMENT AND PAYMENT

Measurement and payment shall be as specified in Section 107 and as follows:

**501-4.1 ADDITIONAL PORTLAND CEMENT.** During the course of construction, the ENGINEER may require the use of additional portland cement in the concrete mix. When requested and used, all cement greater than six sacks (564 lbs.) per cubic yard of concrete except for full-depth repairs shall be measured by the sack (94 lbs.) and paid for at the unit price bid for "Additional Portland Cement".

**501-4.2 CONCRETE REMOVAL.** Unless otherwise specified, thickness of concrete for removal shall be measured to the nearest ¼ inch in the field by the ENGINEER and paid as follows:

<u>Field Measurement</u>	<u>Contract Item</u>
5" and Less	Concrete Removal: 4"
5.25" to 7"	Concrete Removal: 6"
7.25" and Greater	Concrete Removal: 8"

## **SECTION 502 – SLABJACKING**

### **502-1 DESCRIPTION**

This work shall consist of slabjacking concrete in accordance with these specifications and in conformity with dimensions and typical cross sections shown on the plans and with lines and grades established by the ENGINEER.

### **502-2 SLABJACKING MATERIALS**

Slabjacking materials shall consist of portland cement, sand-free loam topsoil, powder limestone, or lime sludge, which shall become fluidlike when mixed with water.

A preferred mixture is lime sludge or powder limestone. Powder limestone shall contain a minimum of 90 percent calcium and magnesium carbonates, grated so that 100 percent pass a 60-mesh screen, 85 percent pass a 100-mesh screen, and 60 percent pass a 200-mesh screen. Portland cement shall contain about a 5:1 ratio of limestone to cement. Topsoil shall be a good loam soil relatively free of sand, clay, pebbles, and roots.

Material shall be the consistency of a thick cream that tends to flow freely and fill all voids and openings, yet should have a sufficient internal resistance (stiffness) that the amount of lift may be controlled.

Cement content may vary with each individual application; some jobs may only contain 5 percent cement, others as much as 15 percent. A high cement content mix may be used when it is desirable to have the mix set up quickly.

Urethane foam resin such as Hydraulic Mudpumps, Inc. RR201 under four inch thick slabs and RR401 under greater than four inch slabs and curb and gutter and NCFI polyurethanes 24-486 are also allowed.

### **502-3 SLABJACKING.**

This work shall consist of raising, leveling, void filling, and stabilizing concrete slabs by drilling through the concrete slab and forcing a fluidlike material on the bottom of the slab.

Slabjacking shall not be done during the following weather conditions:

- a. Excessive rain or when temperature is below 32°F.
- b. When frost is in the ground.
- c. During hot weather where the mixture could stand for any length in time causing setup to occur.

Slabjacking holes shall be drilled into slabs 3/4 inch to 1½ inches in diameter. Equipment used to drill holes shall not strike too heavy a blow and shall avoid breaking off the lower side of the slab as the drill goes through. Any damage to existing adjacent

## SECTION 502 – SLABJACKING

slabs or to the slab to be repaired shall be the responsibility of the CONTRACTOR. Spacing and location of holes shall be drilled according to the project and the way the slab must be lifted, tilted, and voids filled.

Slabjacking holes shall be finished by removing excess slabjacking materials and finishing off each hole with a dry cement mix leaving a slight crown in the middle to allow shrinkage of cement and shall be completed within 7 days after completion of lifting. Any finished surface which has settled below the slab grade shall be removed and refinished. All joints adjacent or within the slabjacked area wider than 3/8 inch shall be sealed in accordance with Section 501.

The work area shall be kept clean and safe at all times.

When a finished slab does not meet the following tolerances, it will be considered a failure and therefore not accepted by the ENGINEER, and no payment will be made:

Curb and Gutter Joints: Sags no more than 1/4 inch per 10 linear feet (LF) or 1/4 inch vertical separation at a joint.

Four-Inch, Six-Inch, and Eight-Inch Concrete: 1/2 inch vertical separation per joint.

Valley Gutters and Driveways: Will be at the discretion of the ENGINEER.

### **502-4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107.

## SECTION 503 – CONTROLLED DENSITY FILL (CDF)

### 503-1 DESCRIPTION

This work shall consist of placement of a controlled density fill which is a mixture of coal fly ash, water, sand, and portland cement that flows like a liquid, sets up like a solid, is self-leveling, and requires no compaction or vibration to achieve maximum density.

### 503-2 MATERIALS

**503-2.1 PORTLAND CEMENT.** Portland cement shall conform to the requirements of ASTM C150, Type IL, Type I or Type II. If for any reason cement becomes partially set or contains lumps of caked cement, it shall be rejected. Cement salvaged from discarded or used bags shall not be used.

**503-2.2 FLY ASH.** Fly Ash shall conform to Section 501.

**503-2.3 FINE AGGREGATE (SAND).** Fine aggregate shall conform to the requirements of ASTM C33 except for aggregate gradation. Any aggregate gradation which produces performance characteristics of the ASTM specified herein will be accepted, except as follows:

Sieve Size	Percent Passing By Weight
$\frac{3}{4}$ "	100
No. 200 (0.075 mm)	0-12

**503-2.4 WATER.** Water used in mixing shall be free of oil, salt, acid, alkali, sugar, vegetable matter, or other substances injurious to the finished product.

Dyes and other methods of coloring the backfill material may be incorporated if desired.

### 503-3 CONSTRUCTION REQUIREMENTS

**503-3.1 PROPORTIONS.** The CONTRACTOR shall submit to the ENGINEER a mix design including the proportions and source of material, admixtures, and dry cubic yard batch weights. The mix shall contain up to 100 pounds of cement and 300 pounds of fly ash per cubic yard, with the remainder of the volume composed of sand, water, and any approved admixtures.

CDF shall be designed to achieve a 28-day compressive strength of 80 to 130 psi when tested in accordance with ASTM C39. There should be no significant strength gain after 28 days. Test specimens shall be made in accordance with ASTM C31, except that the

## SECTION 503 – CONTROLLED DENSITY FILL (CDF)

samples will not be rodded or vibrated and shall be air cured in their molds for the duration of the cure period. The air content, tested in accordance with ASTM C231, shall fall within the range of 10 percent to 12 percent.

Consistency of the fresh mixture shall be such that the mixture may be placed without segregation. A desired consistency may be approximated by filling an open ended three inch diameter cylinder, six inches high to the top, with the mixture and the cylinder immediately pulled straight up. The correct consistency of the mixture will produce an approximate eight inch diameter circular-type spread without segregation. Adjustments of the proportions of materials should be made to achieve proper solid suspension and flowable characteristics; however, the theoretical yield shall be maintained at 1 cubic yard for the given batch weights.

### **503-3.2 PLACEMENT**

CDF may be placed by any reasonable means from a mixing unit into the space to be filled. Agitation is required during transportation and waiting time. Placement shall be performed in such a manner that structures or pipes are not displaced from their desired final position and intrusion of CDF into undesirable areas is avoided. The material shall be brought up uniformly to the fill line shown on the plans or as approved by the ENGINEER. Each placement of CDF shall be as continuous as possible. If CDF is placed in more than one layer, the base layer shall be free of surface water and loose or foreign material prior to placement of the next layer.

CDF shall not be placed on frozen ground. Mixing and placing may begin when the air temperature is at least 35° F and rising. At the time of placement, CDF shall have a temperature of at least 40°F. Mixing and placement shall stop when the air temperature is 40° F and falling or when the anticipated air temperature will be 35°F or less in the 24 hour period following proposed placement.

### **503-3.3 CURING AND PROTECTION**

The air content of the CDF should be maintained at temperatures above freezing for a minimum of 72 hours. If the CDF is subject to temperatures below 32°F, the material may be rejected by the ENGINEER if damage to the material is observed.

The CDF shall not be subject to loads and shall remain undisturbed by construction activities for a period of 48 hours or until a compressive strength of 15 psi is obtained. The CONTRACTOR shall be responsible for providing evidence to the ENGINEER that the material has reached the desired strength. Acceptable evidence shall be based upon the independent testing laboratory compressive test results.

### **503-4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107.

## **SECTION 504 – CONCRETE PAVEMENT REPAIR**

### **504-1 DESCRIPTION**

This work shall consist of concrete pavement repair composed of full depth repairs, spall repairs – partial depth, joint and random crack cleaning and sealing in accordance with these specifications.

### **504-2 MATERIALS**

Materials shall meet the requirements of Section 501. Concrete pavement repairs shall be high-early-strength concrete.

**504-2.1 PORTLAND CEMENT.** Type II or IIA portland cement may be substituted with Type III or IIIA portland cement, meeting requirements of ASTM C150, to achieve high-early-strength concrete.

### **504-3 CONSTRUCTION REQUIREMENTS**

**504-3.1 FORMS.** Forms shall conform to Section 501 for all exposed edges. Wood forms may be utilized for repairs that are less than 15 feet in length.

**504-3.2 SPALL REPAIR – PARTIAL DEPTH.** This item includes all work necessary to complete removal and replacement of partial depth concrete repairs, including, but not limited to:

The edges of the repair area shall be sawn to a minimum of 3 inches with a diamond or carborundum blade. Saw cuts which extend in concrete which will remain shall be only long enough to guarantee a full-depth cut of the repair area and shall be sealed according to Subsection 501-3. The concrete shall be removed by chipping or partial depth milling to remove the deteriorated or delaminated concrete. Removal of concrete by chipping shall be done using a 15 pound chipping hammer with a wide flat bit and hand tools. The CONTRACTOR shall insure that during removal of the concrete to maintain all sawcut edges and surrounding concrete from damages or spalls.

If when removing the pavement the thickness becomes greater than 4 inches and prior to the spall repair being completed the CONTRACTOR shall notify the ENGINEER. The ENGINEER may determine the extent of damage requires a full-depth repair. The ENGINEER shall determine the new extent and limits of the full depth repair.

The area to be repaired shall be sandblasted or pressure washed at minimum of 3,000 psi and clean with compressed air to remove loose particles and shall be done away from traffic lanes.

## SECTION 504 – CONCRETE PAVEMENT REPAIR

A joint spacer material shall be utilized as directed by the ENGINEER.

A thin layer of grout, or approved bonding agent, shall be applied to the clean surface and concrete shall be placed before the grout dries. If grout dries before concrete is placed the CONTRACTOR shall sandblast or pressure wash the repair to remove the dried grout, clean and re-grout the repair. Concrete shall be floated to a true and even plane and troweled.

Spall repairs shall be done when the air temperature is above 40°F and rising.

**504-3.3 FULL- DEPTH REPAIRS.** This item includes all work necessary to complete removal and replacement of full depth concrete repairs, including, but not limited to:

All edges of the repair area shall be sawn full depth with a diamond or carborundum blade. If the full depth cuts are made in more than one pass, the final depth cut shall be made immediately following the partial depth cuts. All cuts shall follow existing joints. Where cuts are done within a panel, transverse cuts shall be made perpendicular to centerline, and longitudinal cuts shall be made parallel to centerline. Saw cuts which extend into concrete which will remain shall be only long enough to guarantee a full depth cut of the repair area and shall be sealed according to Section 501-3.

The CONTRACTOR shall use the lift out method to removed concrete in full depth repair areas with minimal disruption to the subgrade/subbase and without damaging to the remaining concrete. Pulverization of the concrete by any method shall not be allowed, unless approved by the ENGINEER. Any damage to the concrete edge during the removal of concrete shall be repaired by the CONTRACTOR by a method approved by the ENGINEER at the CONTRACTOR's expense.

Subgrade/subbase voids deeper than 1 inch shall be filled with aggregate and compacted to the level of the existing subgrade meeting requirements of Section 302 or as directed by the ENGINEER. Any over depth removal unauthorized by the ENGINEER shall be replaced and compacted as above at the CONTRACTOR's expense.

At joints designated by the ENGINEER, reinforcement steel shall be drilled into existing concrete faces and sealed in accordance with Section 501-3.

Concrete repair areas that are less than 100 feet long shall be placed the same day of removal. Concrete repair areas that are longer than 100 feet shall be placed within 48 hours of removal.

All vertical edges of the repair shall be cleaned and free of dirt and joint sealant prior to placing concrete. Concrete for full depth repairs shall be high-early-strength concrete mix design in accordance with Section 501. Full depth repairs shall be finished so that all adjacent pavement surfaces are flush.

## SECTION 504 – CONCRETE PAVEMENT REPAIR

When adjacent concrete will be removed at a later date the CONTRACTOR shall utilize a bond breaker along the joint.

Where wooden stakes are used to support forms, rails or other objects, the wooden stakes shall be removed completely from the concrete prior to finishing. Steel stakes or other non-organic substitutes may remain in the pavement provided that the material is a minimum of 2 inches below the concrete surface.

Existing joints through an area of full depth repair, shall be sawed within 48 hours of concrete placement and sealed in accordance with Section 504. Mechanical jointing will not be allowed in these repair areas.

**504-3.4 JOINT SEALING.** This item includes all work necessary to complete removal and replacement of concrete joint sealant material, including, but not limited to:

Joint sealing for joints adjacent or included in full depth repairs shall be widened and sealed in accordance with Section 501.

Existing joints in concrete pavement that are not adjacent or included in full depth repairs shall be cleaned and sealed. Joints shall be mechanically cleaned of all existing joint sealant, backer rods, rocks, dirt, oil, asphalt, paint, rust, or other foreign matter using a high-velocity jet of compressed air with a minimum airflow of 185 cfm and 120 psi at the air nozzle. The nozzle shall be no less than 1/2 inch inside diameter utilizing a commercial grade air compressor. A leaf blower shall NOT be an acceptable substitute for compressed air. Backer rods, if utilized, shall be 25 percent larger than joint width and installed full length of joint. The joint faces shall be clean and dry when sealant is applied. Sealant shall be installed according to Section 501. Sealant shall be installed from inside the joint with an approved mechanical device.

Compression joint material within 1/2 inch from surface of pavement shall be removed and sealed..

**504-3.5 RANDOM CRACK WIDEN AND SEAL.** This item includes all work necessary to complete random crack widening and sealing, including, but not limited to:

Random cracks in concrete pavement shall be widened and sealed as directed by the ENGINEER and according to Section 501. Random cracks to be sealed by this method shall be marked by the ENGINEER in the field.

**504-3.6 RANDOM CRACK CLEAN AND SEAL.** This item includes all work necessary to complete random crack cleaning and sealing, including, but not limited to:

Random cracks in concrete pavement shall be cleaned and sealed as directed by the ENGINEER and according to Section 501. Random cracks to be sealed by this method shall be marked by the ENGINEER in the field.

## SECTION 504 – CONCRETE PAVEMENT REPAIR

**504-3.7 FIELD QUALITY CONTROL.** Field quality control testing shall conform to Section 501 “Field Quality Control”.

### **504-4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107 and as follows:

**504-4.1 JOINT SEALING.** Joint Sealing shall be paid per plan quantity.

## DIVISION 600

### CONCRETE SIDEWALKS, DRIVEWAYS, AND CURB AND GUTTER

#### SECTION 601 – CONCRETE SIDEWALKS

##### 601-1 DESCRIPTION

This work shall consist of the construction of air-entrained portland cement concrete sidewalks in accordance with these specifications and standard details at the locations and to the lines and grades shown on the plans or as directed by the ENGINEER. This work shall also include the removal of sidewalk or block walk, when listed on the proposal, as shown on the plans, or as directed by the ENGINEER.

The construction of concrete sidewalks in or along any street shall be executed in strict conformity with the provisions of the City Ordinances.

##### 601-2 MATERIALS

**601-2.1 GENERAL.** Materials shall meet the requirements of Section 501-2 with the following additional provisions.

**601-2.2 PORTLAND CEMENT.** Type IL, Type 1, or Type 1A will be allowed.

**601-2.3 FLY ASH.** Fly ash shall conform to the requirements listed in Section 501.

**601-2.4 DETECTABLE WARNING PANELS.** The following detectable warning panel cast-in-place systems have been pre-approved:

- Advantage Tactile Systems - Advantage Cast Iron Premier ADA Tactile Detectable Warning Tile
- TufTile - Cast Iron ADA Detectable Warning Tile
- TufTile - 10 guage Galvanized Steel Detectable Warning panel
- ADA Arcis Tactile
- Detectable Warning Paver by Hanover Architectural Products
- Cast Iron Coated by East Jordan Iron Works
- ADA Replaceable (Wet-Set) Stainless Steel Tactile Unit by ADA Solutions, Inc
- Stainless Steel Detectable Warning Tile by Advantage Tactile Systems, Inc.
- MetalPanel by Metadome, LLC
- Access Tile by Access Products, Inc.
- Neenah Foundry Detectable Warning Plates

## SECTION 601 – CONCRETE SIDEWALKS

Detectable warning panels shall consist of a surface of truncated domes aligned in a square grid pattern in the predominant direction of travel.

**Dome Size:** Truncated domes in a detectable warning surface shall have a base diameter of 0.9 inches minimum to 1.4 inches maximum, a top diameter of 50 percent of the base diameter minimum to 65 percent of the base diameter maximum, and a height of 0.2 inches.

**Dome Spacing:** Truncated domes in a detectable warning surface shall have a center-to-center spacing of 1.6 inches minimum and 2.4 inches maximum and a base-to-base spacing of 0.65 inches minimum measured between the most adjacent domes on the square grid.

Detectable warning panels shall be safety yellow, U.S.-ANSI Z535.1-1991, unless otherwise directed by the ENGINEER.

**601-2.5 STEEL REINFORCEMENT.** All steel used for reinforcement in sidewalks shall be Grade 40 or higher and conform to Section 501-2 with the following addition:

Epoxy coating for steel reinforcement for sidewalks may not be required at the discretion of the ENGINEER.

Fiberglass rebar may be used in lieu of #4 steel reinforcement in the construction of sidewalks and driveways, fiberglass rebar shall be #3 or #4 Owens Corning, #3 or #4 Gatorbar or approved equal. Fiberglass rebar shall meet ASTM D7957.

**601-2.6 AGGREGATE BASE.** Aggregate base for sidewalks shall be Class 5, blended base or recycled concrete as per Section 302.

**601-2.7 MACRO-FIBER REINFORCEMENT.** Macro-fiber reinforcement shall meet requirements of ASTM C1116 and shall be Type III synthetic. Reinforcing fibers shall be a minimum one and one-half inches (1.5”) in length. Any fibers utilized must be approved by the ENGINEER prior to usage. The following fibers have been pre-approved: Fibermix PolyMesh, Euclid Tuf-Strand SF & MasterFiber MAC Matrix.

### 601-3 CONSTRUCTION REQUIREMENTS

Construction requirements shall conform to Section 501-3 with the following additional provisions:

**601-3.1 SIDEWALK CONCRETE REMOVAL.** All concrete removed shall be disposed of in accordance with Section 501.

**601-3.2 JOINTS.** Expansion joints shall be placed in sidewalk concrete at intervals as shown on the standard details or as directed by the ENGINEER. Expansion joints shall

## SECTION 601 – CONCRETE SIDEWALKS

be used when adjoining private concrete slabs unless otherwise approved by the ENGINEER. The expansion joint material shall have a thickness of 1/2 inch to 3/4 inch.

The sidewalk concrete shall be divided into sections by contraction joints formed by a jointing tool or sawing.

**601-3.3 FORMS.** Forms shall conform to Section 501-3. Forms for use on curves shall be capable of installation to within 1/2 inch of the true curve; if the radius is less than 400 feet, the forms shall be either flexible material or shaped to fit the curve.

**601-3.4 AGGREGATE BASE.** Unless otherwise specified, all new and replacement sidewalk installation shall have aggregate base installed, per Section 302, to the width of the sidewalk plus 0.5' (extended 0.25' on each side). The thickness shall be as per the table below:

	Concrete Thickness	Min. Base Thickness
Sidewalk	4"	2"
ADA Ramps	6"	2"
Driveways - Residential	6"	2"
Driveways - Residential*	8"	2"
Driveways - Commercial	8"	6"
Trench Drains	6"	2"
Valley Gutters	8"	6"

\*Residential Driveways with load concerns as determined by engineer

**601-3.5 CONCRETE STAMPS.** The CONTRACTOR shall mark at the ends of the sidewalk, either by stamping or by inlaying an approved metal plate, which shall conform to Section 501-3.

**601-3.6 BACKFILL.** The four inch concrete shall be backfilled within 14 days of placement to a level width of at least two feet along all edges and to a height equal to the top finished grade of the sidewalk. The backfill shall be compacted in accordance with Section 202 "Excavation and Embankment."

**601-3.7 SIDEWALK EXPANSION JOINT WITH REINFORCING STEEL.** Expansion joints shall be doweled in accordance with standard details. Reinforcing steel shall be 1/2 inch by 12 inches long, smooth or #4 bar by 12 inches deformed (reinforcing bar). Reinforcing Steel shall be centered on the slab parallel to the surface of the slab at 12-inch centers. Paper tubes or speed dowels shall be used at the expansion joint. Expansion joints with reinforcing steel shall be incidental to other bid items.

## SECTION 601 – CONCRETE SIDEWALKS

**601-3.8 CONCRETE QUALITY CONTROL AND SUBGRADE TESTING.** Testing frequencies shall conform to Section 501-3. Payment shall be considered incidental to other bid items.

**601-3.9 ADA CURB RAMPS.** ADA curb ramps must be installed when installation of new sidewalks, new asphaltic or concrete pavements, and repair of existing sidewalks, curbs, valley gutters, and utility cuts are made at an intersection. For any repair done to an existing ADA curb ramp that does not have the detectable warning panels for each direction of the ramp, the CONTRACTOR shall remove the additional concrete to install a detectable warning panel.

The ADA curb ramps shall be tied to adjacent concrete pavements and curb with one foot #4 reinforcing steel spaced at one foot centers.

The curb ramp landing lengths, directions, and placements of the detectable warning panels shall be determined by the ENGINEER in the field.

Curb ramps installed prior to installation of adjacent sidewalk shall be placed such that the top of the ramp matches the low side of the future sidewalk. The top of ramp elevation shall comply with ADA standards and the City of Bismarck Standards for placement and elevations of sidewalks as per Standard Drawing 600-18.

The ADA curb ramps for new asphaltic pavements or concrete pavements shall be protected by steel fence posts until construction of adjacent sidewalks is completed. The number of fence posts and the location shall be in accordance with Standard Details or shall be determined by the ENGINEER. Cost of furnishing and installing steel fence posts shall be considered incidental to the price bid for “Detectable Warning Panel and Detectable Warning Panel CI.”

Detectable warning surface shall extend 24 inches in the direction of pedestrian traffic and the full width of the curb ramp landing.

The detectable warning surface shall be located so that the nearest edge is 6 inches minimum and 8 inches maximum from the face of the curb, or determined by the ENGINEER in the field.

The detectable warning panels shall be installed according to the manufacturer’s recommendation and in accordance with Standard Details 600-3 and 600-4.

When installing ADA ramps with two directional ramps, the distance between the ramps must be no less than three feet. If three feet cannot be maintained between the ramps, a full drop radius ramp shall be installed.

ADA ramps installed as part of new roadway paving project shall have “T” post installed on property line at the center of each new panel. Costs shall be incidental to concrete.

## SECTION 601 – CONCRETE SIDEWALKS

**601-3.10 SIDEWALK TRENCH DRAIN.** Sidewalk trench drains shall be installed to the dimensions shown on the plans and in accordance with Standard Detail 600-5. All costs of labor, materials, and equipment to install sidewalk trench drains shall be included in the price for “Sidewalk Trench Drain.”

**601-3.11 RELOCATION OF LAWN IRRIGATION SYSTEM.** Any concrete work requiring the relocation of any part of a lawn irrigation system shall be paid for as extra work as outlined in Section 104.

**601-3.12 MACRO-FIBER REINFORCED CONCRETE.** All sidewalk concrete shall contain macro-fiber reinforcement unless otherwise directed by the ENGINEER. All macro-fiber shall be in conformance with 601-2.7. Dosage of macro-fiber shall be per the manufacturer recommended dosage rates. The cost for macro-fiber reinforcement shall be considered incidental.

**601-3.13 UNCONTROLLED CRACKING.** Section 501-3.8 does not apply to sidewalks, driveways or curb and gutter. Panels shall be replaced if multiple cracks occur within 2 years of acceptance. Panels with a single crack may be accepted if crack does not exceed ¼” displacement vertically or horizontally, if crack exceeds this displacement within 2 years of acceptance, panel shall be replaced.

All crack repairs and/or panel replacement shall be at CONTRACTOR's expense.

### **601-4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107 and as follows:

**601-4.1 AGGREGATE BASE FOR SIDEWALKS.** Aggregate base for sidewalks shall be paid under contract item “Blended Base” at plan quantity as calculated from the required width and depth given in Section 601-3.4

## **SECTION 602 – CONCRETE DRIVEWAYS**

### **602-1 DESCRIPTION**

This work shall consist of new installation, removal, replacement and/or widening of existing driveways. Construction shall utilize air-entrained portland cement 6-inch for residential construction or 8-inch for commercial construction in accordance with these specifications, standards and standard detail drawings at the locations and to the lines and grades shown on the plans or as directed by the ENGINEER.

The construction of concrete driveways on the public right-of-way shall be as per City Ordinances and Standard Drawing 600-19.

### **602-2 MATERIALS**

Materials for portland cement concrete shall meet the requirements of Sections 501 and 601.

### **602-3 CONSTRUCTION REQUIREMENTS**

Construction requirements shall conform to Section 501 with the following additional provisions:

**602-3.1 CONTRACTOR'S STAMP OR NAME PLATE.** The CONTRACTOR shall mark in each driveway, either by stamping or by inlaying, an approved metal plate conforming to Section 501.

**602-3.2 AGGREGATE BASE.** All new and replacement driveway installation shall have aggregate base installed, per Section 302, to the width of the driveway plus 0.5' (extended 0.25' on each side). The thickness shall be as per Section 601.

**602-3.3 BACKFILL.** Concrete shall be backfilled within 14 days of placement to a level width of at least two feet along all edges and to a height equal to the top finished grade of the driveway, including topsoil. The backfill shall be compacted in accordance with Section 202 "Excavation and Embankment."

**602-3.4 CONCRETE REMOVAL.** Concrete removal and disposal shall be in accordance with Section 501.

**602-3.5 SEALING JOINT.** Joint sealing shall be in accordance with Section 501, with the following exception: Joints shall be sealed prior to the substantial completion date of the project.

Joint sealing shall be incidental to other bid items.

## SECTION 602 – CONCRETE DRIVEWAYS

**602-3.6 TREE REMOVAL OR TREE ROOT CUTTING.** Construction methods and measurement and payment shall be as per Section 201.

**602-3.7 FORMS.** Forms shall conform to Section 501. All driveway forms for 6-inch or 8-inch concrete shall be set at a 90-degree angle to the street or curb and gutter alignment, unless otherwise approved by the ENGINEER.

**602-3.8 JOINTS.** Expansion joint materials shall not be used in 6-inch or 8-inch concrete aprons unless approved by the ENGINEER. Jointing shall conform to Detail Drawings 600-7 and 600-8 or joints approved by the ENGINEER. Jointing shall be done with appropriate jointing tools or sawed. All joints sawed into driveways must be sawed with a double blade in order for joint sealant to be installed to proper width and depth.

Joints for driveways adjacent to existing concrete streets shall follow the joint pattern of the existing concrete pavement. Other joints, such as in flare cuts, shall be allowed without following the joint pattern of the existing concrete pavement.

**602-3.9 REINFORCING STEEL.** Reinforcing steel shall be used for six inch or eight inch driveways where the new concrete meets the sidewalk section, keyways shall not be allowed. Reinforcing steel shall be 1/2 by 12 inches long smooth or #4 by 12 inches deformed (reinforcing bar). Reinforcing steel shall be drilled in at two feet on center. When using 1/2-inch drill bit, paper tubes or speed dowels shall be used.

For driveway widening, reinforcing steel shall be drilled at one foot on center for the entire length of the existing driveway. When using 1/2-inch drill bit, paper tubes or speed dowels shall be used.

When curbing for the driveway exists, the CONTRACTOR shall drill into the existing curb at two feet on center. When using 1/2-inch drill bit, paper tubes or speed dowels shall be used.

Epoxy coating for steel reinforcement for driveways may not be required at the discretion of the ENGINEER.

Fiberglass rebar may be used in lieu of #4 steel reinforcement in the construction of sidewalks and driveways, fiberglass rebar shall as per Section 601.

**602-3.10 CONCRETE QUALITY CONTROL AND SUBGRADE TESTING.** Testing shall conform to Section 501. Payment shall be considered incidental to other bid items.

**602-3.11 MACRO-FIBER REINFORCED CONCRETE.** All driveway concrete shall contain macro-fiber reinforcement unless otherwise directed by the ENGINEER. All macro-fiber shall be in conformance with 601-2.7. Dosage of macro-fiber shall be per the manufacturer recommended dosage rates. The cost for macro-fiber reinforcement shall be considered incidental.

## SECTION 602 – CONCRETE DRIVEWAYS

**602-3.12 UNCONTROLLED CRACKING.** Uncontrolled cracking shall be repaired as per Section 601.

### **602-4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107 and as follows:

**602-4.1 AGGREGATE BASE FOR DRIVEWAYS.** Aggregate base for driveways shall be paid under bid item “Blended Base” at plan quantity as calculated from the required width and depth given in Section 602-3.2.

## **SECTION 603 – CONCRETE CURB AND COMBINED CURB AND GUTTER**

### **603-1 DESCRIPTION**

This work shall consist of the construction of air-entrained portland cement concrete standard curb, combined curb and gutter with six or eight inch gutters sections, and mountable curb and gutter in accordance with these specifications and standard details at the locations and to the lines and grades shown on the plans or as directed by the ENGINEER.

This work shall also include the removal of old curbing and curb and gutter when listed on the proposal, as shown on the plans, or as directed by the ENGINEER.

### **603-2 MATERIALS**

**603-2.1** Materials shall meet the requirements of Section 501.

### **603-3 CLASSIFICATION**

**603-3.1 STANDARD CURB.** The curb constructed under this designation shall be one course, unreinforced or reinforced concrete construction as shown on the standard details. All curbing constructed on a straight line or on a curve shall be considered standard curb.

**603-3.2 STANDARD CURB AND GUTTER.** The work to be completed under this item shall be one-course, reinforced or unreinforced concrete construction as shown on the standard details as a combined curb and gutter section. When constructed in conjunction with an asphalt street, six inch gutter sections shall be used in residential areas and eight inch gutter sections shall be used in all commercial sites unless otherwise stated on plans. On concrete streets, gutter section shall match thickness of street, unless otherwise stated on plans. All curb and gutter constructed on a straight line or on a curve shall be considered standard curb and gutter.

**603-3.3 MOUNTABLE CURB AND GUTTER.** The work to be completed under this item shall be one-course, reinforced or unreinforced concrete construction as shown on the standard details as a combined mountable curb and gutter section. All mountable curb and gutter constructed on a straight line or on a curve under this item shall be classified as mountable curb and gutter.

### **603-4 CONSTRUCTION REQUIREMENTS**

Construction requirements shall conform to Section 501 and as follows:

## SECTION 603 – CONCRETE CURB AND COMBINED CURB AND GUTTER

**603-4.1 GENERAL.** The curb and curb and gutter constructed under this item shall be one-course concrete construction.

When curb and gutter sections are removed for repairs or new construction of driveways or a valley gutter, the curb and gutter shall be removed to the nearest joint or as directed by the ENGINEER. If the existing curb is cracked, the cracked joint shall be sawed. The sawed joint shall be no closer than 5 feet to the existing joint in place. All jagged joints shall be sawed. Sawing shall be incidental to other bid items.

When new curb and gutter is installed and ends do not tie into an existing curb, the ends of the curb and gutter shall have the curb tapered down from six inches to one inch over two feet in length.

**603-4.2 FORMS.** Forms for use on curves shall be capable of installation to within 1/2 inch of the true curve, and if the radius is less than 400 feet, they shall be either flexible material or shaped to fit the curve. On small radius curves such as driveways and street intersections, the CONTRACTOR may use Masonite or approved equivalent, metal, or 1/2 inch dimension lumber.

**603-4.3 DOWEL BARS.** All dowel bars as detailed shall be considered incidental to each item of curb or curb and gutter construction.

**603-4.4 DOWELED EXPANSION JOINTS.** Doweled expansion joints shall consist of two dowels, one expansion boot or three reinforcement bars, and one expansion boot in accordance with Sections 501 "Expansion Joint Material" or 501 "Reinforcing Steel." Doweled expansion joint boots shall be 1/2 to 1/4 inch lower than the surfaces of the top of the curb and gutter.

One doweled expansion joint shall be placed every 100 feet on any new or repaired curb and gutter sections and at both ends of street intersection radii or as determined by the ENGINEER.

Every attempt should be made to center or position the doweled expansion joint to improve the overall appearance of the curb and gutter section.

**603-4.5 SURFACE FINISH.** The final surface finish shall be obtained by uniformly brushing or brooming the surface. No plastering will be permitted unless approved by the ENGINEER.

**603-4.6 BACKFILL.** The curbing shall be backfilled within 14 days of placement to a level width of at least two feet along the front of the gutter and back of the curb to a height equal to the top finished grade of the curbing. The backfill shall be compacted in accordance with Section 202 "Excavation and Embankment."

**603-4.7 CONTRACTOR'S STAMP OR NAME PLATE.** CONTRACTOR shall mark every 100 linear feet for continuous pours of new curb and gutter laid, and every curb

## SECTION 603 – CONCRETE CURB AND COMBINED CURB AND GUTTER

and gutter patch done per city lot, by stamping or by inlaying an approved metal plate conforming to Section 501.

**603-4.8 CURB OR CURB AND GUTTER REMOVAL.** All curb or curb and gutter removed shall be removed and disposed of in accordance with Section 501.

**603-4.9 CURB AND GUTTER EXTRUSION MACHINE.** This type of machine shall be capable of producing concrete curb, curb and gutter, or mountable curb and gutter to conform to the requirements of this section and line, grade, shape, and dimensions given in the plans and specifications or approved by the ENGINEER using materials conforming to the specifications.

The CONTRACTOR shall provide the ENGINEER with the following information prior to being given permission to produce a test section with the machine:

- a. Complete machine specifications regarding the machine and its performance.
- b. Details of the proposed section of curb or curb and gutter to be produced by the machine.
- c. Provide evidence of having previous experience of operating and maintaining the proposed machine.

If the above items are found to be satisfactory to the ENGINEER, written permission will be given to the CONTRACTOR to provide a 100-foot test section in place with the proposed machine.

If the manufacture of the test section and the performance of the extrusion machine prove to be satisfactory, the ENGINEER shall then issue final written approval to the CONTRACTOR. If, during the course of construction on the project, manufacture and performance becomes unsatisfactory, the ENGINEER shall disallow the continued use of said machine.

**603-4.10 SEALING JOINTS.** All expansion joints shall be sealed in accordance with Section 501.

**603-4.11 CONCRETE QUALITY CONTROL AND SUBGRADE TESTING.** Testing shall meet the requirements of Section 501. Payment shall be considered incidental.

**603-4.12 UNCONTROLLED CRACKING.** Uncontrolled cracking shall be repaired as per Section 601.

### 603-5 MEASUREMENT AND PAYMENT

Measurement and payment shall be as specified in Section 107 and as follows:

**603-5.1 STANDARD CURB.** Standard Curb shall be measured along face of curb.

## SECTION 603 – CONCRETE CURB AND COMBINED CURB AND GUTTER

**603-5.2 CURB AND GUTTER.** Curb and Gutter shall be measured along face of curb. When reinforcing steel is required, the reinforcing steel shall be considered incidental.

**603-5.3 CURB AND GUTTER REMOVAL.** Curb and Gutter Removed shall be measured by the linear foot along the face of the curb.

## DIVISION 800

### SEWERS

#### SECTION 801 – SANITARY SEWER

##### 801-1 DESCRIPTION

This item shall consist of pipe of the types, classes, sizes, and dimensions required on the plans, and furnished and installed at the places designated on the plans and profiles or by the ENGINEER in accordance with these specifications and with the lines and grades given.

The bid price per linear foot of pipe in place shall include the cost of excavation and backfill, the cost of furnishing and installing all trench bracing, all fittings required to complete the sewer pipe as shown on the plans, and the material for and the making of all joints, including all connections to existing sewer pipe and manholes.

"Unstable," "Unsuitable," "Suitable," and "Unsatisfactory" soil or aggregate items shall be defined as stated in Section 202.

##### 801-2 MATERIALS

**801-2.1 GENERAL.** The pipe shall be of the type selected by the CONTRACTOR and shall be in accordance with the following appropriate requirements unless otherwise specified.

**801-2.2 CONCRETE SANITARY SEWER PIPE.** Concrete sanitary sewer pipe, reinforced, shall conform to the requirements of ASTM C76.

**801-2.3 POLYVINYL CHLORIDE SANITARY SEWER PIPE.** Polyvinyl chloride sanitary sewer (PVC) pipe 15 inches or smaller shall conform to the requirements of ASTM D3034 for type PSM. PVC sewer pipe and fittings with a bury depth less than 18 feet shall have an SDR of 35. PVC sewer pipe with a bury depth equal to or greater than 18 feet shall have an SDR of 26. Pipe must be of the same type and have the same SDR for full run lengths between manholes. Pipe specifications must be stamped on the pipe.

Polyvinyl chloride sewer pipe 18 inches or larger shall conform to the requirements of ASTM F679-PS46. PVC sewer main line pipe and PVC sewer service pipe shall have the elastomeric gasket-type joint providing a watertight seal. A solvent cement-type joint will not be allowed. PVC wye branches shall be of the "factory assembled type."

## SECTION 801 – SANITARY SEWER

### **801-2.4 RUBBER GASKET JOINT FOR CONCRETE SANITARY SEWER PIPE.**

Rubber-type gaskets for concrete non-pressure pipe shall conform to the requirements of ASTM C443 or ASTM C361.

**801-2.5 MORTAR.** Mortar for connections to manholes shall be composed of one part, by volume, of portland cement and two parts of mortar sand. The portland cement shall conform to the requirements of Section 501. The sand shall conform to the requirements of Section 501. Hydrated lime may be added to the mixture of sand and cement in an amount equal to 15 percent of the volume of cement used. The hydrated lime shall meet the requirements of ASTM C6.

**801-2.6 RUBBER GASKET JOINT FOR PVC SEWER PIPE.** Rubber gaskets for PVC sewer pipe joints shall be of the elastomeric type providing a watertight seal and shall conform to ASTM D3212.

**801-2.7 CONCRETE.** Concrete for pipe cradles and saddles shall conform to the requirements of Section 501.

**801-2.8 BEDDING MATERIAL.** The bedding material shall consist of granular material in accordance with the requirements for gradation shown in the following table:

<b>Square Mesh Sieve Size</b>	<b>Percent by Weight Passing</b>
2"	100%
1"	90-100%
3/4"	80-100%
No. 4	30-90%
No. 30	10-60%
No. 100	0-15%

One gradation test shall be made for each source and change in material provided for each 500 tons of screened and/or blended material and for each 200 tons of non-screened or "bank run" material. Gradation testing shall be incidental to the pipe or other bid items.

The CONTRACTOR may provide a controlled density fill in lieu of the bedding material bed for underground pipe if approved by the ENGINEER prior to installation. The controlled density fill shall conform to Section 503.

If the controlled density fill is placed in the trench in a plastic state, the remaining backfill may not be completed for 48 hours. One compression test shall be made for each 60 cubic yards of control density fill or a minimum of one per day. A testing firm normally engaged in materials testing shall make the test at the expense of the CONTRACTOR. The CONTRACTOR shall remove and replace any material not meeting the requirements at CONTRACTOR's expense. All controlled density fill shall be designed

## SECTION 801 – SANITARY SEWER

for easy removal should it become necessary to repair or remove the pipe in the future. The pipe shall be protected from floating to maintain line and grade.

Controlled density fill shall be paid as bedding material unless otherwise specified. Controlled density fill utilized on the remainder of the trench may be provided incidental if approved by the ENGINEER.

Bedding quantities are based on trench width in Section 801 "Excavation and Preparation of Trench." Any additional bedding material due to a wider ditch shall be the responsibility of the CONTRACTOR.

**801-2.9 SUBCUT GRAVEL.** The subcut gravel shall consist of granular material in accordance with the requirements of gradation shown in the following table:

Square Mesh	Percent by Weight Passing
2"	100%
No. 4	0-10%

**801-2.10 MARKING TAPE.** The CONTRACTOR will be required to furnish and install marking tape located two feet above the top of all sanitary sewer mains installed under the contract. The tape shall be of the non-detectable type and shall have a minimum width of five inches. The tape shall be green in color with the words "CAUTION SEWER LINE BELOW" imprinted on the tape in black capital letters. The marking tape shall be equal to that manufactured by Presco standard grade.

Cost of marking tape and installation shall be considered incidental to other items.

**801-2.11 SANITARY SEWER FORCE MAIN MATERIALS.** All materials for construction of sanitary sewer force mains shall conform to Section 901 "Water Mains."

**801-2.12 SANITARY SEWER WYE BRANCHES.** Wye branches shall be of the same material as the main line sanitary sewer pipe.

**801-2.13 INSULATION BOARDS.** Insulation boards shall conform to Section 901.

### 801-3 CONSTRUCTION REQUIREMENTS

**801-3.1 EQUIPMENT.** All equipment necessary and required for the proper construction of sanitary sewers shall be on the project in first-class working condition and approved by the ENGINEER before construction is permitted to start.

The CONTRACTOR shall handle the pipe while unloading and placing it in its final position without damage to the pipe.

## SECTION 801 – SANITARY SEWER

The CONTRACTOR shall provide methods and means to obtain the required compaction of the pipe bed and the backfill as specified.

The CONTRACTOR shall provide a sufficient number of watertight sewer plugs to prevent infiltration of water and any other foreign material from entering the existing sewer system and the newly constructed sewer lines.

**801-3.2 EXCAVATION AND PREPARATION OF TRENCH.** The trench shall be dug to the alignment and depth required and only so far in advance of pipe laying as the ENGINEER may permit. The discharge from pumps shall be led to natural drainage channels, drains, or storm sewer as per erosion control and storm water pollution control standards.

The trench width may vary depending upon the depth of the trench and the nature of the excavated material but shall be of ample width to permit the pipe to be laid and joined properly and the backfill to be placed and compacted to the required density. The maximum width of trench for calculating bedding material quantities for pipe sizes 15 inches and larger shall not be more than 36 inches greater than the outside diameter of the pipe barrel. For pipe sizes under 15 inches, the maximum width shall be no more than 48 inches.

The trench shall be excavated below the required grade so that the pipe may be laid on four inches of bedding material. See Standard Detail 801-2.

Where the bottom of the trench uncovered at subgrade is unsuitable and, in the opinion of the ENGINEER, cannot support the pipe, further depth and/or width shall be excavated and refilled to the pipe foundation grade with subcut gravel thoroughly compacted. In this instance, subcut gravel shall be considered a pay item.

If other approved means shall be adopted to assure a firm foundation for the pipe, the CONTRACTOR will be allowed extra compensation. Extra compensation shall not be allowed for extra excavation and gravel used for seepage and ground water control.

If ordered in writing by the ENGINEER, the CONTRACTOR will be paid for any sheathing that the ENGINEER orders left in the trench in order to protect existing utilities or other items. The price to be paid for such sheathing material will be the current invoice price of said materials or such lesser price as the CONTRACTOR and the ENGINEER may agree that the material is worth at the time it is left in the trench.

All broken pavement or sidewalks shall be removed from the site of the work and deposited at a place approved by the ENGINEER. It shall be the responsibility of the CONTRACTOR to remove and replace at its own expense all sidewalk and curb and gutter necessary for the installation of the pipe and manholes as shown on the plans and as directed by the ENGINEER, unless items are noted on plans. The removal shall be complete to the nearest joint. No additional compensation will be allowed for this work and shall be included in the price bid for pipe or manhole installation. Replacement of sidewalk and curb and gutter shall be as per Section 600.

## SECTION 801 – SANITARY SEWER

Bell holes of ample dimension shall be dug in earth trenches at each joint to permit the joints to be made properly.

All excavated material shall be piled in a manner that will not endanger the work and that will avoid obstructing sidewalks and driveways. Gutters shall be kept clean or otherwise satisfactory provisions made for street drainage.

The use of trench digging machinery will be permitted except in places where operation of same will cause damage to trees, buildings, or existing structures above or below ground, in which case hand methods shall be employed.

The CONTRACTOR is assumed to be familiar with all federal, state, and local laws, codes, ordinances, and regulations which in any manner affect those engaged or employed in the work, the material, or equipment used in or upon the site, or in any way affect the conduct of the work. No pleas of misunderstanding or ignorance on the part of the CONTRACTOR will, in any way, serve to modify the provisions of the contract. The CONTRACTOR shall provide and maintain on a 24-hour basis all necessary safeguards such as watchmen, traffic control devices, and night lights at CONTRACTOR's expense in accordance with Section 103-5.

Excavation for pipe laying operations shall be conducted in a manner so as to cause the least interruption to traffic. Where traffic must cross open trenches, the CONTRACTOR shall provide suitable bridges at street intersections and driveways. Hydrants under pressure, valve boxes, curb stop boxes, and other utility controls shall be left unobstructed and accessible during the construction period.

Adequate provisions shall be made for the flow of sewers, drains, and water courses encountered during construction, and the structures which may have been disturbed shall be satisfactorily restored upon completion of the work.

Prior to making any connections to the existing sanitary sewer system, the CONTRACTOR shall furnish and install watertight plugs in such a manner as to prevent infiltration and foreign material from entering the existing sewer system. The plugs shall be installed so as to not disrupt existing sewage flow and shall remain in place until the construction has been accepted by the ENGINEER.

Trees, fences, poles, and all other property shall be protected unless their removal is authorized by the ENGINEER, and any property damages shall be satisfactorily restored by the CONTRACTOR. The cost of removal shall be included in the price bid per linear foot of sewer pipe in place unless listed separately in the proposal. Tree removal and root cutting shall be in conformance with Section 201.

**801-3.3 ROCK EXCAVATION.** All rock found in the trench area shall be classified as solid rock and measured for payment if each individual rock, boulder, or continuous slab of ledge rock is 1 cubic foot or more in content. Solid rock shall be measured for payment on the basis of and limited to the maximum trench width allowed under Section 801 "Excavation and Preparation of Trench." If solid rock extends below the necessary

## SECTION 801 – SANITARY SEWER

depth of excavation, it shall be measured for payment to a horizontal plane 6 inches below the bottom of the pipe. All rocks smaller in volume than 1 cubic foot shall not be classified as solid rock, but may be used in backfilling as directed by the ENGINEER.

Whenever ledge rock is encountered, the CONTRACTOR shall strip all overlying earth and he shall then notify the ENGINEER that the rock is ready for measurement. The ENGINEER may then take levels upon the rock or he may at his discretion defer measurement until after the excavation is completed. CONTRACTOR shall not refill any trench where rock is encountered until notified by the ENGINEER that measurement has been made. Payment will not be allowed for any rock unless measurement has been made as herein provided. The rock shall be excavated to a depth of six inches below the bottom of the pipe, and the trench shall be refilled to the proper grade with bedding material.

All rock found in the trench having greater volume of 1 cubic foot shall not be used as backfill but shall be disposed of as directed by the ENGINEER.

**801-3.4 PIPE LAYING.** All watermain and sanitary sewer crossings shall conform to the following:

- a. Where both water and sewer are of new construction:
  1. No additional protections needed if water main crosses at least 5 feet above the sewer.
  2. If the water main crosses within 3 to 5 feet above the sewer, a full length of water main shall be centered over the sewer.
  3. If the water main crosses within 3 feet above the sewer, a full length of water main shall be centered over the sewer, and the sewer joints located within 10 feet of the crossing shall be able to withstand 25 psi internal pressure.
- b. Where water main crosses over an existing sewer:
  1. No additional protection needed if water main is at least 3 feet above the sewer. The intervening dirt must be left undisturbed.
  2. If crossing is within 3 feet above sewer, a full length of water main must be centered over the sewer main.
- c. Where water main crosses under the sewer:
  1. In all cases, additional protection shall be provided by centering a full length of water main under the sewer main. All sewer joints located within 10 feet of the crossing shall be able to withstand 25 psi internal pressure.

Proper implements, tools, and equipment satisfactory to the ENGINEER shall be provided and used by the CONTRACTOR for the safe and convenient prosecution of the work. All pipe and fittings shall be carefully lowered into the trench piece by piece by means of a derrick, ropes, or other suitable tools or equipment in such a manner as to prevent damage to the pipe. Under no circumstance shall pipe be dropped or dumped into the trench.

## SECTION 801 – SANITARY SEWER

After the trench has been excavated to the proper grade, the first pipe at the outlet end of the sewer shall be bedded to the proper line and grade with the bell end upstream. All pipe shall be laid to line and grade. The pipe shall be held in place by backfilling along the bottom and sides of the pipe section with bedding material thoroughly tamped up to the centerline of the pipe and protected from movement.

During the pipe laying operation, the CONTRACTOR shall have a watertight plug available to install in the last pipe laid at the end of each work day, or to install during the work day, to prevent water, sediment, or other foreign material from entering the newly installed pipe.

Wyes for sanitary sewer connections shall be installed at an angle between 10 and 80 degrees from vertical.

The CONTRACTOR shall exercise due care so as to prevent water and other foreign matter from entering the newly constructed sewer mains at new manhole locations.

All joints shall be installed in accordance with the pipe manufacturer's instructions.

Where polyvinyl chloride sewer pipe is installed in a vitrified clay sewer line, V.C. to PVC adaptors shall be used at each junction. Adapters shall be Shear Guard repair couplers as manufactured by Indiana Seal, or approved equivalent.

The cost of adapters shall be considered incidental to the unit price bid for cast iron sewer pipe or polyvinyl chloride sewer pipe.

The interior of the pipe shall be cleaned as the work progresses. The manholes and sewer pipe shall be flushed with clean water after completion and prior to acceptance by the ENGINEER.

All connections to existing utilities shall be considered incidental to other bid items.

**801-3.5 BACKFILLING OF PIPE TRENCH.** After the pipe has been laid to line and grade, the trench shall be backfilled under and along the sides of the pipe up to the centerline of the pipe by thoroughly compacting bedding material into place so as to form a uniform bed for the pipe. The compaction may be obtained by any approved method or equipment which will produce a uniform density meeting the requirement to obtain not less than 85 percent maximum dry density at optimum moisture made in accordance with ASTM D1557 (modified proctor). Care shall be exercised not to displace the pipe or damage the pipe during the compaction operations. If the material in the trench is sand or gravel and acceptable to the ENGINEER, it will not be necessary to furnish any other material than that found within the trench to backfill up to the centerline of the pipe. If sand or gravel is not found within the trench, the CONTRACTOR will be required to furnish bedding material as per Pipe Bedding Standard Plate. CONTRACTOR shall keep the bedding completed within 3 lengths of the last pipe being laid and bedding for all pipe installed shall be completed at the end of each day's work.

## SECTION 801 – SANITARY SEWER

After the pipe has been inspected and bedding material is in place, two feet of backfill shall be placed over the pipe to prevent damage to the installed pipe. The remaining trench shall be backfilled as per Section 801-3.6. On all areas outside of the pavement, curb and gutter, and sidewalk areas, no compaction will be required on the top 4 inches.

The use of drop pile hammers, loaded or unloaded clam shells or backhoe buckets, or other similar equipment will not be permitted to obtain the required density. The CONTRACTOR shall use specialized equipment or hand tamping around appurtenances such as manholes to ensure proper density. The remaining trench shall be backfilled in accordance with the specifications for the class of backfill as set forth in Section 801-3.6. The areas for each class of backfill specified shall be designated on the plans.

The CONTRACTOR shall engage an independent soils testing laboratory, approved by the ENGINEER, to determine the soil moisture density relationships and perform the required compaction testing.

The compaction control tests for this section are based on one individual compaction test per 200 feet of trench per 36 inches of backfill or where directed by ENGINEER. Compaction tests shall be taken for service lines a minimum of one test per line, at a depth as directed by ENGINEER. The CONTRACTOR shall be responsible for all retesting of failing tests and a proctor determination to represent each soil condition to be encountered on the project. The time, locations, depths, and frequency of compaction testing shall be at the discretion of the ENGINEER during construction. Should it become necessary to require an additional number of initial compaction tests, over and above the number specified for bidding purposes, the ENGINEER will assume the responsibility to perform said additional testing. The CONTRACTOR, however, will be required to assume the cost of all retesting of failing tests regardless of the total number required during construction.

Compaction testing to determine densities may be accomplished with a nuclear density testing apparatus and/or the sand cone method. Should disputes arise concerning test results, they will be resolved by using the sand cone method.

Written reports of all test results shall be supplied to the ENGINEER and the CONTRACTOR by the testing laboratory as soon as possible. The availability of the independent testing laboratory when needed and speed of testing and reporting are to be considered the responsibility of the CONTRACTOR.

Compaction control tests as stated above shall be incidental to other bid items.

All excess excavated material and material unsuitable for backfill shall become the CONTRACTORs property. The CONTRACTOR shall be responsible for disposal of and transporting material from the site.

The CONTRACTOR shall restore all shrubbery, fences, sod, or other surfaces disturbed to a condition equal to that before the work began, furnishing all labor and material

## SECTION 801 – SANITARY SEWER

incidental thereto. If the area cannot be restored to the original line and cross section without the aid of grade stakes, they will be furnished by the ENGINEER at the CONTRACTOR expense.

Following acceptance by the ENGINEER, the CONTRACTOR shall maintain the surface, including settlement, of; pavement, unpaved trenches, adjacent curbs and gutters, sidewalks, driveways, shrubbery, fences, grass, sod, or other surfaces disturbed throughout the warranty period. All material and labor required for maintenance of the trenches and adjacent structures shall be supplied by the CONTRACTOR and the work done in a manner satisfactory to the ENGINEER. The cost of backfilling and cleanup shall be included in the price per linear foot of pipe in place.

**801-3.6 BACKFILL CLASSIFICATIONS.** Backfill shall meet the requirements of the backfill classification as per plans, if no backfill class is specified, backfill shall be Class A.

Any costs associated with obtaining backfill requirements shall be incidental.

After the pipe has been inspected and bedding material plus the initial two feet of backfill is in place, as per Section 801-3.5, the remaining trench shall be backfilled in layers of not more than twelve inches and compacted by any approved method or equipment which will produce a uniform density meeting the requirements to obtain the following at optimum moisture in accordance with ASTM D1557 (modified proctor):

(a) **Class AA Backfill.** Not less than 95 percent maximum dry density.

(b) **Class A Backfill.** Not less than 90 percent maximum dry density.

(c) **Class B Backfill.** Not less than 85 percent of maximum dry density.

(d) **Class C Backfill.** Equal to the adjacent undisturbed soil but not to exceed 85 percent of maximum dry density.

(e) **Class D Backfill.** No minimum.

When Class D backfill is specified, material shall be backfilled in 24 to 36 inch layers compacted by any approved method or equipment which will obtain a uniform density.

**801-3.7 CONNECT TO MANHOLE.** Connections to existing structures and new manholes, which are not pre-formed, for sanitary sewer shall be core drilled unless otherwise approved by the ENGINEER. Connections shall be made with flexible pipe to manhole connector (rubber boot) or with PVC manhole adaptor per Section 1205. If connector is used, two bands shall be required to secure boot to pipe.

**801-3.8 PROTECTING UNDERGROUND AND SURFACE STRUCTURES.**

Temporary support, adequate protection, and maintenance of all underground and

## SECTION 801 – SANITARY SEWER

surface structures, culverts, storm sewer, sanitary sewer, watermain, service connections for both sewer and water, and other obstructions encountered in the progress of the work shall be furnished by the CONTRACTOR all at its own expense as approved by the ENGINEER.

**(a) Deviations Occasioned by Other Utility Structures.** Wherever existing utility structures or branch connections leading to main sewer or water mains or other conduits, ducts, pipes, or structures form obstructions to the grade and alignment of the sewer to be laid, they shall be permanently supported, removed, relocated, or reconstructed by the CONTRACTOR through cooperation with the Owner of the utility, structure, or obstruction involved. In those instances where their relocation or reconstruction is impracticable, a deviation from the line and grade will be ordered by the ENGINEER, and the change shall be made in the manner directed by the ENGINEER.

Wherever possible, all existing utility structures, or branch connections leading therefrom, will be located in advance of the excavation of the trench and properly marked. The CONTRACTOR shall not cut any existing utility lines unless it is determined by the ENGINEER that it is necessary in order to install the new sewer pipes. All utility lines that are cut by the CONTRACTOR with the approval of the ENGINEER shall be repaired or replaced by the CONTRACTOR as Extra Work. All utility lines that are damaged by the CONTRACTOR shall be repaired or replaced by the CONTRACTOR at the CONTRACTOR's expense.

Wherever the ENGINEER shall determine it is necessary to remove or relocate any existing utility in order to properly install the new sewer pipe, the change shall be made in a manner directed by the ENGINEER and for which extra compensation will be allowed the CONTRACTOR.

**(b) Deviation Without Engineer's Consent.** No deviation shall be made from the required line and grade established by the ENGINEER without the consent of the ENGINEER.

**(c) Subsurface Explorations.** Whenever necessary to determine the location of existing pipes, valves, or other underground structures, the CONTRACTOR, after examination of available records and upon written order from the ENGINEER, shall make all exploration and excavations for such purpose for which the ENGINEER may allow extra compensation.

**801-3.9 CIRCULAR DEFLECTION TEST.** All flexible pipe of 8 inches in diameter or larger shall be tested by the CONTRACTOR to ensure that circular deflections do not exceed the maximum allowable deflection. Maximum allowable deflections shall be governed by the mandrel requirements stated herein and shall nominally be 5 percent.

The maximum average inside diameter shall be equal to the average outside diameter per applicable ASTM Standards minus 2 minimum wall thicknesses per applicable

## SECTION 801 – SANITARY SEWER

ASTM Standards. Manufacturing and other tolerances shall not be considered for determining maximum allowable deflections.

Deflection tests shall be performed a minimum of 30 days after the pipe has been fully backfilled and received passing compaction tests per Section 801-3.5 “Backfilling of Pipe Trench.”

The mandrel shall be pulled through the pipe by hand to ensure that maximum allowable deflections have not been exceeded. Prior to use, the mandrel shall be certified by the ENGINEER. If the mandrel fails to pass through the pipe, it will be deemed to be over-deflected.

The rigid ball or mandrel used for the deflection test shall have a diameter not less than 95 percent of the base inside diameter or average inside diameter of the pipe depending on which is specified in the ASTM Specification, including the appendix, to which the pipe is manufactured. The test shall be performed without mechanical pulling devices. The mandrel shall be fabricated of steel or aluminum and shall have pull rings at either end. The mandrel shall be stamped or engraved indicating the pipe material specification, nominal size, and mandrel outside diameter. The maximum average inside diameter of the pipe shall be measured and calculated by the ENGINEER in the field prior to installation.

Unless otherwise permitted by the ENGINEER, any over-deflected pipe shall be uncovered and, if not damaged, removed and reinstalled. Damaged pipe shall be removed from the work site and replaced with new pipe. Any pipe requiring replacement shall be retested at the expense of the CONTRACTOR.

All costs incurred by the CONTRACTOR attributable to mandrel and deflection testing, including any delays and reinstallation of deflected pipe, shall be considered incidental to the installation of the pipe.

**801-3.10 LEAKAGE TESTS.** The CONTRACTOR shall provide one of either a Hydrostatic Test or an Air Test as specified below:

Trench shall be completely backfilled to final grade prior to testing, unless otherwise approved by the ENGINEER.

**(a) Hydrostatic Test.** The CONTRACTOR shall perform an exfiltration or infiltration test with a minimum positive head of 2 feet.

Allowable exfiltration or infiltration shall not exceed 100 gallons per inch of internal pipe diameter, per mile, per day.

**(b) Air Test.** The CONTRACTOR shall conduct an air test, as a minimum, conforming to the test procedure as described in ASTM F1417 for plastic pipe. For other materials, test procedures shall be approved by the ENGINEER.

## SECTION 801 – SANITARY SEWER

**801-3.11 TELEWISE SEWER MAIN.** All newly constructed sewer mains shall be televised. If not specified as a bid item, the televising shall be considered incidental to the price bid for the sewer installation. After flushing the sewer main, as per Section 801-3.4, the CONTRACTOR shall have the sewer main televised and recorded by a firm normally engaged in such type of work. The CONTRACTOR shall provide a high-quality digital video or downloadable shared file with a report for each section of sewer main televised. The recording shall be clearly marked as to the project number and recording number. The recording shall describe locations and conditions of the sewer and shall have a visual footage counter showing the distance of the camera from the manhole. After the CONTRACTOR has submitted the recordings and report, they will be viewed by the ENGINEER for acceptance. Any sewer failing inspection shall be replaced and re-televised at the expense of the CONTRACTOR.

Trench shall be completely backfilled to final grade prior to televising, unless otherwise approved by the ENGINEER.

**801-3.12 CLEANOUT.** Cleanouts shall be constructed in accordance with the standard detail 801-1.

**801-3.13 SANITARY SEWER FORCE MAIN.** The construction requirements for sanitary sewer force mains shall comply with Section 901 “Water Mains,” with the exception of the hydrostatic pressure tests, disinfection, and bacteriological testing. The hydrostatic pressure test shall be the same as Section 901 “Water Mains,” except the hydrostatic pressure test shall be 125 pounds per square inch and shall be held for 2 hours. No pipe disinfection or bacteriological testing shall be required.

**801-3.14 CONNECTION TO EXISTING SEWER MAIN.** Whenever a wye branch is not available for a sewer service connection, the connection to the sewer main shall consist of one of the following:

- a. A “factory assembled” wye branch may be cut into an existing PVC sewer main using gasketed repair couplings to the existing PVC sewer main.
- b. A “factory assembled” wye branch may be cut into an existing VC sewer main using Shear Guard couplings, or approved equivalent, to the existing VC sewer main.
- c. PVC, VC, or RCP sewer main may be connected to the existing VC sewer main service using an Inserta Tee as manufactured by Inserta Fittings Co., or approved equivalent. The City of Bismarck Public Works Department will make the tap into the existing PVC, VC, or RCP sewer main. Call to schedule and for the current price of tap.

**801-3.15 WYE BRANCH LOCATIONS.** Wye branches shall be marked with a 2 inch by 2-inch by 4-foot stake placed perpendicular to the main line sewer at the end of the wye.

## SECTION 801 – SANITARY SEWER

**801-3.16 INSULATE SEWER.** The CONTRACTOR shall furnish and install the insulation required to insulate the sewer as shown on the plans. The insulation shall be at least 4 inches thick by 8 feet wide centered on the sewer main. The material between the top of the sewer bedding and the insulation shall consist of a concrete sand.

### **801-4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107 and as follows:

**801-4.1 SANITARY SEWER PIPE.** Sanitary sewer pipe shall be measured from the centerline of manhole to centerline of manhole.

**801-4.2 ROCK EXCAVATION.** All rock found in the trench area greater than 1 cubic foot shall be classified as Rock Excavation.

The CONTRACTOR shall place all rocks greater than 1 cubic foot and less than 1 cubic yard in a pile to be measured by the ENGINEER. The total volume of the stockpile shall be reduced by 25 percent to account for void in the rock stockpile.

All rocks greater than 1 cubic yard shall be individually measured by the ENGINEER.

**801-4.3 TELEWISE SEWER MAIN.** Telewise Sewer Main shall be measured from centerline of the manhole to centerline of the manhole or an end point of televising.

## **SECTION 802 – STORM SEWER**

### **802-1 DESCRIPTION**

This item shall consist of pipe and related items of the types, classes, sizes, and dimensions required on the plans, furnished and installed at the places designated on the plans and profiles, or by the ENGINEER, in accordance with these specifications and with the lines and grades given.

The bid price per linear foot of pipe in place shall include the cost of excavation and backfill, the cost of furnishing and installing all trench bracing, all fittings required to complete the pipe drain, as shown on the plans, and the material for and the making of all joints, including all connections to existing drainage pipe and manholes.

"Unstable," "Unsuitable," "Suitable," and "Unsatisfactory" soil or aggregate items shall be defined as stated in Section 202.

### **802-2 MATERIALS**

**802-2.1 GENERAL.** The pipe shall be of the type called for on the plans or in the proposal and shall be in accordance with the following appropriate requirements.

**802-2.2 REINFORCED CONCRETE STORM SEWER PIPE.** Reinforced concrete storm sewer pipe shall conform to the requirements of ASTM C76.

Unless otherwise specified, all pipe shall be Class III for 24-inch and smaller and Class II for 27-inch and larger in accordance with ASTM C76, Wall B.

All pipe sections shall be cast in sections 8 feet, 6 feet, or 4 feet long, with the exception of the variable length sections may be cast to match at manholes and inlets.

**802-2.3 POLYVINYL CHLORIDE STORM SEWER PIPE.** Polyvinyl chloride storm sewer (PVC) pipe 15 inches or smaller shall conform to the requirements of ASTM D3034 for type PSM, PVC sewer pipe and shall have an SDR of 35, all of which shall be stamped on the pipe. Polyvinyl chloride sewer pipe 18 inches or larger shall conform to the requirements of ASTM F679-PS46. PVC sewer shall have the elastomeric gasket type joint providing a watertight seal.

**802-2.4 CORRUGATED STEEL STORM SEWER PIPE.** Corrugated steel storm sewer pipe shall have a zinc coating weight of 2 ounces per square foot and shall conform to the requirements of AASHTO M36. This material may be used if approved by the ENGINEER.

**802-2.5 HIGH DENSITY POLYETHYLENE STORM SEWER PIPE** High Density polyethylene storm sewer pipe shall be of the quality to that manufactured by

## SECTION 802 – STORM SEWER

ADS/Hancor, or approved equivalent. The pipe shall have a smooth interior and annular exterior corrugations. The 4-inch to 60-inch pipe with integral bell and spigot joints shall conform to ASTM F2306. The joint shall be water tight and gaskets shall conform to ASTM F477. Fittings shall conform to ASTM F2306. Bell and spigot connections shall utilize a spun-on or welded bell. Valley or saddle gaskets shall meet the soil-tight performance requirements of ASTM F477.

**802-2.6 RIBBED POLYVINYL CHLORIDE STORM SEWER PIPE.** Ribbed polyvinyl chloride storm sewer pipe shall be of a quality equal to that manufactured by Extrusion Technologies, Inc. Ultra-Rib, or approved equivalent. The pipe shall meet the requirements of ASTM F794 and shall have a smooth interior. The pipe shall have a bell end and a spigot end which shall be connected using elastomeric gaskets. The pipe stiffness shall be a minimum of 46 psi when tested at 5 percent deflection in accordance with ASTM D2412.

**802-2.7 CORRUGATED POLYVINYL CHLORIDE STORM SEWER PIPE.** Corrugated polyvinyl chloride storm sewer pipe shall be manufactured by Extrusion Technologies, Inc. Ultra-Corr, or approved equivalent. The pipe shall meet the requirements of ASTM F949 and shall have a smooth interior. The pipe shall have a bell end and a spigot end which shall be connected using elastomeric gaskets. The pipe stiffness shall be a minimum of 50 psi when tested at 5 percent deflection in accordance with ASTM D2412.

**802-2.8 PERFORATED PIPE.** Perforated concrete pipe in sizes 4 inches and above shall conform to the requirements of ASTM C444, Type 1 or 2. Corrugated HDPE perforated pipe in sizes 3 inches to 6 inches shall conform to ASTM F2648 or AASHTO M252. Corrugated HDPE perforated pipe in sizes 8 inches to 24 inches shall conform to ASTM F667 OR ASHTO M252/294. If PVC perforated pipe is selected, it must meet the requirement of Section 802-2.6, or an approved equivalent.

**802-2.9 ARCH PIPE.** Arch pipe shall conform to the same requirements as listed for standard pipe of like material.

**802-2.10 FLARED END SECTIONS.** Flared end sections shall be RCP material for the flared end section and 2 adjacent pipe sections. The 2 sections and the flared end section shall be tied together using joint ties, or an approved equivalent.

**802-2.11 CONCRETE MANHOLES AND INLETS.** Concrete manholes and inlets shall conform to Section 1205.

**802-2.12 MORTAR.** Mortar for pipe joints and connections to other drainage structures shall be composed of 1 part, by weight, of portland cement and 2 parts of mortar sand. The portland cement shall conform to the requirements of Section 501. The sand shall conform to the requirements of Section 501. Hydrated lime may be added to the mixture of sand and cement in an amount equal to 15 percent of the weight of cement used. The hydrated lime shall meet the requirements of ASTM C6.

## SECTION 802 – STORM SEWER

**802-2.13 CONCRETE.** Concrete for pipe cradles shall conform to the requirements of Section 501.

**802-2.14 CONCRETE PIPE JOINTS.** Concrete pipe joints for non-pressure pipe shall be sealed with a butyl joint mastic. Butyl joint mastic shall be equal to EZ-STIK as manufactured by the Press-Seal Gasket Corporation, or approved equivalent. The CONTRACTOR shall use 1/2-inch butyl for 12-inch to 18-inch RCP, 3/4-inch for 21-inch to 36-inch RCP, 1-inch for 42-inch to 66-inch RCP, and 1½-inch for 72-inch to 120-inch RCP. Rubber-type gaskets for concrete low-head pressure pipe shall conform to the requirements of ASTM C443 and ASTM 361, if specified.

**802-2.15 GASKET JOINT FOR PVC STORM SEWER PIPE.** Gaskets for PVC storm sewer pipe joints shall be of the elastomeric type providing a watertight seal.

**802-2.16 BEDDING MATERIAL.** The bedding material shall be defined as stated in Section 801.

**802-2.17 SUBCUT GRAVEL.** The subcut gravel shall be as defined in Section 801.

**802-2.18 MARKING TAPE.** The CONTRACTOR will be required to furnish and install marking tape located 2 feet above the top of all storm sewer mains installed under the contract. In cases where there is less than 30 inches of fill material over the top of the pipe, the tape shall be placed 12 inches from the top of the pipe. The tape shall be of the non-detectable type and shall have a minimum width of 5 inches. The tape shall be green in color with the words "CAUTION SEWER LINE BELOW" imprinted on the tape in black capital letters. The marking tape shall be manufactured by Presco standard grade or approved equivalent

Cost of marking tape and installation shall be considered incidental to other items.

**802-2.19 RIPRAP.** Rock shall be hard, durable, angular in shape, and free from cracks, overburden, shale, and organic material. The width and the thickness of a single stone shall each be less than one-third the length of the stone. Rock shall not sustain a loss of more than 40 percent after 500 revolutions in an abrasion test conducted in accordance with ASTM C535-69. Rock shall not sustain a loss of more than 10 percent after 12 cycles of freezing and thawing (AASHTO T103 for ledge rock, procedure A). Rock shall have a minimum specific gravity of 2.50.

CONTRACTOR shall be responsible for all costs of testing rock for compliance with these specifications. In lieu of testing proposed rock for compliance with these specifications, rock obtained from County or North Dakota Department of Transportation approved quarries may be used. All rock materials considered for use as riprap shall have prior approval by the ENGINEER before being placed.

## SECTION 802 – STORM SEWER

Gradation for riprap are as follows:

Riprap	% Smaller than Given Size by Weight	Intermediate Rock Dimension (Inches)	d <sub>50</sub> * (Inches)
Type VL	70-100	12	–
	50-70	9	–
	35-50	6	6**
	2-10	2	–
Type L	70-100	15	–
	50-70	12	–
	35-50	9	9**
	2-10	3	–
Type M	70-100	21	–
	50-70	18	–
	35-50	12	12
	2-10	4	–
Type H	100	30	–
	50-70	24	–
	35-50	18	18
	2-10	6	–
Type VH	100	42	–
	50-70	33	–
	35-50	24	24
	2-10	9	–

\*d<sub>50</sub> = Mean particle size

\*\*Bury types VL and L with native topsoil and revegetate to protect from vandalism.

**802-2.20 CULVERTS.** Culverts installed within CITY right-of-way shall be reinforced concrete pipe (RCP) or corrugated steel storm sewer pipe.

**802-2.21 STORM SEWER FORCE MAIN MATERIALS.** All materials for construction of storm sewer force mains shall conform to Section 901 “Water Mains.”

### 802-3 CONSTRUCTION REQUIREMENTS

**802-3.1 EQUIPMENT.** All equipment necessary and required for the proper construction of storm sewers shall be on the project in proper working condition and approved by the ENGINEER before construction is permitted to start.

The CONTRACTOR shall provide appropriate hoisting equipment to handle the pipe while unloading and placing it in its final position without damage to the pipe.

## SECTION 802 – STORM SEWER

The CONTRACTOR shall provide method and means to obtain the required compaction of the pipe bed and the backfill as specified.

The CONTRACTOR shall provide a sufficient number of watertight sewer plugs to prevent infiltration of water and any other foreign material from entering the existing sewer system and the newly constructed sewer lines.

**802-3.2 EXCAVATION AND PREPARATION OF TRENCH.** Excavation and preparation of the trench for storm sewer construction shall conform to Section 801 with the following additions:

HDPE sewer pipe shall have bedding material installed to 6 inches over the top of the pipe. Bedding material from the center of the pipe to 6 inches over the pipe shall be considered incidental to the pipe items.

If perforated storm drain is installed, the fine aggregate shall conform to Section 802-3.7.

**802-3.3 ROCK EXCAVATION.** The rock excavation shall conform to Section 801.

**802-3.4 PIPE LAYING.** Pipe laying shall conform to Section 801 with the following additions:

Connections between HDPE and RCP shall be made using an internal coupler spigot adaptor equivalent to the Mar-Mac Coupler manufactured by Advanced Drainage Systems per Detail No. 802-2. This work shall be incidental to the storm sewer pipe.

**802-3.5 SIX-INCH CLEANOUT - IN-LINE.** Where shown on the plans, storm sewer in-line cleanouts shall be constructed according to the corresponding Detail (802-3) in the City of Bismarck Construction Specifications and conform to the following criteria. The pipe shall be polyvinyl chloride sanitary sewer (PVC) pipe. Pipe that is 15 inches or smaller shall conform to the requirements of ASTM D3034 for TYPE PSM, PVC sewer pipe and fittings and shall have an SDR of 35, all of which shall be stamped on the pipe. Polyvinyl chloride sewer pipe 18 inches or larger shall conform to the requirements of ASTM F679-PS46. PVC sewer main line pipe and PVC sewer service pipe shall have the elastomeric gasket-type joint providing a watertight seal. A solvent cement-type joint will not be allowed. Connection to pipe shall be made with PVC 2-Way cleanout tee as manufactured by Charlotte Pipe or approved equal. The top of the pipe shall have a PVC threaded clean out adapter with a PVC threaded plug placed under a Neenah No. R-1976 or East Jordan Iron Works No. 1578 or approved equivalent cover set in concrete as per the aforementioned detail.

**802-3.6 SIX-INCH CLEANOUT - END OF RUN.** Where shown on the plans, storm sewer end-of-line cleanouts shall be constructed according to the corresponding detail (802-4) in the City of Bismarck Construction Specifications and conform to the following criteria. The pipe shall be polyvinyl chloride sanitary sewer (PVC) pipe. Pipe that is 15

## SECTION 802 – STORM SEWER

inches or smaller shall conform to the requirements of ASTM D3034 for type PSM, PVC sewer pipe and fittings and shall have an SDR of 35, all of which shall be stamped on the pipe. Polyvinyl chloride sewer pipe 18 inches or larger shall conform to the requirements of ASTM F679-PS46. PVC sewer main line pipe and PVC sewer service pipe shall have the elastomeric gasket-type joint providing a watertight seal. A solvent cement-type joint will not be allowed. The PVC 90 degree bend shall be a sweeping bend; right angle bends will not be accepted. The top of the pipe shall have a PVC threaded clean out adapter with a PVC threaded plug placed under a Neenah No. R-1976 or East Jordan Iron Works No. 1578 or approved equivalent cover set in concrete as per the aforementioned detail.

**802-3.7 DRAINAGE AGGREGATE.** The drainage aggregate shall meet either of the gradations in the following table.

<b>NDDOT Class 43</b>	
<b>Sieve Size</b>	<b>Percent Passing</b>
3/8"	100
No. 4	20-70
No. 8	0-17
No. 200	0-2
Shale	8.0%

<b>NDDOT Class 2</b>	
<b>Sieve Size</b>	<b>Percent Passing</b>
3/4"	100
3/8"	50-95
No. 10	0-15
No. 30	0-4

**802-3.8 BACKFILLING OF PIPE TRENCH.** Backfilling shall conform to Section 801-3.5 with the following additions:

When backfilling perforated pipe, the CONTRACTOR shall backfill with fine aggregate conforming to Section 501 to a point 2 feet below the finished surface. The remaining 2 feet shall be backfilled with existing spoil. The excess spoil shall be disposed of by the CONTRACTOR, incidental to other bid items. Care shall be taken when backfilling around the pipe to prevent damage to the trench section surrounded by the geotextile fabric.

When backfilling flexible pipe, the CONTRACTOR shall place and compact bedding material to a point 6 inches above the top of the pipe. Care shall be used not to over-deflect the roundness of the pipe. For flexible pipe, the pipe bedding shall be considered incidental from the center of the pipe to 6 inches over the top of the outside of the pipe.

## SECTION 802 – STORM SEWER

The remaining trench shall be backfilled in accordance with the specifications for the class of backfill as set forth in Section 801. The areas for each class of backfill specified shall be designated on the plans.

**802-3.9 BACKFILL CLASSIFICATIONS.** The backfill classifications shall be as defined in Section 801.

**802-3.10 PROTECTING UNDERGROUND AND SURFACE STRUCTURES.**

Temporary support, adequate protection and maintenance of all underground and surface structures, drains, sewers, water mains, service connections for both sewer and water, and other obstructions encountered in the progress of the work shall be furnished by the CONTRACTOR all at its own expense as approved by the ENGINEER.

**(a) Deviations Occasioned by Other Utility Structures.** Wherever existing utility structures or branch connections leading to main sewer or water mains or other conduits, ducts, pipes, or structures form obstructions to the grade and alignment of the sewer to be laid, they shall be permanently supported, removed, relocated, or reconstructed by the CONTRACTOR through cooperation with the Owner of the utility, structure, or obstruction involved. In instances where their relocation or reconstruction is impracticable, a deviation from the line and grade will be ordered by the ENGINEER, and the change shall be made in the manner directed by the ENGINEER.

Wherever possible, all existing utility structures or branch connections leading therefrom will be located in advance of the excavation of the trench and properly marked. The CONTRACTOR shall not cut any existing utility lines unless it is determined by the ENGINEER that it is necessary to install the new sewer pipes. All utility lines that are cut by the CONTRACTOR with the approval of the ENGINEER shall be repaired or replaced by the CONTRACTOR as Extra Work.

All utility lines that are damaged by the CONTRACTOR shall be repaired or replaced by the CONTRACTOR at the CONTRACTOR's expense.

Wherever the ENGINEER shall determine it is necessary to remove or relocate any existing utility to properly install the new sewer pipe, the change shall be made in a manner directed by the ENGINEER and for which extra compensation will be allowed the CONTRACTOR.

**(b) Deviation Without Engineer's Consent.** No deviation shall be made from the required line and grade established by the ENGINEER without the consent of the ENGINEER.

**(c) Subsurface Explorations.** Whenever necessary to determine the location of existing pipes, valves, or other underground structures, the CONTRACTOR, after examination of available records and upon written order from the ENGINEER, shall make all explorations and excavations for such purpose for which the ENGINEER may allow extra compensation.

## SECTION 802 – STORM SEWER

**802-3.11 CIRCULAR DEFLECTION TEST.** All fittings and flexible pipe of 8 inches in diameter or larger shall be tested by the CONTRACTOR to ensure that circular deflections do not exceed the maximum allowable deflection. The CONTRACTOR shall test in accordance with Section 801 "Circular Deflection Test." Any pipe requiring replacement shall be retested at the expense of the CONTRACTOR.

Deflection tests shall be performed a minimum of 30 days after the pipe has been fully backfilled or after gravel section is in place and compacted when pipe is under roadway, and received passing compaction tests per Section 801 Backfilling of Pipe Trench.

**802-3.12 RIPRAP.** Hand placement of riprap may be required to ensure an acceptable gradation, uniform surface, and to fill gaps between larger rocks to cover any exposed riprap fabric.

Type VL riprap and Type L riprap shall be buried with topsoil and revegetated. All items shall be considered incidental to the bid price for riprap, unless otherwise specified. Riprap fabric shall be used under the riprap as bedding. All costs for providing and installing the riprap fabric shall be incidental to the riprap.

Riprap grout shall be installed for the first 3 feet from the end of the flared end section (FES) the width of the flared end section plus 1 foot on each side of the FES.

Grout shall be installed on a 4-inch thick layer of granular material. The granular material shall be in accordance with Section 801 "Bedding Material." The riprap prior to the grout placement must be as clean as practical. The grout shall be delivered to the place of final deposit by means that will ensure uniformity and prevent segregation of the grout. Placing of grout shall be obtained by pumping under pressure through a 2-inch maximum diameter hose to ensure complete penetration of the grout into the rock layer. A vibrator is to be employed near the nozzle during placement to aid the flow of the grout. The excess grout must be removed immediately by washing to leave a clean rock face exposed.

Grout shall fill the voids to within approximately 4 inches of the riprap surface. The recommended minimum grout specifications include entrained air, a 28-day strength of at least 2,400 pounds per square inch, and a high slump (5-7 inches) in order to penetrate either the full depth of the riprap layer or at least 2 feet where the riprap layers thicker than 2 feet. Concrete having maximum aggregate size of 3/4 inch may be substituted for grout when using Type M riprap or larger.

**802-3.13 FLUSH AND TELEVISION SEWER MAIN.** All storm sewer, including laterals and culverts, regardless of pipe material, shall be flushed and televised as per section 801.

### **MEASUREMENT AND PAYMENT.**

Measurement and payment shall be as specified in Section 107 and as follows:

## SECTION 802 – STORM SEWER

**802-4.1 STORM SEWER PIPE.** Storm Sewer Pipe shall be measured from centerline of manhole or inlet to centerline of manhole or inlet. If no inlet or manhole is installed, pipe shall be measured to end of pipe section. Flared end sections shall be paid under separate bid item.

**802-4.2 ARCH STORM SEWER PIPE.** Arch STS Pipe shall be measured from centerline of manhole or inlet to centerline of manhole or inlet.

**802-4.3 CORRUGATED STEEL STORM SEWER PIPE.** Corrugated Steel STS Pipe shall be measured from centerline of manhole or inlet to centerline of manhole or inlet.

**802-4.4 PERFORATED PIPE.** Bends, tees, caps and coupling bands shall be considered incidental.

**802-4.5 BEDDING MATERIAL.** Bedding Material shall be measured and paid for as per Section 801, with the following revision:

When no pipe material is specified, any additional bedding material required due to installing pipe material other than RCP shall be considered incidental to the pipe and no additional compensation shall be made. If pipe material other than RCP is specified, material shall be measured and paid as per Section 801.

**802-4.6 ROCK EXCAVATION.** Rock Excavation shall be measured and paid as per Section 801.

**802-4.7 RIPRAP GROUT.** Granular bedding material and installation shall be considered incidental.

## SECTION 810 – CURED IN PLACE PIPE (CIPP)

### 810-1 DESCRIPTION

This item covers the requirements for the reconstruction of the identified pipeline(s) or conduit(s) by the installation of a resin-impregnated flexible tube that is either inverted or pulled into the original pipeline/conduit and expanded to fit tightly against said pipeline by the use of a water column or air pressure. This method includes cleaning and video inspection of the designated line, bypass pumping, traffic control, identification of existing live taps, removing of protruding taps by remote methods, performing point repairs, installation of a resin-impregnated tube into existing pipe, ultraviolet light or hot (water, steam, or air) curing as specified by the resin manufacturer, reopening service taps into the line, sampling and testing, and cleanup. Before final acceptance of each line segment, a post-rehabilitation video inspection and sample testing must be conducted and approved. Rehabilitation must be completed for the full length from manhole to manhole, resulting in a sound, tight-fitting, watertight liner with a smooth interior surface.

### 810-2 MATERIALS

**810-2.1 TUBE.** The tube shall be fabricated to a size that, when installed, will tightly fit the internal circumference and the length of the original pipeline or conduit. Allowances shall be made in its manufacture for the longitudinal and circumferential stretching that occurs during the placement of the tube.

The tube shall be uniform in thickness and, when subjected to the installation pressures, shall meet or exceed the designed finish wall thickness throughout its length.

Any plastic film applied to the tube on what will become the interior wall of the finished CIPP shall be compatible with the resin system used, translucent enough that the resin saturation is clearly visible, and shall be firmly bonded to the felt material. Tubes with removable calibration tubes such as those used in UV light-cured CIPP do not have to meet this bonding requirement.

The tube shall be marked for distance at regular intervals, not to exceed 5 feet, along its entire length. Such markings shall also include the CIPP System Manufacturer's name or identifying symbol (brand).

**(a) TUBE - ULTRAVIOLET LIGHT CURED.** The glass fiber tubing shall be seamless and spirally wound, including an exterior and interior film that protects and contains the resin used in the liner. The exterior film shall be provided with a UV light blocker foil. The tube shell fiber shall be flexible and have allowable strain values (expandable) of equal to 8 to 10 percent. The tube shall not have a longitudinal seam, including a stitched seam, stitch-free-weld or bond, or stitch-free overlap. The tube shall be

## SECTION 810 - CURED IN PLACE PIPE (CIPP)

constructed to withstand installation pressures and have sufficient strength to bridge missing pipe.

**(b) TUBE - HEAT CURED.** The tube shall consist of one or more layers of a flexible needled felt or nonwoven or woven material (such as fiberglass), or a combination of nonwoven and woven materials, capable of carrying the prescribed quantity of resin, withstanding the required installation pressures and curing process temperatures. The tube's materials of construction shall be compatible with the resin system to be used on this project. The material shall be able to stretch to fit irregular pipe sections, negotiate minor bends, and dimple at any service or branch connections.

**810-2.2 RESIN SYSTEM.** The resin system shall be a corrosion resistant polyester, vinyl ester, or epoxy and catalyst system that when properly cured within the tube composite meets the minimum requirements given herein or those that are to be utilized in the design of the CIPP for this project.

The resin system shall be formulated for the CIPP application. Its viscosity shall be conducive to its being saturated into the void space of the tube's matrix; and its thixotropy shall be adjusted to minimize its migration during the tube installation process.

The pot life of the catalyzed resin system shall be such that it provides a reasonable timeframe for the tube to be installed. The resin system used on this project shall be within the resin manufacturer's recommended shelf life. Resins that are expired shall not be permissible.

**810-2.3 STRUCTURAL REQUIREMENTS.** The design thickness of the liner shall be arrived at using standard engineering methodology in accordance with ASTM F1216. The long-term flexural modulus to be used in the design shall have been verified through long-term testing. The long-term modulus shall not exceed 50% of the short-term value for the resin-tube system unless testing demonstrates a greater value should be used.

The finished CIPP shall fit tightly to the host pipeline at all observable points and shall meet or exceed the minimum thickness established by the design process. The materials properties of the finished CIPP shall conform to the following minimum structural standards:

MINIMUM PHYSICAL PROPERTIES				
Property	ASTM Test Method	Polyester System	Filled Polyester System	Vinyl Ester System
Flexural Strength	D790	4,500psi	4,500psi	5,000psi
Flexural Modulus (Initial)	D790	250,000psi	400,000psi	300,000psi
Flexural Modulus (50 Yr)	D790	150,000psi	200,000psi	150,000psi

## 810-3 CONSTRUCTION REQUIREMENTS

### 810-3.1 PRE-INSTALLATION

**(a) Notifications.** A public notification program shall be implemented and shall, at a minimum, provide the following:

1. Written notice to be delivered to each home or business describing the proposed work schedule, how it affects them, and a local telephone number of the CONTRACTOR they can call to discuss the project or any problems that could arise. The ENGINEER will supply the CONTRACTOR with a list of affected residences and businesses.
2. Personal contact and attempted written notice a minimum of 24 hours for residences and 48 hours for businesses prior to the beginning of work being conducted on the section relative to the properties affected. The CONTRACTOR shall be required to notify the City and all affected properties whose service laterals will be out of service and to advise against water usage until the sewer main is back in service.
3. Personal contact with any home or business that cannot be reconnected within the time stated in the written notice.

**(b) Sewage Flow.** The CONTRACTOR shall make every effort to maintain service usage throughout the duration of the project. In the event that a lateral sewer will be temporarily out of service, the maximum amount of time of no service shall be 8 hours for any property served by the sewer. The CONTRACTOR shall identify any section of pipe where it is anticipated that the pipe will be out of service for more than 8 hours and provide a plan, to the ENGINEER for approval.

**(c) Bypassing Sewage.** The CONTRACTOR, when required, shall provide for the flow of sewage around the section or sections of pipe designated for repair. Plugging the line at an existing upstream manhole and pumping the flow into a downstream manhole or adjacent system shall make the bypass. The pump(s) and bypass line(s) shall be of adequate capacity to accommodate the sewage flow. The ENGINEER shall be provided a detail of the bypass plan prior to beginning bypass operations.

**(d) Pre-Construction Televising.** Experienced personnel trained in locating breaks, obstacles, and service connections by closed circuit television shall perform inspection of the pipeline. The interior of the pipeline shall be carefully inspected to determine the location of any conditions that may prevent proper installation of the CIPP into the pipeline, and it shall be noted so that these conditions may be corrected. A video and suitable log shall be kept for later reference by the ENGINEER. The CONTRACTOR shall verify all existing service taps by flowing water or dye test visually with a CCTV or approved method by the ENGINEER. All inspections will be performed by Pipeline Association and Certification Programs (PACP) trained and certified personnel.

## SECTION 810 - CURED IN PLACE PIPE (CIPP)

**(e) Cleaning and Repairs.** It shall be the responsibility of the CONTRACTOR to clear the line of obstructions and debris such as solids and roots that will prevent the insertion of the CIPP. If pre-installation inspection reveals an obstruction such as a protruding service connection, dropped joint, or a collapse that will prevent the CIPP installation process and cannot be removed by conventional sewer cleaning equipment, the CONTRACTOR shall make a point repair excavation to uncover and remove or repair the obstruction through a negotiated change order with the OWNER or the OWNER will perform the repair through their own or contracted forces. After any point repair has been completed, the CONTRACTOR shall visually inspect all repairs with a CCTV as deemed necessary by the ENGINEER.

**(f) Tube wet out.** The CONTRACTOR shall wet out the tube as recommended by the manufacturer. Wet out reports shall be supplied to the ENGINEER prior to installation for each tube that is wet out.

### 810-3.2 INSTALLATION

**(a) TUBE INSERTION (FOR FIBERGLASS/UV CURED PRODUCTS).** A slip sheet shall be installed on the bottom half of the pipe prior to liner insertion, for the purpose of smoothing out the bottom of the liner to increase flow characteristics.

The preliner tube, or outer film, shall be installed into the pipe prior to inserting the liner, unless it is manufactured on the exterior of the liner.

A constant tension winch should be used to pull the glass fiber liner into position in the pipe. Once inserted, end plugs shall be used to cap each end of the glass fiber liner to prepare for pressurizing the liner. The end plugs shall be secured with straps to prevent them from being expelled due to pressure. Liner restraints should be used in manholes.

The glass fiber liner shall be cured with UV light sources at a constant inner pressure. When inserting the curing equipment in the liner, care must be taken not to damage the inner film material.

The UV light sources shall be assembled according to the manufacturer's specifications for the liner diameter. For the liner to achieve the required water tightness and specified mechanical properties, the following parameters must be controlled during the entire curing process:

1. Curing Speed
2. Light source working and wattage
3. Inner air pressure
4. Exothermic (curing) temperatures
5. Date and time
6. Length of liner

A record of the curing parameters of the liner shall be given to the ENGINEER in order to demonstrate that the entire liner has been cured properly. The recording shall be accomplished using a computer and database that are tamper-proof. During the curing

## SECTION 810 - CURED IN PLACE PIPE (CIPP)

process, infrared sensors shall be used to record curing data. The data shall be submitted to the ENGINEER with a post CCTV inspection on DVD or other electronic means acceptable to the ENGINEER.

Pressure and wattage shall be those defined in the Quality Tracker UV curing protocol issued by the manufacturer.

The inner film material shall be removed and discarded after curing to provide optimal quality of the final product.

Flushing of the cured fiberglass/UV cured CIPP liner (to reduce styrene residual) is not required for fiberglass/UV cured CIPP products that provide third-party test results that document styrene residual levels (without flushing) within acceptable defined levels.

### **(b) TUBE INSERTION/INVERSION (FOR FELT/HOT WATER CURED PRODUCTS).**

The resin impregnated tube shall be transported and stored in a refrigerated environment until it is installed by using an application of water, air, or cable and winch to properly place the tube between the upstream and downstream manholes.

The wet out felt tube shall be inserted, or inverted, through an existing manhole or other approved access. Liner installation head pressures shall be maintained within the minimum and maximum range for hot and cold conditions as specified by the manufacturer, regardless of which method of installation (stand pipe, pressure unit, etc.) is used.

Using the inversion procedure, the tube end shall initially be turned inside out and attached to a platform ring, standpipe, or other means as approved by the ENGINEER. The addition of water shall be adjusted to sufficient height/pressure to cause the impregnated tube to invert from manhole to manhole, and hold the tube tight against the existing pipe wall.

Using the insertion procedure, the tube shall be winched into position according to manufacturer's recommendations. The addition of water shall be adjusted to sufficient height/pressure to cause the calibration hose to invert from manhole to manhole and hold the tube tight against the existing pipe wall.

Liner restraints should be used in manholes.

After the installation of the liner is completed, the CONTRACTOR shall use a system capable of providing the required amount of heat uniformly throughout the section for a complete cure of the resin. Boiler truck operators must be fully certified by a certifying agency approved by the ENGINEER. Only fully certified boiler truck operators shall operate boiler trucks.

The curing temperature and schedule shall be as recommended by the resin/catalyst system manufacturer. The heat source shall be fitted with suitable monitors to gauge the temperature of the incoming and outgoing heat supply. Additionally, for any pipe

## SECTION 810 - CURED IN PLACE PIPE (CIPP)

with nominal diameter of 18-inch or larger, the CONTRACTOR shall utilize a remote temperature sensing method to ensure adequate curing, considering the possibility of heat sinks. Temperatures monitored at the manholes do not guarantee an adequate representation of the temperatures for every foot of liner. Temperatures from each remote sensing device shall be recorded by a strip-chart recorder on a continuous tape or another method approved by the ENGINEER. Graphs of the tape shall reflect readings from start of cure to completion of cure/draining of line. Tapes for each segment shall be submitted to the ENGINEER upon completion of each section. Initial cure may be considered completed when the remote sensing device(s) reflect that the cure temperatures, as specified by the resin/catalyst system manufacturer, have been achieved. Curing temperatures and schedule shall comply with submitted data and shall include an adequate "cool down" as specified by the resin manufacturer.

The CONTRACTOR shall cool the hardened pipe in accordance with the resin manufacturer's specifications, before relieving the water column of pressure. Cool water may be added to the water column while maintaining circulation as water is drained from a small hole at the opposite end of the cured-in-place pipe, so that a constant water column height is maintained until cool down is completed. Care shall be taken in the release of the water column so that a vacuum will not develop that could damage the newly installed pipe. Coupon samples shall be obtained for testing (see 3.6 Quality Assurance Procedures).

As styrene is considered a volatile organic compound and a carcinogen, insure that styrene levels are below EPA standards for airborne, surface, and water contamination. The EPA has set the maximum contaminant level at 0.1 ppm for drinking water and other water sources that impact drinking water. For sanitary sewer flow to a sewage treatment plant, styrene contamination must be kept below 2.1 ppm so as not to interfere with the effectiveness of the plant.

Effluent from the curing process shall be disposed of directly to a Wastewater Treatment Plant (WWTP) in full compliance with the WWTP's Industrial Pretreatment Program requirements. The WWTP must provide written documentation that the effluent content complies with their Industrial Pretreatment Program requirements, a copy of which shall be submitted to the ENGINEER for each rehabilitated pipe, or each day of lining work.

If EPA or wastewater treatment levels are exceeded on the surface of the liner for storm water or sanitary sewer pipes (respectively), the CONTRACTOR shall flush the line until styrene levels in flush water are brought within the appropriate standard. If the CONTRACTOR is unable to bring styrene levels down to appropriate levels, the disposal of contaminated water shall be the CONTRACTOR's responsibility and shall be collected and delivered to WWTP in full compliance with the WWTP's Industrial Pretreatment Program requirements. The WWTP must provide written documentation that the effluent content complies with their Industrial Pretreatment Program requirements. Proof of proper disposal, as specified above, shall be presented to the ENGINEER.

## SECTION 810 - CURED IN PLACE PIPE (CIPP)

**810-3.3 FINISHED PIPE.** The finished CIPP shall be continuous over the entire length of each section lined and be free from defects which will or could affect the structural integrity of the lining, cause flow impairment, or leaks. Defects shall be repaired in accordance with the approved repair or replacement procedures as recommended by the CIPP system manufacturer. The repair or replacement of the defects shall be at the CONTRACTOR's expense.

**810-3.4 SERVICE LINE REINSTATEMENT.** Reconnections of existing services shall be made after the CIPP has been installed, fully cured, and cooled. It is the CONTRACTOR's responsibility to ensure that all active service connections are reconnected.

Service taps or branches reconnected internally shall be fully reopened and trimmed to a neat, clean, circular opening concentric with the service line pipe, free of jagged edges, "sawteeth," resin plugs, or resin shelves.

The exact location and number of service connections or side sewers shall be verified during the initial television inspection. It shall be the CONTRACTOR's responsibility to field locate all existing service connections or side sewers and establish means for access for flow control.

Reinstatements shall provide a sufficient seal to prevent water tracking between the pipe and the host pipe. All coupons cut from the liner for reopening of lateral connections shall be retrieved from the sewer and disposed of accordingly.

No additional payment shall be made for excavations for the purpose of reestablishing connections, and the CONTRACTOR shall be responsible for all costs and liability associated with such excavation and restoration work, in accordance with City of Bismarck specifications.

**810-3.5 SEALING AND BENCHES IN MANHOLE.** The liner through each manhole shall be properly aligned, invert to invert, with no obstructions to the flow. Resin slugs shall be removed as necessary from reinstated service connections. Any miss-cuts shall be repaired at the CONTRACTOR's expense. Repairs shall be performed utilizing an additional thinner liner to prevent water from entering behind the liner to the full satisfaction of the ENGINEER.

The CIPP shall make a tight-fitting seal with the existing pipe(s) in the manhole. The top half of the pipe shall be neatly cut off and not broken or sheared off, at least four inches away from the walls. The channel in the manhole shall be a smooth continuation of the pipe(s) and shall be merged with other lines or channels, if any. Channel cross section shall be U-shaped with a minimum height of half pipe diameter, and three-fourths of the pipe diameter for pipes 15 inches and larger. The side of the channels shall be built up with mortar/concrete to provide benches at a maximum of one inch vertical for every 12 inches horizontal pitch towards the channel.

## SECTION 810 - CURED IN PLACE PIPE (CIPP)

The rubber joint seal shall be an extended hydrophilic rubber compounded from chloroprene (Neoprene) rubber and a hydrophilic resin, which expands upon contact with water. The rubber joint shall be bonded with adhesive on one face to hold it in place during assembly. On contact with water, the rubber shall swell by up to 10 times its original volume if necessary, and mold itself to completely fill any gaps and exert pressure evenly to ensure the seal. High compression or bolt up forces shall not be necessary to affect a complete and watertight seal. The hydrophilic neoprene rubber shall have the following characteristics:

Characteristic	Unit	Value	Test Method
Shore A Hardness	point	50 +/- 5	ASTM D2240
Tensile Strength	psi	1177	ASTM D412
Elongation at Break	%	523	ASTM D412
Specific Gravity		1.2	ASTM D297
Swell Capacity in Water Contact	%	200	GRCSC

CIPP and the existing pipe in the manhole must be sealed as above before proceeding on to the next manhole section, and all manholes shall be individually inspected for liner cut-offs, benches, and sealing works.

### 810-3.6 QUALITY ASSURANCE PROCEDURES

**(a) Sampling.** The CONTRACTOR shall prepare a sample for each installation of CIPP that is undertaken. The samples shall be restrained samples for diameters of CIPP less than 18 inches; and flat plate samples for diameters of CIPP 18 inches and larger. Restrained samples shall be made using forms having a similar I.D. to that of the existing piping. The sample shall be taken preferably from an intermediate manhole or the receiving manhole. The sample shall be cut in half lengthwise and half shall be given to the ENGINEER. The form must be maintained in a reasonably horizontal orientation with a proper heat sink (i.e. sandbags). The length of the form shall be a minimum of two times and preferably three times the sample length required by the lab. The flat plate samples shall be taken directly from the wet out tube, clamped between flat plates, and cured in the downtube. The CONTRACTOR shall test the first 3 samples taken from the project and every 5th sample thereafter or otherwise determined by the ENGINEER. The ENGINEER shall have the discretion to have any sample taken tested. The CONTRACTOR shall supply their sample for testing with the OWNER's sample being available if there are any discrepancies. The samples shall be tested for thickness and initial physical properties by an independent laboratory. A certified copy of these test results shall be delivered to the ENGINEER.

CIPP wall thickness shall be determined in a manner consistent with ASTM D5813. Thickness measurements shall be made in accordance with the practice in ASTM D3567 for ASTM D5813. Deduct from the measured values the thickness of any plastic coating or CIPP layer not included in the structural design of the CIPP. The average thickness shall be calculated using all measured values and shall meet or exceed the

## SECTION 810 - CURED IN PLACE PIPE (CIPP)

minimum design thickness. The minimum wall thickness at any point shall not be less than 87.5% of the approved specified thickness.

The layers of the finished CIPP shall be uniformly bonded so that they act as a whole. It shall not be possible to separate any two layers with a probe or point of a knife blade so that the layers separate cleanly or such that the knife blade moves freely between the layers. If separation of the layers occurs during testing of the field samples, new samples will be cut from the work. Any reoccurrence may be cause for rejection of the work by the ENGINEER.

**(b) Post Construction Televising.** In addition to physically sampling the finished CIPP, the CONTRACTOR shall post televise the completed work. The television inspection shall be used to confirm tightness of the fit of the CIPP to the host pipe and to identify any imperfections or defects in the new CIPP. The flow shall be bypassed during the post-TV work so that a full, unobstructed view of the newly installed liner can be obtained. The camera shall be properly set up so that it is approximately in the center of the pipeline and the lighting is attenuated such that it will produce an accurate image of the finished CIPP. The finished liner shall be continuous over its entire length and be free from visual defects such as foreign inclusions, dry spots, holes, and delamination. All observed conditions shall be logged. A copy of the final CCTV survey, including the coding log, shall be delivered to the ENGINEER. All inspections will be performed by Pipeline Association and Certification Programs (PACP) trained and certified personnel.

**(c) LEAKAGE TEST.** The CONTRACTOR shall conduct an air test, as a minimum, conforming to the test procedure as described in ASTM F1417 for plastic pipe.

### 810-4 MEASUREMENT AND PAYMENT

Measurement and payment shall be as specified in Section 107 and as follows:

**810-4.1 SEWAGE BYPASS PUMPING.** Item shall include all labor, equipment, and materials required to implement a sewage by-pass plan for the entire project, including the cost of all sub-contracted sewage by-pass specialists.

**810-4.2 CLEAN PIPE.** Cleaning Pipe for CIPP shall be measured from centerline of the manhole to centerline of the manhole or an end point.

**810-4.3 INSPECTION OF MAINLINE – PRE-REHABILITATION.** Item shall be measured from centerline of the manhole to centerline of the manhole or an end point. Item shall include pre-cleaning and post cleaning CCTV for ENGINEER review and does not include CCTV inspection just prior to CIPP installation, which shall be incidental. All inspections shall be performed by PACP trained and certified personnel.

**810-4.4 INSPECTION OF MAINLINE - POST REHABILITATION.** Item shall be measured from centerline of the manhole to centerline of the manhole or an end point.

## SECTION 810 - CURED IN PLACE PIPE (CIPP)

**810-4.5 CIPP Lining.** Items shall be measured from centerline of the manhole to centerline of the manhole or an end point.

## DIVISION 900

### WATER DISTRIBUTION

#### SECTION 901 – WATERMAIN

##### 901-1 DESCRIPTION

This item shall consist of watermain pipe and related items of the types, classes, sizes, and dimensions required on the plans, furnished and installed at the places designated on the plans and profiles, or by the ENGINEER in accordance with these specifications and with the lines and grades given.

The bid price per linear foot of pipe in place shall include the cost of excavation and backfill, the cost of furnishing and installing all trench bracing, concrete bases, and concrete thrust blocking, and the material for and the making of all joints, including all connections to existing watermain.

“Unstable,” “Unsuitable,” “Suitable,” and “Unsatisfactory” soil or aggregate items shall be defined as stated in Section 202.

##### 901-2 MATERIALS

**901-2.1 GENERAL.** All materials that may come into contact with water intended for use in a public water system shall meet the American National Standards Institute (ANSI) / National Sanitary Foundation International (NSF) Standard 61. A product will be considered as meeting this standard if so certified by NSF, the Underwriters Laboratories, or other organization accredited by ANSI to test and certify such products. The materials shall be of the type selected by the CONTRACTOR and in accordance with the following appropriate requirements unless otherwise specified.

**901-2.2 POLYVINYL CHLORIDE (PVC) PIPE.** Polyvinyl chloride pipe (PVC) or molecularly oriented PVC (PVCO) shall meet the requirements of AWWA C900 or C905 or C909, or the latest revision thereof, and shall be furnished in ductile iron pipe (DIP) equivalent outside diameters with elastomeric joints. The pressure class of PVC pipe shall be PC235 with a DR of 18. PVCO pipe shall be pressure class PC235 (AWWA C900 DR18 equivalent).

Where shown on the plans, restrained joint pipe and fittings shall be used. Restrained jointing systems require approval of the ENGINEER. Preapproved restraining systems include Certa-Lok, Yelomine, and EBAA Iron, Inc (MEGALUG). The CONTRACTOR shall note that the standard mechanical joint is not a restrained joint.

## SECTION 901 – WATERMAIN

**901-2.3 HIGH DENSITY POLYETHYLENE (HDPE) PIPE.** Pipe shall be manufactured in accordance with PE4710 conforming to the latest ANSI/AWWA C906 and NSF/ANSI 61. For potable water applications, PE4710 compound shall conform to ASTM D3350 minimum cell classification 445574C-CC3. The minimum wall thickness of the high-density polyethylene pipe shall meet the requirements of DR 11 pipe with ductile iron pipe outside diameters. HDPE pipe shall conform to the requirements of ASTM F714 for Polyethylene (PE) Plastic Pipe.

All pipes shall be made of virgin material. No rework except that obtained from the manufacturer of the same formulation shall be used. The pipe shall be homogeneous throughout and be free of faults such as visible cracks, holes, foreign material, and blisters.

**901-2.4 DUCTILE IRON PIPE.** Ductile iron pipe shall be manufactured in accordance with the requirements of AWWA/ANSI C151/A21.51. Push-on joints and mechanical joints shall be manufactured in accordance with AWWA/ANSI C111/A21.11. Pipe thickness shall be designated in accordance with AWWA/ANSI C150/A21.50. All pipe under 16 inches shall use pressure Class 350. All 16-inch to 20-inch pipe shall use pressure class 250 or higher. All 24-inch pipe shall be pressure Class 200 or higher. All 30-inch pipe or larger shall be pressure Class 150 or higher. All pipe shall be supplied with a cement mortar lining in accordance with AWWA/ANSI C104/A21.4. All pipe shall have a bituminous exterior coating in accordance with AWWA/ANSI C110/A21.10.

All pipe material suppliers shall be ISO 9001 or 9002 registered or provide the services of an independent inspection agency. Prior to the start of manufacturing, any manufacturer not meeting the ISO registration requirements shall submit to Owner or Owner's engineer the name of an independent inspection agency for approval. The independent inspection agency shall be responsible for sample monitoring of chemical and mechanical tests, and sample visual inspection of quality assurance tests performed on in-process pipe and fittings, and a sample visual and dimensional inspection report from the independent inspection agency of all witnessed tests shall be supplied to Owner or Owner's engineer within 10 days of completion of pipe manufacturing.

Chemical samples shall be taken from each ladle of iron, and the manufacturers' chemical control limits shall be maintained for at least the following elements: carbon, sulfur, phosphorus, silicon, magnesium, chromium, manganese, tin, aluminum, cerium, copper, and lead. When chemical values fall outside the manufacturers' control limits, additional mechanical property tests shall be performed to assure minimum mechanical properties are met.

Where called out on the plans, restrained joint pipe and fittings shall be used. All restrained jointing systems require approval of the ENGINEER. Preapproved restraining systems include Griffin Pipe Product Co. Snap-Lok, US Pipe TR Flex, Sigma One-Lok or American Cast Iron Pipe Co. Flex-Ring. The CONTRACTOR shall note that the standard mechanical joint is not a restrained joint and offers no practical resistance against joint separations.

## SECTION 901 – WATERMAIN

**901-2.5 DUCTILE IRON FITTINGS.** Ductile Iron fittings shall be manufactured in accordance with AWWA/ANSI C110/A21.10 and shall be furnished with either Standardized Mechanical Joints or Push-On Joints. Ductile Iron fittings shall be manufactured in accordance with AWWA/ANSI C153/A21.53 or AWWA/ANSI C110/A21.10. Ductile iron fittings shall have a working pressure of 350 pounds per square inch. All ductile iron fittings shall contain an interior and exterior bituminous seal conforming to AWWA/ANSI C104/A21.4. All ductile iron fittings shall be considered incidental to the price bid for watermain.

**901-2.6 COUPLINGS.** All pipe couplings 12-inch diameter and smaller shall be epoxy coated ductile iron meeting the requirements of ASTM A 536, grade 65-45-12 and AWWA C219. Couplings shall have a minimum working pressure of 250 psi and have end rings that are segmented and joined with a pinless hinge. Gaskets shall be for water and sewer as per ASTM D2000. Fasteners shall be stainless steel.

Couplings larger than 12-inch diameter shall be Romac Macro HP, Hymax High Pressure or approved equivalent. Couplings larger than 12-inch diameter shall be mechanical joint long body sleeves (min. 15" length) meeting AWWA C153.

**901-2.7 GATE VALVE.** The gate valve furnished shall be manufactured by American Flow Control or American AVK Company or approved equivalent, under the minimum requirements in design, material, and workmanship conforming to the latest AWWA Standard C515. The metals used shall be in accordance with AWWA and ASTM Standards. Unless otherwise designated, all gate valves shall have a non-rising stem, O-ring stem seals, 2-inch operating nuts, and open counterclockwise. If a stem extension is specified, it shall be fastened to the operating nut with a set screw. The operating nut shall be drilled or otherwise indented to accept the set screw and provide a secure connection that will prevent an extension from coming loose during operation. The gate valve shall have a resilient synthetic rubber coating seat attached to the wedge, manufactured and designed in accordance with the latest AWWA Standard C515. Resilient-seated gate valve body and bonnet shall be coated, inside and out, with a fusion bonded epoxy in accordance with AWWA C550. The waterway shall have a full unobstructed flow without recesses in the bottom. All bonnet bolts shall be stainless steel.

All gate valves 14 inch and larger shall have a beveled gear actuator, actuator shall be included in the price bid.

All valves shall be placed on a minimum 6 inch thick concrete pad of sufficient dimensions for valve size.

**901-2.8 VALVE BOXES.** The valve boxes furnished shall be manufactured by Tyler Pipe Model 6860, Sigma Type "G" or Star Pipe Products Cast Iron Heavy Duty Model "G" or approved equivalent, with bases and dimensions of each section to be as follows:

- a. No. 6 round base for 16-inch and smaller gate valves.

## SECTION 901 – WATERMAIN

- b. No. 160 oval base for 24-inch or larger.
- c. No. 6 round base for all butterfly valves.
- d. Covers marked "Water."
- e. Top Section 25½ inches long.
- f. Extension pieces as required.

Valve box debris plugs as manufactured by Infact Corporation or approved equivalent shall be furnished and installed into new valve boxes.

All valve boxes shall be capable of a minimum 6 inch top adjustment in either direction, up or down, to or from, the finished grades shown in the plans.

Valve box debris plugs and valve box extension pieces required to make the above-mentioned adjustment shall be considered incidental to the price bid for "Gate Valve and Box."

**901-2.9 GATE VALVE ADAPTOR.** Gate valve adaptor shall be as manufactured by Adaptor, Inc. or approved equivalent. The adaptor shall be ¼-inch steel with a UV protective coating and a ¾-inch gasket attached to the adaptor. The adaptor shall be considered incidental to the price bid for "Gate Valve and Box".

**901-2.10 HYDRANTS.** Hydrants shall be manufactured in accordance with the requirements of AWWA C502. The hydrants shall be equipped with break-a-way type traffic flanges and two 2½-inch hose connections with National Standard Threads and one 4½ -inch pumper connection with National Standard Threads. All 6-inch and 8-inch hydrants shall be 5¼-inch Waterous Pacer Model WB-67-250 as manufactured by American Flow Control or 5¼-inch American Darling Model B-62-B as manufactured by American Flow Control, or approved equivalent. New fire hydrants shall have a minimum of 24 inches between the 2½-inch hose connection and the nominal ground line groove and have a bury depth of 8½ feet unless otherwise called for per plans. All metal internal moving parts below ground will be brass, Class 304 or 316 stainless steel, or have an epoxy coating as such to prevent corrosion for the life of the fire hydrant. All washers and barrel bolts below ground level shall be stainless steel. The hydrant lower rod shall be Class 304 or 316 stainless steel or have an epoxy coating as such to prevent corrosion for the life of the fire hydrant. The hydrants shall be surrounded by ½ cubic yards of subcut gravel so placed that it will readily take up all water from the drip valves. The hydrants shall be set on a concrete pad 6 inches thick and 18 inches square.

All fire hydrant leads will have a gate valve installed on the lead. The valve shall be restrained to the tee with a city-approved method. For those fire hydrant leads 4 feet or less, a special fitting such as a Foster Adapter will be acceptable. No valve shall be installed closer than 2 feet from the fire hydrant.

Fire hydrants shall be installed with a 48-inch Red FH800 American Series Fire Hydrant Marker manufactured by Flexstake, Inc. of Fort Myers, Florida, or an equivalent

## SECTION 901 – WATERMAIN

approved by the ENGINEER. All costs to furnish and install marker shall be incidental to hydrant.

When a hydrant extension is required, extension shall be as required for the make and model of the hydrant per manufacturer's recommendations.

**901-2.11 RESET HYDRANT.** Hydrants to be reset shall be either furnished by the CITY OF BISMARCK or an existing hydrant salvaged during construction. Hydrants shall be set at the location shown on the plans. Care shall be taken by the CONTRACTOR not to damage existing watermain, connections, or valves while removing existing hydrants. Care shall also be taken not to damage the hydrant to be reset during transportation or storage by the CONTRACTOR.

The depth of earth cover over the connecting pipe shall be no less than 8 feet. The hydrants shall be surrounded by ½ cubic yards of subcut gravel so placed that it will readily take up all water from the drip valves. The hydrants shall be set on a concrete pad 6 inches thick and 18 inches square.

Reset fire hydrants shall be installed with a 48-inch Red FH800 American Series Fire Hydrant Marker manufactured by Flexstake, Inc. of Fort Myers, Florida, or an equivalent approved by the ENGINEER. All costs to furnish and install marker shall be included with the cost to reset the hydrant.

**901-2.12 TAPPING SLEEVE WITH TAPPING VALVE.** For pipe sizes of 6 inches to 24 inches, the tapping sleeve shall be stainless steel with a stainless steel flange and bolts and shall conform to the "Smith Blair" Type 663, "Romac" Type SST, "PowerSeal" 3480AS, or approved equivalent. For pipe sizes of 24 inches or larger, the tapping sleeve shall be epoxy-lined and coated with stainless steel bolts and shall conform to the "Smith Blair" Type 622 Split Sleeve with O-Ring Seal. The tapping valve shall conform to City of Bismarck Standard Specification 901-2.7 for Gate Valves. Tapping saddles shall be installed according to manufacturer's installation instructions. The tapping saddle bolts shall be torqued using a calibrated torque wrench with a handle at least 12 inches in length. The CONTRACTOR should be prepared to show certification of torque wrench calibration at the request of the ENGINEER.

**901-2.13 CONCRETE.** Concrete for pipe cradles, anchors, and thrust blocking shall conform to the requirements of Section 501.

**901-2.14 BEDDING MATERIAL.** The bedding material shall be defined as stated in Section 801.

**901-2.15 SUBCUT GRAVEL.** The subcut gravel shall be as defined in Section 801.

**901-2.16 SALVAGE MATERIAL.** All existing pipe, gate valves, fittings, etc., removed during construction, when requested by the ENGINEER, shall be salvaged and delivered to the City of Bismarck Water Department as directed. No extra compensation will be allowed for this work.

## SECTION 901 – WATERMAIN

**901-2.17 MARKING TAPE.** The CONTRACTOR will be required to furnish and install marking tape located 2 feet above the top of all watermain installed under the contract. The tape shall be of the non-detectable type and shall have a minimum width of 5 inches. The tape shall be blue in color with the words "CAUTION WATER LINE BELOW" imprinted on the tape in black capital letters. The marking tape shall be equivalent to that manufactured by Presco standard grade.

Cost of marking tape and installation shall be considered incidental to other items.

**901-2.18 POLYETHYLENE ENCASEMENTS.** All ductile iron and cast iron pipe, valves, valve boxes, fittings, couplers, and hydrants shall be encased with 8-mil linear low-density (LLD) polyethylene film in accordance with ANSI/AWWA C105/A21.5. All encasements shall be considered incidental. Care shall be taken so as not to damage epoxy coating or painted surfaces. Damaged pipe and fittings shall be replaced at the expense of the CONTRACTOR.

**901-2.19 MECHANICAL JOINT BOLT REQUIREMENTS.** Bolts for mechanical joints for fittings, valves, and hydrants shall be alternated with one-half stainless steel and one-half low alloy steel. All stainless steel bolts shall be Grade 304.

**901-2.20 RESTRAINED JOINT BOLT REQUIREMENTS.** Bolts for restrained joints shall be stainless steel. All stainless steel bolts shall be Grade 304.

**901-2.21 INSULATION BOARDS.** Polystyrene insulation board shall have a thermal conductivity of not more than 0.28 BTU per hour per square foot per degree Fahrenheit per inch of thickness as tested in accordance with ASTM C177. The insulation shall not absorb moisture to an extent greater than 2.5 percent by volume as tested in accordance with ASTM D2842. The compression strength of the insulation shall be greater than 20 psi as tested in accordance with ASTM D1621. The density of the insulation shall be between 0.9 and 1.3 pounds per cubic feet as tested in accordance with ASTM D-1622. The insulation shall be specifically designed for protection of underground utilities and shall be installed in accordance with the manufacturer's recommendations.

### 901-3 CONSTRUCTION REQUIREMENTS

**901-3.1 EQUIPMENT.** All equipment necessary and required for the proper construction of watermain shall be on the project, in first-class working condition, and approved by the ENGINEER before construction is permitted to start.

The CONTRACTOR shall provide appropriate hoisting equipment to handle the pipe while unloading and placing it in its final position without damage to the pipe.

The CONTRACTOR shall provide methods and means to obtain the required compaction of the pipe bed and the backfill, as specified.

## SECTION 901 – WATERMAIN

**901-3.2 EXCAVATION AND PREPARATION OF TRENCH.** Excavation and preparation of the trench for watermain construction shall conform to Section 801 with the following additions:

The CONTRACTOR shall notify the City of Bismarck Fire Department of any loss of service of a fire hydrant or ability to use a fire hydrant 1 day before the occurrence. The CONTRACTOR shall also notify the City of Bismarck Fire Department when each hydrant is back in service. Any existing hydrants and valve boxes to be removed and not replaced shall be cut off 2 feet below the surface, and the void shall be filled with granular material, up to 2 feet below the surface. All hydrant heads shall be salvaged and delivered to the City of Bismarck Public Works Department at 601 South 26th Street.

Existing gate valves shall only be operated by City of Bismarck representatives. The CONTRACTOR will operate its newly installed valves until the project is accepted. Existing valves may not close tight enough to get a watertight closure. The CONTRACTOR may have to do work without a total water shut off with no extra charge to the City of Bismarck. In the event extra valves have to be shut down to slow the flow of water, there shall be no extra charge to the City of Bismarck by the CONTRACTOR for the time, up to 2 hours, to accomplish the water shutdown.

**901-3.3 ROCK EXCAVATION.** The rock excavation shall be as defined in Section 801.

**901-3.4 PIPE LAYING.** All pipe laying shall conform to Section 801 with the following additions:

Before lowering and while suspended, pipe shall be inspected for defects. Any defective, damaged, or unsound pipe shall be rejected. All foreign matter or dirt shall be removed from the inside of the pipe before it is lowered into its position in the trench, and it shall be kept clean by approved means during and after laying. Care shall be taken to prevent dirt from entering the joint space. At times when pipe laying is not in progress, the open ends of the pipe shall be closed by approved means, and no trench water shall be permitted to enter the pipe.

Cutting pipe for inserting valves, fittings, or closure pieces shall be done in a neat and workmanlike manner without damage to the pipe. Unless otherwise directed, pipe shall be laid with the bell ends facing the direction of laying. For lines on an appreciable slope, bells shall face upgrade, if directed by the ENGINEER. Whenever necessary to deflect the pipe from straight line, whether in the vertical or horizontal plane to avoid obstructions, to plumb stems, or other reasons, the degree of deflection shall not exceed manufacturer's recommendations and shall be approved by the ENGINEER. When any railroad is crossed, all precautionary construction measures required by the railroad officials shall be followed. No pipe shall be laid in water or when the trench condition or the weather is unsuitable for such work except by permission of the ENGINEER.

## SECTION 901 – WATERMAIN

The CONTRACTOR shall place a 16-inch by 16-inch or larger concrete block, as directed by the ENGINEER, under all valves. A larger block will be required for larger valves. The block shall be considered incidental to the price bid for the valve.

When installing watermain 12 inches and larger, on either side of each fitting and valve, a minimum of 50 lineal feet and 2 uncut sections of pipe shall be installed with restrained joints.

Restrained joint systems require approval by the ENGINEER. Preapproved restraining systems include Certa-Lok, Yellowmine, Romac 600 Series, Ford uniflange, Sigma PV-Lok and EBAA Iron, Inc C100. (Megalug). The CONTRACTOR shall note that the standard mechanical joint is not a restrained joint and offers no practical resistance against joint separations. All nuts, bolts and threaded rod shall be stainless steel. Restraining systems shall be incidental to watermain. All restrained joint systems shall be wrapped with 8mm poly.

All bolted fittings and service saddles shall be installed according to the manufacturer's recommendations. All bolts shall be tightened with a torque wrench according to the manufacturer's recommendations. The CONTRACTOR shall have a copy of the installation guide on site.

The CONTRACTOR shall furnish and install temporary watertight plugs in any opening left in the main line or lead off the main line, during construction, which would allow water or other debris to enter the newly constructed pipe or any existing pipe.

**901-3.5 TESTS.** Inspection and tests must be made by the manufacturer on all pipe and component parts before shipment. Such tests shall be made by a testing laboratory satisfactory to the ENGINEER, and such tests shall be made in accordance with the requirements of the American Society for Testing Materials. Documentary evidence that the materials have been passed such inspection and tests must be furnished to the ENGINEER before the delivery of the materials on the job. Any materials which do not prove satisfactory after being placed must be removed from the premises and replaced with satisfactory material. The cost of foundry inspection shall be paid for by the CONTRACTOR. After the pipe has been laid, all new pipe, including pipe for water services or any valve section thereof, shall be subject to a hydrostatic pressure test under the supervision of the ENGINEER. The test section shall be filled with water, and the pressure shall be gradually increased. If defects are found, the CONTRACTOR shall immediately make the necessary repairs at its own expense. The final pressure test shall be 150 pounds per square inch and shall be held at least 2 hours. The CONTRACTOR shall furnish all tools, equipment, and material necessary to perform the pressure test. The CITY OF BISMARCK will provide the water for filling the pipe.

**901-3.6 DISINFECTION AND BACTERIOLOGICAL TESTING.** After the new mains, replacement mains, service lines, and valved extensions have been hydrostatic pressure tested, they shall be flushed at a minimum scour rate of 3.0 fps until all foreign material has been removed. Chlorination applications shall be made under supervision of the ENGINEER in accordance with AWWA C651-14 Disinfecting Water Mains, with

## SECTION 901 – WATERMAIN

the exception that 5.1.1.1 Option B will not be allowed. Water shall be fed into the new line with chlorine applied in amounts to maintain a chlorine residual of 50 milligrams per liter for 24 hours or chlorine residual of 200 milligrams per liter for three hours. All valves and hydrants in the section treated shall be operated during this time in order to disinfect the appurtenance. Heavily chlorinated water should not remain in prolonged contact (maximum of 48 hours) with the watermain pipe. The chlorine shall be flushed from the main through hydrants and taps until all excess chlorine has been removed. The CONTRACTOR shall be responsible for repairing all grass, new or existing, damaged by the chlorination and flushing process. No chlorination water will be permitted in the watermain trench. The CONTRACTOR shall furnish all tools, equipment, materials, and chlorine to complete the chlorination process, incidental to other bid items. Prior to discharging chlorinated water into any drainage way, the CONTRACTOR shall obtain the permission of the ENGINEER. Taps are to be provided so at least one set of samples may be collected from every 1,200 feet of the new watermain, with one set from the end of the line and at least one set from each branch exceeding 20 feet in length. If the new watermain is less than 1,200 feet but more than 400 feet the CONTRACTOR shall collect two sets of samples, with one set from the end of the line and one set from location as determined by the ENGINEER. If the new watermain is less than 400 feet, one set of samples will be acceptable.

After final flushing two consecutive sets of acceptable samples, taken at least 16 hours apart, shall be collected from the new main. Any other option will only be allowed with the approval of the ENGINEER. The CONTRACTOR or testing laboratory, in the presence of the ENGINEER, shall perform the sampling. The CONTRACTOR shall record the locations, by street, station and date, the samples were taken. Sampling shall be performed with due care to prevent contamination using sterile bottles provided by the testing laboratory. It is not recommended that samples be collected from hoses or fire hydrants. The testing of the samples shall be performed by a State of North Dakota certified testing laboratory selected by the CONTRACTOR. All samples shall be tested for bacteriological quality, chlorine residual, and shall show the absence of coliform organisms. All super chlorinated water from the disinfection of a potable distribution system shall not reach waters of the state until the total residual chlorine level has become non-detectable. Any sample result less than 0.05 mg/l will be considered "non-detectable."

Written records of all test results shall be supplied to the ENGINEER and the CONTRACTOR by the testing laboratory as soon as possible. If trench water has entered the new main during construction or if, in the opinion of the ENGINEER, excessive quantities of dirt or debris have entered the new main, bacteriological samples shall be taken at intervals of approximately 200 feet and shall be identified by location. Samples shall be taken of water that has stood in the new main for at least 16 hours after final flushing has been completed.

The testing laboratory shall test for coliforms and e-coli using the "Colilert" or other ENGINEER approved equivalent test. The "Colilert" test is a pass/fail test that does not quantify the amount of bacteria. Any presence of coliforms or e-coli shall qualify as a failed test.

## SECTION 901 – WATERMAIN

If the initial disinfection fails to produce satisfactory bacteriological results, the new main may be reflushed and shall be resampled. If check samples also fail to produce acceptable results, the main shall be rechlorinated by the continuous-feed or slug methods of chlorination until satisfactory results are obtained.

Disinfection of any repair or short connection shall be in accordance with AWWA C651-14 Disinfecting Water Mains.

When corporation stops are used for testing and/or flushing, corporation stop shall be closed and left in place, no plugs are allowed.

All disinfection and bacteriological testing shall be incidental to other items.

**901-3.7 HANDLING PIPE AND ACCESSORIES.** Pipe, fittings, valves, hydrants, and other accessories shall, unless otherwise directed, be unloaded at the point of delivery, and hauled to and distributed at the site of the project by the CONTRACTOR. They shall at all times be handled with care to avoid damage. In loading and unloading, they shall be lifted by hoists or slid or rolled on skidways in such a manner as to avoid shock. Under no circumstances shall they be dropped. Pipe handled on skidways must not be skidded or rolled against pipe already on the ground. In distributing the material at the site of the work, each piece shall be unloaded opposite or near the place where it is to be laid in the trench. Pipe shall be handled in such a manner that a minimum of damage to the coating will result. Damaged coating shall be repaired in a manner satisfactory to the ENGINEER. Pipe shall be placed on the site of work parallel with the trench alignment and with bell ends facing the direction in which the work will proceed unless otherwise directed. The interior of all pipe fittings and other accessories shall be kept free from dirt and foreign matter at all times. Valves and hydrants, before installation, shall be drained and stored in a manner that will protect them from damage by freezing.

**901-3.8 BACKFILLING OF PIPE TRENCH.** Excavation and preparation of the trench for watermain construction shall conform to Section 801 with the following revision:

After the pipe has been laid to line and grade, the trench shall be backfilled under and along the sides of the pipe up to 2 inches over the top of the pipe by thoroughly compacting bedding material into place so as to form a uniform bed for the pipe.

**901-3.9 BACKFILL CLASSIFICATIONS.** The backfill classifications shall be as defined in Section 801.

**901-3.10 PROTECTING UNDERGROUND AND SURFACE STRUCTURES.** Protection shall conform to Subsection 801.

**901-3.11A BLOCKING HYDRANTS AND FITTINGS.** All hydrants, tees, and bends 22½ degrees and larger, and tapping saddles 3 inches and larger, shall be provided with suitable reaction blocking of concrete blocks of adequate size or poured in place concrete to prevent movement of fittings and hydrants when the pipe is under pressure.

## SECTION 901 – WATERMAIN

Precast concrete blocks shall be allowed for pipe sizes 12 inches and smaller. Thrust blocks for pipe sizes larger than 12 inches shall be poured in place. The blocks shall be placed in a manner acceptable to the ENGINEER and shall allow pipe and fitting joints to be accessible for repair. The concrete blocks may be poured in place if sufficient time is allowed for curing.

**901-3.11B HYDRANT EXTENSIONS.** Hydrant extensions shall be furnished and installed by CONTRACTOR per manufacturer's recommendations. Maximum extension length shall be three vertical feet. CONTRACTOR shall not stack multiple extensions.

**901-3.12 GATE VALVE ADAPTORS.** All gate valve boxes shall be installed upon the valve with the use of a gate valve adaptor. The adaptor shall be considered incidental to the price bid for "Gate Valve and Box".

**901-3.13 MARKING VALVE BOX LOCATIONS.** The CONTRACTOR will be required to furnish and install a steel fence post by each valve box unless directed not to by the ENGINEER. Steel fence posts to be used for valve locations shall be a "Tee" or "U" post having a minimum length of 5½ feet. The post shall be located within 2 feet from the valve box in a direction toward the street.

The cost of the steel fence post and the installation shall be considered incidental to other bid items.

**901-3.14 INSULATE WATERMAIN.** The CONTRACTOR shall furnish and install the insulation required to insulate the watermain as shown on the plans. The insulation shall be at least 4 inches thick by 8 feet wide centered on the watermain. The material between the top of the watermain bedding and the insulation shall consist of a concrete sand.

**901-3.15 TEMPORARY WATER SUPPLY.** If the CONTRACTOR elects to use a temporary water supply, the CONTRACTOR must provide a continuous water supply to the affected properties. The CONTRACTOR must use a polyethylene or PVC pipe. Rubberized garden hoses may not be used. The method and type of material shall be approved by the ENGINEER prior to setting up the temporary water supply. Any damage that may occur from the temporary water supply shall be the responsibility of the CONTRACTOR. All materials, labor, and equipment necessary to provide the temporary water supply shall be considered incidental to other bid items.

All temporary water mains and services shall be disinfected as per section 901-3.6 after installation or relocation and prior to putting into use. One water sample shall be taken per 1000 lineal feet of mainline and each individual service over 100 lineal feet at the end of a service connection after the temporary water is flushed. The sample shall show the absence of bacteria before connections are allowed. All mains and services shall be flushed prior to being put in service. No additional time or compensation shall be made for failure to pass bacteria test.

## SECTION 901 – WATERMAIN

**901-3.16 ABANDONED WATERMAIN.** The CONTRACTOR shall plug all exposed ends of the watermain to be abandoned with concrete and remove all existing valve boxes and hydrant heads on the abandoned line, incidental to other bid items. CONTRACTOR shall confirm all existing valves to be abandoned are closed prior to removal of the box.

**901-3.17 TAPPING SLEEVE WITH TAPPING VALVE.** Tapping saddles with valves shall be hydrostatically pressure tested on the main prior to requesting a tap. The test shall be minimum 125 pounds per square inch for a duration of 30 minutes.

The City of Bismarck Public Works Department will tap the watermain at a charge to the CONTRACTOR. The CONTRACTOR shall be responsible for all other work connected with installation of the tapping sleeve and valve, including the necessary space around the watermain required for the tapping machine and assisting the Public Works Department in positioning the tapping machine.

### **901-4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107 and as follows:

#### **901-4.1 MISCELLANEOUS ITEMS.**

All fittings, restraints, foster adaptors, and couplings shall be included in the price bid, unless otherwise specified.

Air Release Valve and Manholes shall be measured and paid for per Section 1205.

Bedding Material shall be measured and paid for per Section 801.

Subcut Gravel shall be measured and paid for per Section 801.

Rock Excavation shall be measured and paid for per Section 801.

**901-4.2 WATERMAIN.** The watermain pipe shall be measured through fittings and from centerline of pipe to centerline of pipe as shown in Standard Detail 900-2.

## **SECTION 910 – WATER MAIN PIPE BURSTING**

### **910-1 DESCRIPTION**

This specification shall cover the rehabilitation of the existing water mains by the pipe bursting method.

### **910-2 MATERIALS**

**910-2.1 WATER MAIN.** Pipe used for pipe bursting shall be fusible PVC C900 or high density polyethylene (HDPE), unless otherwise specified.

Fusible PVC C900 water main piping shall include: C900 and C905 which shall meet all requirements as per section 901 of the City of Bismarck Construction Specifications. Pipe shall have a DR18 rating with ductile iron pipe outside diameters. Pipe shall meet the product standards of AWWA C900 and C905. Pipe compound classification shall have a minimum cell classification of 12454 as defined in ASTM D1784.

High density polyethylene (HDPE) pipe shall be as per Section 901.

**910-2.2 VALVES, HYDRANTS AND FITTINGS.** All valves, hydrants, fittings, and related materials shall meet the requirements of section 900 of the City of Bismarck Construction Specifications.

All hydrant leads shall be PVC C900 from the hydrant to the mainline tee.

Where High-Density Polyethylene pipe is connected to mechanical joint fittings and valves, a HDPE mechanical joint adaptor shall be fused to the end of the pipe when a connection will be made to an existing pipe. Electrofusion fittings shall be PE4710 HDPE, Cell Classification of 345464C as determined by ASTM D3350-99, manufacturing standard ASTM D3261 and shall have a pressure rating equal to or greater than the pipe rating.

**910-2.3 SERVICE CONNECTIONS.** All water service and sanitary sewer service connection fittings and materials shall meet the requirements of Section 1209.

### **910-3 CONSTRUCTION REQUIREMENTS**

**910-3.1 CONSTRUCTION MEETING.** The CONTRACTOR shall attend a weekly construction update meeting, with the day and time to be determined at the preconstruction meeting, to discuss project status, upcoming work items, areas, traffic control and coordination with other projects.

## SECTION 910 - WATER MAIN PIPE BURSTING

**910-3.2 HANDLING AND STORAGE.** All pipe, fittings, and other materials shall be transported, handled, and stored as recommended by the manufacturer to prevent any damage. Any section of pipe having defects such as concentrated ridges, discoloration, excessive spot roughness, pitting, variable wall thickness, or any other defect in manufacturing shall be rejected by the ENGINEER and must be removed from the project site. If new pipe, fittings, and other materials become damaged during installation, they shall be rejected by the ENGINEER and replaced by the CONTRACTOR at his expense before proceeding further.

**910-3.3 EQUIPMENT.** The methods approved for rehabilitation of existing water mains are T.T. Technologies, Inc., Grundoburst Systems, Vermeer Bursting Systems, or approved equivalent. The bursting tool shall be capable of forcing its way through the existing water main by fragmenting the pipe and compressing the existing pipe into the surrounding soil and creating a void in which the new pipe, attached to the expander, can be pulled simultaneously. The unit shall maintain automatic thrust and pull back. A static unit must be capable of bursting in two directions from the same excavation.

The pipe bursting method shall be static with a minimum of 80 ton pull force. The existing pipe size and new pipe size shall be as noted on the construction plans. Any pipe bursting that introduces any lubricants into the pipe shall not be allowed.

All water main and related work, not covered in the Special Provisions shall be done in accordance with the City of Bismarck Construction Specifications.

**910-3.4 PIPE FUSION.** The pipe shall be assembled and joined on the site using the butt fusion method to provide a leak proof joint. Solvent cement or threaded joints will not be allowed. All equipment and procedures used shall be in strict compliance with the manufacturer's recommendations. A butt fused joint shall be true in alignment and have uniform rollback beads resulting from the use of proper temperature and pressure. The fused joint shall be watertight and have a tensile strength equal to or greater than that of the pipe.

Data loggers shall be used to record length of heating, fusing and cooling time, temperature, and pressure of each pipe joint and electrofused fitting. Resultant Data shall be submitted by the CONTRACTOR to the ENGINEER upon request.

Fused joints shall be subject to acceptance by the ENGINEER prior to installation. All defective joints shall be cut out and replaced at no cost to the OWNER. Any section of the pipe with a gash, blister, abrasion, nick, scar, or other fault greater in depth than 10 percent of the wall thickness shall be rejected and removed from the project site. A defective area of the pipe may be cut out and the joint fused in accordance with the procedures stated above.

**910-3.5 EXISTING WATER MAIN SHUTOFF.** Existing water main shall not be shut off to proceed with construction until the following procedures or items are complete and in place:

## SECTION 910 - WATER MAIN PIPE BURSTING

- a. Traffic control
- b. Sidewalk closures
- c. Construction and water disruption notifications to water users
- d. Hydrants out of order approved by ENGINEER
- e. Temporary water in place and ready for switchover
  1. Passing bacterial test results submitted to ENGINEER
- f. Other procedures required for preparing water system for disruption as directed by ENGINEER

**910-3.6 INSTALLATION.** The CONTRACTOR shall follow all manufacturer's procedures and specifications for the water main bursting equipment being used.

Water main pull lengths, bend radii, and entrance ramps shall be as per manufacturer's specifications and shall not exceed the limitations for the pipe type being installed.

For all water main piping, manufacturer's recommendations shall be followed for sufficient time to allow the pipe to relax from thermal expansion and pull stress after being pulled into place and prior to being cut or connected.

Water main installation may not be accepted by the ENGINEER if manufacturer's recommendations are not followed.

Water mains to be burst shall be no closer than 10 ft from a live water main. If closer than 10 ft, the live water main shall be isolated at the next valve going back on the system.

The number of excavation pits shall be kept to a minimum, as necessary to perform the work efficiently. The CONTRACTOR shall consider using an area that will have to be excavated for a valve insertion, water service connection, or connections to existing water mains.

Connections to existing water mains shall be included in the price bid for water main.

Where subcut gravel is used to set up or support the pipe bursting equipment, it shall be included in the price bid for water main and there will be no extra compensation.

The invert profile of most water mains is assumed. The CONTRACTOR shall verify the existing elevations of all connections and crossings prior to making the connections. The grade of the water main shall be adjusted gradually minimizing the need for vertical bends.

Wrap all existing ductile and cast iron water main and fittings that are exposed during construction. Include within the price bid for water main.

The CONTRACTOR shall plug all exposed ends of the water main to be abandoned with concrete and remove all top sections of gate valve boxes, hydrant heads and curb stop boxes below ground level. Fill the remaining hydrant barrel or gate valve box with sand and add a minimum of 1 foot of concrete at the top of the hydrant barrel or gate

## SECTION 910 - WATER MAIN PIPE BURSTING

valve box section and confirm that all valves to be abandoned are closed. All hydrant heads shall be scheduled and delivered to City of Bismarck, Public Works scrap metal pile at 601 S. 26<sup>th</sup> Street. This work shall be included in the price bid for water main items.

Removal of existing thrust blocking behind elbows, tees, hydrants and valves shall be included in the price bid for water main items.

The CONTRACTOR shall be responsible for any damage to utilities result from bursting or excavation operations. The CONTRACTOR shall be responsible for any damage to properties and such damage shall be repaired and the property restored to its original condition at the CONTRACTOR's expense.

The CONTRACTOR shall provide verification to the ENGINEER by means of potholing or excavation of the water main for areas that are within 12 inches of another utility or as called out on the plans. The verification at utility crossings shall be excavated to relieve loading and/or prevent damage during the bursting process. All verifications shall be included in the price bid for Surface Restoration.

The CONTRACTOR may encounter abandoned utilities while excavating. Extra time to verify and removal of the abandoned utility shall be included in the price bid for water main items.

The CONTRACTOR shall notify the ENGINEER if material of existing pipe is found to differ from what is stated in the plans.

**910-3.7 BACKFILLING.** Backfill shall be done in accordance with section 801 of the City of Bismarck Construction Specifications.

All imported backfill shall be Class A.

**910-3.8 TESTING.** The hydrostatic pressure test, disinfection and bacteriological testing shall be done in accordance with section 901 of the City of Bismarck Construction Specifications.

Pressure testing of the new water main shall be completed only after the water main has been installed and connected.

### **910-4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107 and as follows:

Water main pay quantities are based on actual length of water main, not stationing.

All fittings, restraints, foster adaptors, and couplings shall be included in the price bid for water main.

## **DIVISION 1000**

### **ELECTRICAL**

#### **SECTION 1002 – UNDERGROUND CIRCUITS**

##### **1002-1 DESCRIPTION**

This work shall consist of the installation of underground electrical conductors, conduits, junction boxes, and related items in accordance with these specifications and standard details at the locations shown on the plans or as directed by the ENGINEER.

##### **1002-2 MATERIALS**

**1002-2.1 GENERAL.** Materials to be furnished by the CONTRACTOR shall be all materials required to install the underground electrical circuits in place as shown on the plans complete and ready for operation.

All materials and equipment furnished shall be new and shall be approved by the Underwriter's Laboratories, Inc. as conforming to its standards in every case where such a standard has been established for the item in question.

It is the intent of the plans and specifications to comply with the requirements set forth by the National Electric Code, the North Dakota State Electrical Board, the local utility company, and the ordinances established by the CITY. It shall be the responsibility of the CONTRACTOR to ensure that the above requirements are met. All electrical work outlined in this section shall be done under the supervision of a master electrician.

Should the plans or the specifications not meet these minimum established standards, either through omission or specification of equipment, material, and installation methods installation, the CONTRACTOR shall immediately notify the ENGINEER.

Requests for approved equivalents, alternates or substitutions shall be in accordance with Section 102 for all items included in this section. Equivalents, alternates or substitutions will be provided to plan holders in advance of opening of bids.

The CONTRACTOR shall submit shop drawings or product data, in accordance with Section 104 for all items included in this section. Drawings or product data shall be marked with bid item designation and submitted within 30 days after contract award. No equipment shall be ordered until shop drawings and product data have been approved by the ENGINEER.

The CONTRACTOR shall keep one set of plans at the construction site as work is occurring to record any deviations from the plans and specifications including, but not

## SECTION 1002 – UNDERGROUND CIRCUITS

limited to, relocated light units, feed points, junction boxes and changes in the cable location. This red-lined plan set shall be turned over to the CITY prior to the close of the project.

The CONTRACTOR shall be responsible for locating and marking all underground circuits associated with the project throughout the course of the project. The CONTRACTOR shall be relieved of this responsibility at such point in the project when the lights are fully operational, a set of red lined drawings has been submitted and approved by the ENGINEER. The cost for all locating and marking shall be incidental to the cost of other items.

When the installation is complete and at such time as may be specified by the ENGINEER, the CONTRACTOR shall conduct an operating test for approval. The equipment shall be demonstrated to operate in accordance with the requirement of the specifications, the plans, and to the satisfaction of the ENGINEER. The CONTRACTOR shall furnish all instruments and personnel required for all tests. All test results shall be recorded. The CONTRACTOR shall be present during all tests and inspections unless so informed by the ENGINEER.

**1002-2.2 UNDERGROUND CONDUCTORS.** Underground circuit conductors shall be stranded copper per ASTM B-3, Class B stranding per ASTM B-8, and type RHH/RHW-2/USE-2 insulation complying with UL Standard 854 for type USE-2 and UL standard 44 for Types RHH and RHW-2. Conductor sheath shall be marked with voltage, AWG, Type (RHH/RHW-2/USE-2) and manufacturer. The conductor sheath shall be color coded to indicate red-power, blue-power, and white-neutral.

Ground conductor shall be stranded copper, per ASTM B-3, Class B stranding per ASTM B-8, and type TW/THW/THW-2 insulation complying with UL Standard 83. Conductor sheath shall be marked with voltage, AWG, Type (TW/THW/THW-2) and manufacturer. The conductor sheath shall be green in color.

Service conductors from electric utility service point shall be Type RHW-USE, sized as per utility company requirements and electrical loading.

**1002-2.3 CONDUITS.** Conduits for underground circuits shall be 2-inch polyvinyl chloride (PVC) Schedule 40 or smooth-wall HDPE innerduct unless otherwise noted in the plans.

The schedule 40 PVC shall be ETL listed, conforming to UL-651 and NEMA TC2, listed for electrical usage, sunlight resistant. Bell-type fittings shall be placed at both ends.

The HDPE innerduct shall be red in color, ETL listed, conforming to UL-651A, UV stabilized meeting HDPE resin requirements per ASTM D 3350. Innerduct connections shall be a push-lock coupler providing a watertight and airtight connection.

**1002-2.4 MARKER TAPE.** Marker tape shall be 6-inch wide red plastic tape marked "Caution - Buried Electric Cable" for all trenched conduit or conductors.

## SECTION 1002 – UNDERGROUND CIRCUITS

**1002-2.5 JUNCTION BOXES.** Junction boxes shall be made of a lightweight, high-density, polymer concrete composite, UL listed with knockouts for conductor entrance. The box shall comply with ANSI/SCTE 77 with a design load of 22,500 pounds, a test load of 33,750 pounds, and meet ANSI Tier 22 test provisions. The cover shall meet an 8,000-pound design load and 12,000-pound test load. Boxes shall be resistant to sunlight exposure, weathering, chemicals, and unaffected by freeze-thaw cycles to -50°F. Minimum dimensions shall be 24-inch by 13-inch by 18-inch D (stackable). Box covers shall have stainless steel hex bolts and be stamped with standard logo "Street Lighting."

Box manufacturer shall be Quazite, Model PG or approved equivalent.

**1002-2.6 SPLICE CONNECTORS.** Splice connectors within junction boxes for multiple connections shall be Homac, Type RAB-X-URD-BUSS submersible insulated subsurface terminal for copper conductor, or approved equivalent.

**1002-2.7 UNDERGROUND SPLICES** Underground splices are not permitted unless approved by the ENGINEER. When the ENGINEER has determined that a splice is acceptable, the CONTRACTOR shall install a Homac, Type FSS splice or Tyco Gel Wrap 6-inch type, RAY-GELWRAP-18/4-150-5PLC-CLOSR-6IN.

**1002-2.8 GROUND RODS** Ground rods shall be ½" X 10' copper-bonded for each streetlight unit and junction box. Ground rods for streetlighting feedpoints shall be per Section 1003. Ground rods for streetlight units shall be per Section 1004.

### 1002-3 CONSTRUCTION REQUIREMENTS

**1002-3.1 STREETLIGHTING CIRCUITS.** All streetlighting circuits shall be 120/240-volt or 240-volt circuits consisting of two or three conductors as indicated on the plans. Conductors shall be continuous from each pole base, feedpoint or junction box. Splicing conductors underground will not be allowed without specific approval of the ENGINEER.

All conductors shall be installed in conduit unless otherwise indicated on the plans or in the special provisions.

Ground conductors shall be provided between all streetlight poles, feedpoints and junction boxes. A ground rod shall be installed at each light standard and at each junction box. Ground rods shall be 1/2inch x 10 feet and shall be attached to ground wire using ground rod clamps. Bond ground conductors to grounding lug in pole handhole, ground rod, feed point enclosure, feed point panels and relay cabinets per the NEC.

Any tree roots encountered and/or damaged during the installation of conduit, conductors, feedpoints or junction boxes shall be handled according to Section 201 "Tree Root Cutting."

## SECTION 1002 – UNDERGROUND CIRCUITS

**1002-3.2 CONDUIT INSTALLATION - BORED.** The conduit shall be bored whenever possible to avoid pavement and sod removal and replacement. The conduit for all street lighting conductors shall be installed between 24-inches and 30-inches below final grade and 12-inches behind the back of curb. The conduit for utility service conductors shall be installed a between of 36-inches and 40-inches below final grade. The alignment and depth of the conduit must be maintained as detailed such that the bored conduit does not deviate more than 6 inches from its intended location. The CONTRACTOR shall mark with paint or flag the location of the bored conduit.

At the request of the ENGINEER, the CONTRACTOR shall demonstrate the installed conduit meets the alignment and required depth throughout the length of any conduit run. Any deviation in alignment and/or depth shall be corrected by the CONTRACTOR as directed by the ENGINEER, at no cost to the CITY.

For concrete light standards, the conduit shall end between 12-inches and 18-inches from the pole wire entrance to allow space for a frost loop. At feedpoints and streetlights with concrete bases, connect the conduit to the conduit at the feedpoint and concrete base such that the conduit is continuous into the feedpoint or concrete base. At junction boxes, the conduit should extend one inch past the edge of the junction box wall. Conduit shall end between 24-inches and 36-inches from any underground splices. Conduit ends shall be terminated with bell-type fittings. Where practical, conduit shall be sloped to provide drainage.

If an obstruction is encountered when boring conduit under a concrete or asphalt street, driveway, or alley, or for any reason it becomes impractical to install the conduit in this manner, the ENGINEER may grant the CONTRACTOR permission to cut or saw the street, driveway, or sidewalk so conduit can be trenched into place. The width of the concrete or asphalt to be removed and the depth of the saw cutting shall be performed as directed by the ENGINEER. No extra payment will be made for cutting, removing, and replacing the concrete or asphalt. Cost of installing conduit by this method shall be included in the price bid for 2-inch conduit. Street cuts shall not be started until permission is granted by the ENGINEER.

Any excavations or exploratory cuts to any asphalt or concrete surface for the purpose of locating any existing underground utilities or obstructions to aid in the boring conduit shall be included in the price bid for conduit bored including any traffic control requirements. No extra payment will be made for sawing, removing, and replacing the concrete or asphalt. The width of the concrete or asphalt to be removed and the depth of the saw cutting shall be performed as directed by the ENGINEER.

**1002-3.3 CONDUIT INSTALLATION - TRENCHED.** The conduit installed by trenching shall be installed as per Section 1002-3.2 except for the method of installation. Excavate trench to 3-inches below the required minimum depth per Section 1002-3.2. Conduit shall be laid in the trench as per the standard detail.

Trench shall be backfilled and compacted in inch lifts or layers to the top of the trench.

## SECTION 1002 – UNDERGROUND CIRCUITS

Only suitable material as defined by Section 202 shall be used for backfilling of trenches. Backfill with substandard material is prohibited even though such materials may have been excavated from the trench.

The trenches shall be compacted by approved methods to a minimum 90 percent of maximum dry density at optimum moisture in accordance with ASTM D1557 when under future pavement or concrete areas (including sidewalks and driveways). Boulevards, grassed areas, and any other disturbed areas shall be compacted to a minimum 80 percent of maximum dry density at optimum moisture.

Marker tape shall be provided near the top of trench (6 to 8 inches below final grade) in all trenches. Cost shall be incidental to the trenching price.

### **1002-3.4 CONDUCTOR INSTALLATION.**

Install conductors in conduit by hand pulling such that the conductors are not strained or exceed maximum pulling tension as recommended by the manufacturer. Care shall be taken during installation of conductors to not bend or kink conductor to a radius of less than six times the conductor diameter.

Install a 12-inch to 18-inch diameter frost loop between the end of the conduit and any concrete light standard or at either end of a buried splice. All streetlight conductors routed from pole to pole or junction box shall be brought up into pole or junction box whether they are to be spliced or not. Splicing will only be allowed in junction boxes, pole bases, feed point cabinets or as approved by the ENGINEER. Split bolts shall not be used as a means of splicing or bonding.

In areas where conduit is not installed, the conductors shall be direct buried in a trench. Excavate trench to 3-inches below the required minimum depth per Section 1002-3.2. The trench shall be filled with 3-inches of clean, washed sand bedding, leveled, and lightly tamped. The conductors shall be laid in the trench as per the standard detail. Trench shall again be filled with 3-inches of clean, washed sand bedding, leveled, and lightly tamped across the full width of the trench.

The trench shall then be backfilled and compacted in 4-inch lifts or layers to the top of the trench. Only suitable material as defined by Section 202-1c shall be used for backfilling of trenches. Backfill with substandard material is prohibited even though such materials may have been excavated from the trench.

The trenches shall be compacted by approved methods to 90 percent of maximum dry density at optimum moisture in accordance with ASTM D1557 when under future pavement or concrete areas (including sidewalks and driveways). Boulevards, grassed areas, and any other disturbed areas shall be compacted to 80 percent of maximum dry density at optimum moisture.

If a specific excavation is judged to be free of rocks and debris, CONTRACTOR shall be allowed to utilize backfill without sand cushion upon approval of the ENGINEER.

## SECTION 1002 – UNDERGROUND CIRCUITS

**1002-3.5 JUNCTION BOX INSTALLATION.** Junction boxes shall be provided and installed at locations shown on plans. Top of junction boxes shall be the same elevation as top of adjacent curb or sidewalk or as directed by the ENGINEER. Provide a 6-inch base of drainage aggregate under the junction box as shown in standard detail. Ground rods shall be provided at all junction box locations.

Provide a slack loop in all conductors so conductor can be pulled up out of junction box to a minimum of 24-inches above ground.

Splice connectors shall be as indicated in Subsection 1002-2.6 “Splice Connectors” and shall be raised off the bottom of the junction box such that they are directly below the junction box cover and positioned upward.

Tape connector kits with a half-lapped layer of rubber or synthetic rubber tape and one layer of tape for a distance of 1½ inches each side of joint. Each conductor shall be labeled with the circuit number.

**1002-3.6 UNDERGROUND SPLICES.** Underground splices shall not be permitted unless approved by the CITY. No more than two underground splices shall be permitted on any continuous run of cable between feed points, poles, and junction boxes.

When the ENGINEER has determined that a splice is acceptable, the CONTRACTOR shall install the splice connector kit. The splice shall then either be wrapped once with 3M tape, Type 130C, and twice with Scotch tape, Type Super 33 Plus, or install a Tyco Gel Wrap 6-inch type, RAY-GELWRAP-18/4-150-5PLC-CLOSR-6IN.

The CONTRACTOR shall mark all underground splice locations, along with the distance from the feedpoint, junction box, or streetlight standard on the same red lined drawings, as required under Section 1002-2.1 of the City of Bismarck Construction Specifications for Municipal Public Works Improvements.

**1002-3.7 REPAIRS TO SIDEWALKS AND STREETS.** In locations where sidewalks, pavement, driveways, or streets are opened for installation of cable, conduit, or poles, the removed area shall be replaced to the original thickness. The repair shall conform to either Sections 300 and 400 for AC Pavement or Sections 500 and 600 for Concrete Pavement Repair.

In the event of the inability of the CONTRACTOR to bore conduit under an improved area, the CONTRACTOR shall, with the ENGINEER's permission, be allowed to open cut the area. The CONTRACTOR shall minimize the area removed as much as possible but must allow enough area to allow for installation of cable or conduit and access for compaction equipment. The CONTRACTOR shall make cuts so that uniform edges for trenches may be obtained. In concrete, the CONTRACTOR shall utilize existing joints or sawed joints as required.

## SECTION 1002 – UNDERGROUND CIRCUITS

The backfill under all improved areas shall be Class A and shall be compacted to not less than 90 percent of maximum dry density at optimum moisture in accordance with ASTM D1557.

Where specified on plans, CONTRACTOR shall be paid at the unit price bid for Concrete or AC Pavement unless incidental. In the event of the inability of the CONTRACTOR to bore under an improved area and an open cut is required, the cost of the concrete or AC pavement shall be incidental to the installed conduit.

In the event of damage of an improved area due to construction, all repair costs shall be borne solely by the CONTRACTOR.

At the discretion of the ENGINEER, AC pavement patches or repairs shall be seal coated in accordance with Section 400.

**1002-3.8 SEEDING AND SODDING.** Where installation of trench or excavation is in an unimproved area, the CONTRACTOR shall return the area to its previous state. The topsoil from the trench and excavation shall be salvaged and reused. If additional topsoil is required, it shall be in accordance with Section 1201 of the CITY Specifications; seeding shall be in accordance with Section 1202. The cost of seeding the trench or excavation shall be incidental in the price bid for the trench or the excavation.

In areas where there is an established lawn or at the direction of the ENGINEER, the trench or excavation shall be sodded. Sodding shall conform with Section 1203. The CONTRACTOR may reuse the existing sod provided that it is cleanly cut, rolled up, stored and kept moist. Topsoiling cost shall be incidental to sodding bid item.

### **1002-4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107 and as follows:

#### **MISCELLANEOUS PAY ITEMS:**

Sodding and Seeding shall be measured and paid for under Section 1202 and 1203. Conversion for sodding from square yards to linear feet shall be: 1 square yard equals 6 linear feet for an 18 inch wide roll of sod.

**1002-4.1 CONDUIT.** Conduit shall include installation of 2-inch PVC conduit or HDPE innerduct by either directional boring or trenching.

Excavations, bore pits and trenches required for the installation of conduit shall be a part of the conduit installation price including removing and replacing concrete, asphalt, backfilling, topsoiling and seeding. The conduit shall be measured from center to center

## SECTION 1002 – UNDERGROUND CIRCUITS

of pole, junction box or feedpoint including the horizontal offset from the main circuit location.

**1002-4.2 2-WIRE CONDUCTORS.** Two No. 4 or two No. 2 single conductors meeting the requirements of this specification, installed in conduit or laid in trench. Measurement of the 2-wire conductor will be from center to center of pole, junction box or feedpoint including the horizontal offset from the main circuit location. CONTRACTOR shall make allowance for necessary conductors in and out of poles, feedpoints and junction boxes along with any slack loops or vertical conductor runs required by this specification in the unit price bid.

**1002-4.3 3-WIRE CONDUCTORS.** Three No. 4 or three No. 2 single conductors meeting the requirements of this specification, installed in conduit or laid in trench. Measurement of the 3-wire conductor will be from center to center of pole, junction box or feedpoint including the horizontal offset from the main circuit location. CONTRACTOR shall make allowance for necessary conductors in and out of poles, feedpoints and junction boxes along with any slack loops or vertical conductor runs required by this specification in the unit price bid.

**1002-4.4 COPPER GROUND.** Copper ground shall be No. 6 ground wire meeting the requirements of this specification, installed in conduit or laid in trench. Measurement of the ground conductor will be from center to center of pole, junction box or feedpoint including the horizontal offset from the main circuit location. CONTRACTOR shall make allowance for necessary conductors in and out of poles, feedpoint and junction box along with any slack loops or vertical conductor runs required by this specification in the unit price.

**1002-4.5 JUNCTION BOX.** Junction box shall include the junction box and cover, installed at the required elevation, splice connectors, excavation, backfill, compaction, ground rod, connections and surface restored to preconstruction conditions.

**1002-4.6 TRENCH** Trenching shall include all excavation required for trenches as shown on the plans or as directed by the ENGINEER including sand cushion, backfill, compaction and marker tape.

Measurement for payment shall be at the unit price bid for each linear foot (LF) of trench excavated, backfilled, compacted and surface restored to preconstruction conditions as installed and accepted by the ENGINEER.

## **SECTION 1003 – STREETLIGHTING FEEDPOINT**

### **1003-1 DESCRIPTION**

This item consists of installation of streetlighting feedpoint, pad or pole mounted, including cabinet, cabinet foundation, relays, photocell, load center and appurtenances in accordance with these specifications and standard details at the locations shown on the plans or as directed by the ENGINEER.

### **1003-2 MATERIALS**

**1003-2.1 GENERAL.** CONTRACTOR shall furnish all materials required to install streetlighting feedpoint in place as shown on the plans complete and ready for operation.

All materials and equipment furnished shall be new and shall be approved by the Underwriter's Laboratories, Inc. as conforming to its standards in every case where such a standard has been established for the item in question.

It is the intent of the plans and specifications to comply with the requirements set forth by the National Electric Code, the North Dakota State Electrical Board, the local utility company, and the ordinances established by the CITY. It shall be the responsibility of the CONTRACTOR to ensure that the above requirements are met. All electrical work outlined in this section shall be done under the supervision of a master electrician.

Should the plans or the specifications not meet these minimum established standards, either through omission or specification of equipment, material, and installation methods installation, the CONTRACTOR shall immediately notify the ENGINEER.

Requests for approved equivalents, alternates or substitutions shall be in accordance with Section 102 for all items included in this section. Equivalents, alternates or substitutions will be provided to plan holders in advance of opening of bids.

The CONTRACTOR shall submit shop drawings or product data in accordance with Section 104 for all items included in this section. Drawings or product data shall be marked with bid item designation and submitted within 30 days after contract award. No equipment shall be ordered until shop drawings and product data have been approved by the ENGINEER.

The CONTRACTOR shall keep one set of plans at the construction site as work is occurring to record any deviations from the plans and specifications including, but not limited to, relocated light units, feed points, junction boxes and changes in the cable location. This red-lined plan set shall be turned over to the CITY prior to the close of the project.

## SECTION 1003 – STREETLIGHTING FEEDPOINT

When the installation is complete and at such time as may be specified by the ENGINEER, the CONTRACTOR shall conduct an operating test for approval. The equipment shall be demonstrated to operate in accordance with the requirement of the specifications, the plans, and to the satisfaction of the ENGINEER. The CONTRACTOR shall furnish all instruments and personnel required for all tests. All test results shall be recorded. The CONTRACTOR shall be present during all tests and inspections unless so informed by the ENGINEER.

### **1003-2.2 FEEDPOINT ENCLOSURES.**

- a. Pad-mounted feedpoint enclosure having the following features:
  1. Minimum 1/8-inch aluminum, with a brushed aluminum finish, NEMA 3R with a domed roof and NEMA 3R drip shield. ETL or UL listed in accordance with UL 50.
  2. Dimensions of the enclosure: 42" W X 12" D X 51" H.
  3. Base frame: minimum 2" along each side and 1/4" thick
  4. Two doors with continuous stainless steel or aluminum piano-style hinges, a neoprene gasket, and a stainless steel 3-point latch capable of being padlocked.
  5. The enclosure shall be equipped with back panel rails or unistrut such that equipment may be mounted in the cabinet with no penetrations to the exterior of the cabinet. The back panel shall be galvanized steel. All hardware shall be non-corrosive.
  6. Pre-approved manufacturers:
    - Povolny Specialties, Inver Grove Heights, MN
    - States Manufacturing, Minneapolis, MNOther manufacturers as approved by special provision or addendum.
  
- b. Pole-mounted feedpoint enclosure having the following features:
  1. Minimum 1/8-inch aluminum, with a brushed aluminum finish with an exterior mounting plate, NEMA 3R. ETL or UL listed in accordance with UL 50.
  2. Dimensions of the enclosure: 30" W X 8" D X 36" H (minimum).
  3. One door with three lift off hinges, a neoprene gasket, and a stainless steel 3-point latch capable of being padlocked.
  4. The enclosure shall be equipped with back panel rails such that equipment may be mounted in the cabinet with no penetrations to exterior of the cabinet. The back panel shall be galvanized steel. All hardware shall be non-corrosive.
  5. Pre-approved manufacturers:
    - Hoffman Enclosures
    - Povolny Specialties, Inver Grove Heights, MN
    - States Manufacturing, Minneapolis, MNOther manufacturers as approved by special provision or addendum.

**1003-2.3 LIGHTING RELAYS/CONTACTORS.** Lighting relays/contactors shall be Square D-Type S as manufactured by Schneider Electric, Eaton-Type CN 35 as manufactured by Cutler-Hammer or approved equivalent and shall be electrically held,

## SECTION 1003 – STREETLIGHTING FEEDPOINT

rated at 60 A, UL listed, with normally open contacts, and housed in a NEMA 1 enclosure.

### **1003-2.4 PANEL AND CIRCUIT BREAKERS.**

- a. For a pad mounted feedpoint, the electric panel shall be a single-phase load center with a NEMA 1 rated enclosure with minimum 8 two-pole spaces (16 single-pole circuits), rated 120/240 volt, 100-amp two-pole main breaker, copper bus, and a minimum 22,000-amp IR. The load center shall be Square D, Model QO116M100 with QO breakers or equivalent.
- b. For a pole mounted feedpoint, the electric panel shall be a single-phase load center with a NEMA 1 rated enclosure with minimum 6 two-pole spaces (12 single-pole circuits), rated 120/240 volt, 100-amp two-pole main breaker, copper bus, and a minimum 22,000-amp IR. The load center shall be Square D, Model QO112M100 with QO breakers or equivalent.

### **1003-2.5 SWITCHES AND OUTLETS.**

- a. A single pole test switch shall be provided to test the lights and bypass the photocell. The switch shall be mounted on a metal box with raised cover.
- b. A 20 A, GFI duplex receptacle shall be provided. The outlet shall be mounted on a metal box with a raise cover.

**1003-2.6 PHOTOCCELL.** Photocell for control of relays shall be Hubbell PBT-1, Intermatic K4021C, or approved equivalent.

**1003-2.7 METER TRIM** Meter trim shall be in a NEMA 3R enclosure, galvanized steel with a gray powder coat finish. Meter trim shall be ringless, UL listed, rated for 600V, 200A and shall have a lever bypass. Meter trim as manufactured by Milbank or approved equivalent.

## **1003-3 CONSTRUCTION REQUIREMENTS**

### **1003-3.1 FEEDPOINT-PAD MOUNTED -TYPE I, II, III and IV.**

The new pad-mounted feedpoint shall be installed per standard details 1003-1, 1003-2, 1003-4, and 1003-5. Each Feedpoint-Pad Mounted Type refers to the number of 2-wire or 3-wire streetlight circuits.

The concrete to be used in the construction of the concrete foundations shall conform to the City of Bismarck Specifications, Section 600 for Sidewalks, Driveways, Curb, and Combined Curb and Gutter. Install two 8" X 4' concrete piers, anchored with rebar as shown in the detail. The concrete pad shall be set on 12-inches of drainage aggregate subbase. Provide 1-inch chamfer around all edges.

## SECTION 1003 – STREETLIGHTING FEEDPOINT

Provide a minimum of seven 2-inch PVC stub outs through concrete base and extending a minimum of 12 inches beyond edge of the base. Point one conduit towards power company transformer and six towards direction of outgoing circuits. Provide two 1-inch conduits for ground rod conductors through the base only. Notify ENGINEER a minimum of 24 hours prior to pouring concrete base such that the form and cable entrances may be inspected. All unused conduits shall be sealed with a duct plug as manufactured by Tyco, Series JM. All used conduits shall be sealed with duct seal.

Install a concrete housekeeping pad between the feedpoint foundation and the edge of the sidewalk when sidewalks are already in place or as specified in the plans. The housekeeping pad shall run the length of the feedpoint foundation and shall be 4 inches thick and meet the requirements of City sidewalks as detailed in Section 601 of the standard specifications.

The pad-mounted feedpoint enclosure shall be anchored to the concrete foundation, at a minimum, at each corner, with minimum 3/8" diameter x 8" bolts. No more than 2" of the anchor bolt shall be exposed. Seal the external interface between all feedpoint cabinets and foundations to prevent infiltration of dust and moisture. Sealant shall be a silicone or polyurethane product rated for exterior use, readily bond to both metal and concrete, and be grey or clear in color.

Provide one lighting relay or contactor for each 3-wire streetlight circuit (2-120V) or one lighting relay or contactor for each 2-wire streetlight circuit (1-240V). Provide one 40-amp two-pole breaker for each 2-wire or 3-wire circuit, a 15-amp one-pole breaker for control circuit and a 20-amp one-pole breaker for convenience outlet. Control circuit includes installing the switch to bypass the photocell for testing of streetlight circuits. Install GFI outlet.

Provide min. 1-1/4" flexible conduit and min. 6"x6"x36" wire trough with tool-less access covers to enclose all exposed conductors between the load center, lighting contactors and the field conduits, as per standard detail 1003-1. Terminal blocks shall be provided by the CONTRACTOR for use for any connection within the feedpoint. The terminal blocks(s) shall be installed within the wire trough. Wire nuts shall not be permitted in the feedpoint or wire trough to make any connection. Terminal blocks will not be required when connections within the feedpoint are not required. The Contractor shall reserve the space for future terminal blocks in the layout of the feedpoint.

Photocell shall be mounted on the side of enclosure as per the detail; direct photocell to north or as directed by the Engineer.

Provide two 5/8-inch by 10-foot copper ground rods. The two ground rods shall be a minimum of 6 feet apart and shall be looped. Bond all circuits, relay cabinets, electric panel cabinet, enclosure, and neutral per NEC.

Install 120/240-volt single-phase service from power company transformer. Service conductors, rated at 200 amp, shall be installed in 2-inch, minimum, conduit with three

## SECTION 1003 – STREETLIGHTING FEEDPOINT

Type RHW-USE conductors sized for voltage drop and power utility company requirements.

Underground conductors to provide power to the feedpoint shall be 36 inches deep and shall be included in the cost of the feedpoint. Conduit above grade and not otherwise enclosed shall be galvanized rigid steel conduit. Rigid steel conduit ends shall be carefully reamed to provide a smooth surface for conductors. Plastic bushings shall be placed on rigid steel conduit ends. Route conduit through meter. Meter location shall be as shown on standard feedpoint detail. Size and type of incoming power conductors must meet NEC and utility company requirements. All unfused conductors within the feedpoint enclosure shall be placed in conduit.

Verify location of pad-mounted feedpoint with the utility company based on transformer location and space requirements. Notify ENGINEER if feedpoint cannot be served at the location shown on the plans.

**1003-3.2 FEEDPOINT-POLE MOUNTED -TYPE I AND II.** The new pole-mounted feedpoint shall be installed per standard details 1003-3, 1003-4 and 1003-5. Each Feedpoint-Pole Mounted Type refers to the number of 2-wire or 3-wire streetlight circuits.

Incoming service shall be fed from below grade unless otherwise shown on the plans. Underground conductors to provide power to the feedpoint shall be 36 inches deep and shall be included in the cost of the feedpoint. Route conduit through meter. Meter location shall be as shown on standard feedpoint detail. Size and type of incoming power conductors must meet NEC and utility company requirements. All unfused conductors within the feedpoint enclosure shall be placed in conduit.

Provide one 1½-inch galvanized rigid steel conduit stub outs for each 2-wire or 3-wire streetlight circuits and conduit as required by utility company for power conductors. Rigid steel conduit ends shall be carefully reamed to provide a smooth surface for conductors. Plastic bushings shall be placed on rigid steel conduit ends. Point one conduit towards power company transformer and all other conduits in the direction of the outgoing circuits. Provide two 1-inch conduits for ground rod conductors. All conduits shall be sealed with duct seal.

Provide one lighting relay or contactor for each 3-wire streetlight circuit (2-120V) or one lighting relay or contactor for each 2-wire streetlight circuit (1-240V).

Provide two 5/8-inch by 10-foot copper ground rod at bottom of pole as shown on detail drawings; ground enclosure and service. The two ground rods shall be a minimum of 6 feet apart and shall be looped. Bond all circuits, relay cabinets, electric panel cabinet, enclosure, and neutral per NEC.

Terminal blocks shall be provided by the CONTRACTOR for use for any connection within the feedpoint. The terminal blocks(s) shall be installed within the wire trough. Wire nuts shall not be permitted in the feedpoint or wire trough to make any connection.

## SECTION 1003 – STREETLIGHTING FEEDPOINT

Terminal blocks will not be required when connections within the feedpoint are not required. The Contractor shall reserve the space for future terminal blocks in the layout of the feedpoint.

Verify location of pole-mounted feedpoint with the utility company based on transformer location and space requirements. Notify ENGINEER if feedpoint cannot be served at the location shown on the plans.

**1003-3.3 NAMEPLATES.** Provide nameplates for all feedpoint cabinets consisting of letters and/or numbers, printed on a thermosetting laminated plastic consisting of melamine or phenolic core and melamine surface.

Mount nameplates on the front of the feedpoint with a combination of stainless steel or aluminum rivets and 3M adhesive similar to Type EC-847.

Provide nameplates with a black background and white letters and/or numbers unless noted otherwise. Provide one 1½-inch X 6-inch nameplate (minimum length) and one 1½-inch X 3-inch nameplate (minimum length) for each new feedpoint to label the front of the enclosure. The feedpoint number shall be as designated in standard detail 1003-5.

Provide two 1/2-inch by 1½-inch nameplates (minimum) for the test switch. The switch options shall be marked as “Test” and “Auto” with two 1/2-inch by 1½-inch nameplate(minimum).

Provide one 1-inch by 1½-inch nameplate (minimum) for each lighting relay or contactor. Label relays as shown on standard detail 1003-1. Marker as a means of labeling will not be acceptable.

### **1003-4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107 and as follows:

#### **1003-4.1 PAD MOUNTED FEEDPOINT.**

Pad mounted feedpoint include the following:

- a. Feedpoint cabinet, lighting relays, load center, photocell, ground rods, and appurtenances as specified such that the feedpoint is complete and operational.
- b. Concrete foundation pad with reinforced concrete piers
- c. All conduit leading from the feedpoint to one foot beyond the edge of the concrete pad.
- d. Conduits and conductors to provide utility power to the feedpoint meter, including the meter, all connections and coordination with the utility company along with any fees to provide service to the feedpoint.

## SECTION 1003 – STREETLIGHTING FEEDPOINT

Measurement for payment shall be for each complete unit installed and ready for operation.

### **1003-4.2 POLE MOUNTED FEEDPOINT.**

Pole mounted feedpoints include the following:

- a. Feedpoint cabinet, lighting relays, load center, photocell, ground rods, and appurtenances as specified such that the feedpoint is complete and operational.
- b. Wood pole, mounting hardware and appurtenances to mount feedpoint cabinet, meter trim, and conduit.
- c. All conduit leading from the feedpoint to one foot beyond the edge of the concrete pad.
- d. Conduits and conductors to provide utility power to the feedpoint meter, including the meter, all connections and coordination with the utility company along with any fees to provide service to the feedpoint.

Measurement for payment shall be for each complete unit installed and ready for operation.

## **SECTION 1004 – STREETLIGHT UNITS**

### **1004-1 DESCRIPTION**

This work shall consist of the installation of streetlights, streetlight foundations and appurtenances in accordance with these specifications and standard details as shown on the plans or as directed by the ENGINEER.

### **1004-2 MATERIALS**

**1004-2.1 GENERAL.** Materials to be furnished by the CONTRACTOR shall be all materials required to install roadway streetlighting in place as shown on the plans complete and ready for operation.

All materials and equipment furnished shall be new and shall be approved by the Underwriter's Laboratories, Inc. as conforming to its standards in every case where such a standard has been established for the item in question.

It is the intent of the plans and specifications to comply in every respect to the requirements set forth by the National Electric Code, the North Dakota State Electrical Board, the local utility company, and the ordinances established by the CITY, and it shall be the responsibility of the CONTRACTOR to ensure that the above requirements are met in every respect. All electrical work outlined in this section shall be done under the supervision of a master electrician.

Should the plans or the specifications not meet these minimum established standards, either through omission of equipment, material, and method of installation, or by specification of material, equipment, or installation methods, the CONTRACTOR shall immediately notify the ENGINEER.

Approved equivalents for equipment and materials in this section will be considered annually. Submittals must be received on or before the first business day after December 1 to be considered for projects for the next year. Equivalency for any luminaire will be based on the following minimum requirements based on the type of fixture specified:

- a. Type III photometrics as defined by Illuminating Engineering Society (IES) per ANSI/IES RP-8-18 complete with IES files for each fixture.
- b. Specified lumen output, driver current and color temperature.
- c. Input watts not to exceed specifications.
- d. Fixture housing requirements including general appearance, and specified features.
- e. BUG rating.
- f. Surge protection per ANSI C136.2 with a surge rating of 20kV/10kA.
- g. UL listed or CSA Certified to UL Standards.
- h. 10-year manufacturer's warranty with supporting documentation.

## SECTION 1004– STREETLIGHT UNITS

All submittals must contain the following information:

- a. Digital IES files
- b. Full product specification detailing how the product meets the specifications per the standard specifications and details.
- c. Applicable structural test data for light standards.
- d. A minimum of three references on comparable installations.

Incomplete submittals will not be considered. Approved equivalents will be at the discretion of the ENGINEER and will be included in the project special provisions in advance of opening of bids.

The CONTRACTOR shall submit shop drawings or product data, in accordance with Section 104 for all items included in this section. Drawings or product data shall be marked with bid item designation and submitted within 30 days after contract award. No equipment shall be ordered until shop drawings and product data have been approved by the ENGINEER.

The CITY reserves the right to order additional light standards and/or luminaires along with the CONTRACTOR's shipment for the specific project for the following types of light units: BL, L, L1, C, C1 and DL1, as detailed in these specifications. Materials are to be billed to the CITY at the CONTRACTOR's invoice cost plus 15 percent; the CITY is exempt from paying sales tax. The CITY will be responsible for unloading and storing additional materials ordered by the CITY. The CONTRACTOR shall contact the CITY, by letter or email, prior to placing the order for light standards and luminaires. The CITY shall state quantities of additional materials, per item desired, in a letter or email addressed to the CONTRACTOR.

The CONTRACTOR shall keep one set of plans at the construction site as work is occurring to record any deviations from the plans and specifications including, but not limited to, relocated light units, feed points, junction boxes and changes in the cable location. This red-lined plan set shall be turned over to the CITY prior to the close of the project.

When the installation is complete and at such time as may be specified by the ENGINEER, the CONTRACTOR shall conduct an operating test for approval. The equipment shall be demonstrated to operate in accordance with the requirement of the specifications, the plans, and to the satisfaction of the ENGINEER. The CONTRACTOR shall furnish all instruments and personnel required for all tests. All test results shall be recorded. The CONTRACTOR shall be present during all tests and inspections unless so informed by the ENGINEER.

### **1004-2.2 TYPE BL STREETLIGHT UNIT**

- a. Type BL light standard, concrete having the following features:
  1. Precast, pre-stressed spun concrete, direct embedded, octagonal, tapered, 13' nominal mounting height.

## SECTION 1004– STREETLIGHT UNITS

2. 2 7/8-inch cast aluminum tenon
  3. Mix color and finish: Equivalent to Ameron color No.112-sky gray, or Stresscrete color salt & pepper with gloss acrylic graffiti-resistant coating.
  4. Handhole opening, placed at 180° to curb side, minimum 1 5/8"X9" opening (consistent through the depth of the pole wall) with cast aluminum frame and cover with stainless steel screws.
  5. Cable entrances, placed at 90° and 270° to curb side, minimum 1 5/8" X 8" (consistent through the depth of the pole wall).
  6. Grounding lead to bond the pole to the grounding system.
  7. Manufacturers and model number:
    - Ameron SEO04SPL
    - Stresscrete E16'4"-APO-G-S30-AG C/W 140(30/30)
    - Traditional Concrete, Inc. D413-SP-PA-3T
    - Other manufactures and models as approved by special provision.
- b. Type BL Luminaire, post top fixture having the following features:
1. Type and style of fixture to equal to Holophane, model PTUE3 series.
  2. Heavy grade cast aluminum, non-photocell type housing with tool-less access to electrical components, integral slip-fitter for 3-inch OD tenon for mounting to the pole having a total of 6 tenon set screws, black polyester powder coat finish to meet a 5000 hour salt spray test.
  3. High CRI LEDs with IES Type III photometrics with a semi cutoff distribution glass refractor, BUG rating not to exceed B3-U3-G3.
  4. Luminaire to operate LED's at 4000K with minimum lumen output of 7000 lumens, a maximum rated power of 60W, and a maximum driver current of 1075 mA.
  5. The fixture shall be L70 rated, have a full 10-year manufacturer's warranty with supporting documentation, and UL Listed or CSA Certified to UL Standards.
  6. Surge protection per ANSI C136.2 with a surge rating of 20kV/10kA.
  7. Manufacturer:
    - Holophane, model number per special provisions.
    - Other manufactures and models as approved by special provision.

### 1004-2.3 TYPE L STREETLIGHT UNIT

- a. Type L light standard, concrete having the following features:
  1. Precast, pre-stressed spun concrete, direct embedded, octagonal, tapered, 28-foot nominal mounting height.
  2. 6-foot galvanized steel mast arm with 4-bolt arm clamp with scroll assembly, Ameron Part No. C6ARMA.
  3. Mix color and finish: equivalent to Ameron color No.112-sky gray, or Stresscrete color salt & pepper with gloss acrylic graffiti-resistant coating.
  4. Bolt on cast aluminum top cap with two 3/8" X 1" cap screws.
  5. Handhole opening, placed at 180° to curb side, minimum 2" X 7" opening (consistent through the depth of the pole wall) with cast aluminum frame and cover with stainless steel screws.

## SECTION 1004– STREETLIGHT UNITS

6. Cable entrances, placed at 90° and 270° to curb side, minimum 2 1/4" X 9" (consistent through the depth of the pole wall).
  7. Grounding lead to bond the pole to the grounding system.
  8. Manufacturers and model number:
    - Ameron MEO-8.5-C6-Brace
    - Stresscrete E330-BPO-G-S30-AG C/W
    - Traditional Concrete, Inc. D128-SP-PA-FI
    - Other manufactures and models as approved by special provision.
- b. Type L Luminaire, mast arm mounted fixture having the following features:
1. Heavy grade diecast aluminum, non-photocell type housing with tool-less access to electrical components, bubble level, 2" slip-fitter for horizontal mounting and 3G vibration design, gray polyester powder coat finish to meet a 5000 hour salt spray test.
  2. High CRI LEDs with IES Type III photometrics, BUG rating not to exceed B2-U0-G2.
  3. Luminaire shall deliver a minimum of 11,000 lumens at 4000K with a maximum rated power of 90W, a maximum driver current of 1,000 mA, and a rated life of 100,000 hours. The light engine and assembly shall have a minimum IP65 rating.
  4. The fixture shall be L70 rated, have a full 10-year manufacturer's warranty with supporting documentation and UL Listed or CSA Certified to UL Standards.
  5. Surge protection per ANSI C136.2 with a surge rating of 20kV/10kA.
  6. Manufacturer:
    - American Electric Lighting or GE Current, model numbers per special provision.
    - Other manufacturers and models as approved by special provision.

### 1004-2.4 TYPE L1 STREETLIGHT UNIT

- a. Type L1 light standard, concrete having the following features:
1. Precast, pre-stressed spun concrete, direct embedded, octagonal, tapered, 28-foot nominal mounting height.
  2. 6-foot galvanized steel mast arm with 4-bolt arm clamp with scroll assembly brace, Ameron Part No. C6ARMA.
  3. Mix color and finish: equivalent to Ameron color No.112-sky gray, or Stresscrete color salt & pepper with gloss acrylic graffiti-resistant coating.
  4. Bolt on cast aluminum top cap with two 3/8" X 1" cap screws.
  5. Handhole opening, placed at 180° to curb side, minimum 2" X 7" opening (consistent through the depth of the pole wall) with cast aluminum frame and cover with stainless steel screws.
  6. Cable entrances, placed at 90° and 270° to curb side, minimum 2 1/4" X 9" (consistent through the depth of the pole wall).
  7. Grounding lead to bond the pole to the grounding system.
  8. Manufacturers and model number:
    - Ameron MEO-8.5-C6-Brace

## SECTION 1004– STREETLIGHT UNITS

Stresscrete E330-BPO-G-S30-AG C/W  
Traditional Concrete, Inc. D128-SP-PA-FI  
Other manufactures and models as approved by special provision

- b. Type L1 Luminaire, mast arm mounted fixture having the following features:
1. Heavy grade diecast aluminum, non-photocell type housing with tool-less access to electrical components, bubble level, 2" slip-fitter for horizontal mounting and 3G vibration design, gray polyester powder coat finish to meet a 5000 hour salt spray test.
  2. High CRI LEDs with IES Type III photometrics, BUG rating not to exceed B3-U0-G3.
  3. Luminaire shall deliver a minimum of 18,000 lumens at 4000K with a maximum rated power of 130W, a maximum driver current of 1,000 mA, and a rated life of 100,000 hours. The light engine and assembly shall have a minimum IP65 rating.
  4. The fixture shall be L70 rated, have a full 10-year manufacturer's warranty with supporting documentation and UL Listed or CSA Certified to UL Standards.
  5. Surge protection per ANSI C136.2 with a surge rating of 20kV/10kA.
  6. Manufacturer:  
American Electric Lighting or GE Current, model numbers per special provision.  
Other manufactures and models as approved by special provision.

### 1004-2.5 TYPE DL1 STREETLIGHT UNIT

- a. Type DL1 light standards, concrete having the following features:
1. Precast, pre-stressed spun concrete, direct embedded, octagonal, tapered, 19.5' nominal mounting height.
  2. 2 7/8-inch cast aluminum tenon
  3. Mix color and finish: Equivalent to Ameron color No. 6P3A, or Traditional Concrete Eclipse Black with gloss acrylic graffiti-resistant coating.
  4. Handhole opening, placed at 180° to curb side, minimum 2" X 7" opening (consistent through the depth of the pole wall) with cast aluminum frame and cover with stainless steel screws.
  5. Cable entrances, placed at 90° and 270° to curb side, minimum 2" X 9" (consistent through the depth of the pole wall).
  6. Grounding lead to bond the pole to the grounding system.
  7. Manufacturers and model number:  
Ameron MEO06  
Stresscrete E23'10"-BPO-G-E11-AG C/W 140(30/30)  
Traditional Concrete, Inc. D120-EB-EA-3T  
Other manufactures and models as approved by special provision.
- b. Type DL1 luminaires, post top mounted having the following features:
1. Type and style of fixture to equal to Holophane, model WAE3 STS series complete with ornate trim including spike finial, bands, ribs and medallions,

## SECTION 1004– STREETLIGHT UNITS

2. Heavy grade cast aluminum, non-photocell type housing with tool-less access to electrical components, integral slip-fitter for 3-inch OD tenon for mounting to the pole, black polyester powder coat finish to meet a 5000 hour salt spray test.
3. High CRI LEDs with IES Type III photometrics with a semi cutoff distribution glass refractor, BUG rating not to exceed B3-U5-G5.
4. Luminaire to operate LED's at 4000K with a minimum lumen output of 13,300 lumens, a maximum rated power of 95W, and a maximum driver current of 525 mA.
5. The fixture shall be L70 rated, have a full 10-year manufacturer's warranty with supporting documentation and UL Listed or CSA Certified to UL Standards.
6. Surge protection per ANSI C136.2 with a surge rating of 20kV/10kA.
7. Manufacturer:
  - Holophane-Washington Postlite Series, model number per special provision.
  - Other manufactures and models as approved by special provision.

### 1004-2.6 TYPE CL STREETLIGHT UNIT

- a. Type CL light standards, galvanized steel having the following features:
  1. 40' nominal mounting height, davit type pole with a 6' mast arm and aluminum transformer base.
  2. The pole shaft, a one-piece assembly, conforming to ASTM A572 Grade 55 and davit arm conforming to ASTM A595 Grade A.
  3. Anchor bolts conforming to ASTM F1554 Grade 55. Bolts have an L bend on one end and are galvanized a minimum of 12" on the threaded end.
  4. Aluminum transformer base, nominal height 17", complete with connecting bolts, flat washers, bearing washers and hex nuts. Access door minimum 8.5" X 11". As manufactured by Akron Foundry or Valmont, type TB1-17 or approved equivalent.
  5. Reinforced handhole opening and cover, placed at 180° to curb side, minimum 4" X 6.5" and 18" above grade. A grounding lug to be provided inside handhole.
  6. Manufacturers and model number:
    - Millerbernd Manufacturing, RLDB6-400ND
    - Valmont Industries, Inc. DS90 RTS
    - Other manufactures and models as approved by special provision.
- b. Type CL Luminaire, mast arm mounted fixture having the following features:
  1. Heavy grade diecast aluminum, non-photocell type housing with tool-less access to electrical components, bubble level, 2" slip-fitter for horizontal mounting and 3G vibration design, gray polyester powder coat finish to meet a 5000 hour salt spray test.
  2. High CRI LEDs with IES Type III photometrics, BUG rating not to exceed B3-U0-G3.

## SECTION 1004– STREETLIGHT UNITS

3. Luminaire shall deliver a minimum of 18,000 lumens at 4000K with maximum rated power of 130W, a maximum driver current of 1,000 mA, and a rated life of 100,000 hours. The light engine and assembly shall have a minimum IP65 rating.
4. The fixture shall be L70 rated, have a full 10-year manufacturer's warranty with supporting documentation and UL Listed or CSA Certified to UL Standards.
5. Surge protection per ANSI C136.2 with a surge rating of 20kV/10kA.
6. Manufacturer:
  - American Electric Lighting or GE Current, model numbers per special provision.
  - Other manufactures and models as approved by special provision.

### 1004-2.7 TYPE CL1 STREETLIGHT UNIT

- a. Type CL1 light standards, galvanized steel having the following features:
  1. 40' nominal mounting height, davit type pole with a 6' mast arm and aluminum transformer base.
  2. The pole shaft, a one-piece assembly, conforming to ASTM A572 Grade 55 and davit arm conforming to ASTM A595 Grade A.
  3. Anchor bolts conforming to ASTM F1554 Grade 55. Bolts have an L bend on one end and are galvanized a minimum of 12" on the threaded end.
  4. Aluminum transformer base, nominal height 17", complete with connecting bolts, flat washers, bearing washers and hex nuts. Access door minimum 8.5" X 11". As manufactured by Akron Foundry or Valmont, type TB1-17 or approved equivalent.
  5. Reinforced handhole opening and cover, placed at 180° to curb side, minimum 4" X 6.5" and 18" above grade. A grounding lug to be provided inside handhole.
  6. Manufacturers and model number:
    - Millerbernd Manufacturing, RLDB6-400ND
    - Valmont Industries, Inc. DS90 RTS
    - Other manufactures and models as approved by special provision.
- b. Type CL1 Luminaire, mast arm mounted fixture having the following features:
  1. Heavy grade diecast aluminum, non-photocell type housing with tool-less access to electrical components, bubble level, 4-bolt. 2" slip-fitter for horizontal mounting and 3G vibration design, gray polyester powder coat finish to meet a 5000 hour salt spray test.
  2. High CRI LEDs with IES Type III photometrics, BUG rating not to exceed B3-U0-G4.
  3. Luminaire shall deliver a minimum of 27,000 lumens at 4000K with maximum rated power of 200W, a maximum driver current of 1,100 mA, and a rated life of 100,000 hours. The light engine and assembly shall have a minimum IP65 rating.

## SECTION 1004– STREETLIGHT UNITS

4. The fixture shall be L70 rated, have a full 10-year manufacturer's warranty with supporting documentation and UL Listed or CSA Certified to UL Standards.
5. Surge protection per ANSI C136.2 with a surge rating of 20kV/10kA.
6. Manufacturer:
  - American Electric Lighting or GE Current, model numbers per special provision.
  - Other manufactures and models as approved by special provision.

**1004-2.8 WIRING SPLICE CONNECTORS AT LIGHT UNIT.** Splice connectors at pole handhole shall be ILSCO PBTS with 3/16 min. hex size, or approved equivalent.

**1004-2.9 IN-LINE FUSE AND FUSE HOLDER.** The fuse holder shall be type FEB, Ferraz Shawmut, rated for 600Vac and 30 amps or approved equivalent. The fuse shall be a fast-acting midget fuse with an interrupt rating of 10kA at 600Vac, 5 amp as manufactured by Bussmann, Littelfuse or equivalent.

### 1004-3 CONSTRUCTION REQUIREMENTS

**1004-3.1 STREETLIGHT STANDARD – GENERAL REQUIREMENTS.** Streetlight standards shall be set as shown on the plans. Install 1/2-inch by 10-foot ground rod at each streetlight. All streetlight standards shall be grounded. Bond ground conductor, streetlight standard, and ground rod.

Pole wiring shall be No. 10 AWG stranded copper, Type THHN/THWN 600-volt cable, three conductors minimum (power, neutral, and ground), and shall be continuous from the luminaire to the fuse holder in the light standard base. Wire nuts shall not be permitted.

Fuse each luminaire in the base of the lighting standard at the handhole. Tape fuse kits with a 1/2-inch lapped layer for a distance of 1½ inches on each side of joint with conductor. Fuse holders to be complete with proper fuse to protect luminaire. The neutral conductor shall be solidly connected and unfused throughout system.

The fuse holder shall be supported by the conductors at the level of the hand hole. Sufficient excess conductor length shall be provided to permit withdrawal of the fuse holder through the hand hole a minimum of 6 inches outside of the hand hole for purposes of installation and inspection.

All luminaires shall be leveled after the pole is standing or in place, ready for operation. For fixtures with mast arms, mast arms to be oriented perpendicular to the face of the curb unless otherwise noted. For post top mounted streetlight units, the fixture shall be orientated so the optics are perpendicular to the face of the curb unless otherwise noted.

**1004-3.2 STREETLIGHT UNITS - DIRECT EMBEDDED (TYPES, BL, L, L1 and DL1).** A concrete-bearing base pad, 6 inches thick and a minimum 16 inches diameter, shall

## SECTION 1004– STREETLIGHT UNITS

be provided under the bottom of the pole as shown in the standard detail. Provide roofing tar paper around poles between pole and concrete pad. In sidewalks, provide 3/4-inch expansion joint around concrete pad between concrete pad and sidewalk.

A concrete housekeeping pad of dimensions shown in the standard detail shall be constructed around the base of the direct buried concrete standard.

The concrete to be used in the construction of the concrete housekeeping pads and bearing base pads shall be a minimum of 4,000 psi strength at 28 days with a minimum of six bags of cement per cubic yard of concrete and shall conform in all respects to the City of Bismarck Specifications, Section 600 for Sidewalks, Driveways, Curb, and Combined Curb and Gutter.

**1004-3.3 STREETLIGHT UNITS WITH CONCRETE FOUNDATIONS (TYPES CL and CL1).** Concrete foundations shall be installed as per standard detail. Foundations shall be completed with anchor bolts, rebar, and conduit stub-in. Anchor bolt spacing to accommodate poles shall be verified in the field prior to construction.

The concrete to be used in the construction of the concrete foundations shall be a minimum of 4,000 psi strength at 28 days with a minimum of six bags of cement per cubic yard of concrete and shall conform in all respects to the City of Bismarck Specifications, Section 600 for Sidewalks, Driveways, Curb, and Combined Curb and Gutter.

The CONTRACTOR shall notify the ENGINEER at least 24 hours prior to pouring a concrete foundation such that the form with the anchor bolt placement, rebar, conduit stub-ins, and ground rod can be inspected. The CONTRACTOR shall provide concrete tests in conformance with City of Bismarck Specifications, a minimum of one test per day or a minimum of one test per truckload of concrete or as directed by the ENGINEER.

**1004-3.4 REMOVE STREETLIGHT STANDARD.** The standard shall be removed from the site shown on the plans, salvaged, transported, and stored (by blocking and supporting at three points) in the CITY storage yard located at the Municipal Solid Waste Facility on North 52nd Street. Where plans indicate that the light unit shall not be salvage, the CONTRACTOR will be responsible to dispose of the light unit.

The luminaire wiring within the pole shall be disconnected at the fuse. The luminaire shall be removed from the mast arm, salvaged, and delivered to CITY storage at 601 South 26th Street.

Where the plans call for salvaging the conductors and re-splicing the underground conductors, the standards shall be removed carefully to prevent damage to the conductors. Splices shall be made as detailed in these specifications.

## SECTION 1004– STREETLIGHT UNITS

The hole where the standard was removed shall be filled with earth supplied by the CONTRACTOR and tamped to the density of the surrounding soil. The surface shall be returned to that of the adjoining area.

**1004-3.5 RELOCATE STREETLIGHT STANDARD.** This item shall consist of removing a light unit from its present location and reinstalling at either the same location or a new location as shown on the plans including reconnecting to the new or existing streetlight system conductors as indicated in the plans.

The standard shall be removed, salvaged, transported, and stored (by blocking and supporting at three points) in the CITY storage yard located at the Municipal Solid Waste Facility on North 52nd Street or at a location approved by the ENGINEER. The CONTRACTOR shall take care in the removal, relocation and storage of the light standard to prevent damage to the standard or luminaire. Any damage that occurs to the light as part of the relocation will be the responsibility of the CONTRACTOR.

Where the plan calls for relocating the pole, the CONTRACTOR shall fill the existing hole with earth supplied by the CONTRACTOR and tamped to a density of the surrounding soil. The surface shall be returned to that of the adjoining area.

### **1004-4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107 and as follows:

#### **1004-4.1 STREETLIGHT UNIT.**

Type BL and DL1 consists of:

- a. Designated LED luminaire.
- b. Concrete direct buried poles.
- c. Wiring and connections to underground circuits.
- d. Ground rod with connection.
- e. Fuse holder, fuses and internal wiring.
- f. Concrete housekeeping pads and concrete-bearing base pads.
- g. Unit set in place, ready for operation.

Type L and L1 consists of:

- a. Designated LED luminaire.
- b. Concrete direct buried poles with bracket (mast arm).
- c. Wiring and connections to underground circuits.
- d. Ground rod with connection.
- e. Fuse holder, fuses and internal wiring.
- f. Concrete housekeeping pads and concrete-bearing base pads.
- g. Unit set in place, ready for operation.

Type CL and CL1 consist of:

- a. Designated LED luminaire.

## SECTION 1004– STREETLIGHT UNITS

- b. Galvanized steel, davit type anchor base pole with mast arm.
- c. Wiring and connections to underground circuits.
- d. Fuse holder, fuses and internal wiring.
- e. Reinforced concrete base, anchor bolts, anchor bolt covers, ground rod, and conduit.
- f. Unit set in place and ready for operation.

Measurement for payment shall be for each complete unit installed and ready for operation.

**1004-4.2 REMOVE STREETLIGHT STANDARD.** This item shall consist of removal, transport, storage or disposal of streetlight standards and restoration of the ground to that of the surrounding area.

**1004-4.3 RELOCATE STREETLIGHT STANDARD.** This item shall consist of removal, transport, storage, relocating/resetting and reconnecting conductors as required. Where plans call for the relocation of a type CL or CL1 streetlight unit, the cost of the concrete foundation will be paid under Streetlight Base.

Measurement for payment shall be for each streetlight standard removed, stored, relocated, reconnected and accepted by the ENGINEER.

**1004-4.4 STREETLIGHT BASE.** This item consists of constructing concrete base per specification and standard details for type CL or CL1 streetlight units.

## DIVISION 1200

### MISCELLANEOUS CONSTRUCTION

#### SECTION 1201 – TOPSOIL

##### 1201-1 DESCRIPTION

This item shall consist of preparing the ground surface for topsoil application, removing topsoil from designated stockpiles or areas to be stripped on the site or from approved sources off the site, and placing and spreading the topsoil on prepared areas in accordance with this specification at the locations shown on the plans as directed by the ENGINEER.

##### 1201-2 MATERIALS

**1201-2.1 TOPSOIL.** Topsoil shall be the surface layer of soil with no admixture of refuse or any material toxic to plant growth, and it shall be reasonably free from subsoil and stumps, roots, brush, stones (2 inches or more in diameter), clay lumps, or similar objects. Brush and other vegetation which will not be incorporated with the soil during handling operations shall be cut and removed. Ordinary sods and herbaceous growth such as grass and weeds are not to be removed but shall be thoroughly broken up and intermixed with the soil during handling operations. The topsoil or soil mixture, unless otherwise specified or approved, shall have a pH range of approximately 5.5 pH to 7.6 pH, when tested in accordance with the methods of testing of the Association of Official Agricultural Chemists in effect on the date of invitation of bids. The organic content shall be not less than 3 percent nor more than 20 percent as determined by the wet-combustion method (Chromic acid reduction). There shall be not less than 20 percent nor more than 80 percent of the material passing the 200 mesh sieve as determined by the wash test in accordance with ASTM D1140.

Natural topsoil may be amended by the CONTRACTOR with approved materials and methods to meet the above specifications.

**1201-2.2 INSPECTION AND TESTS.** When topsoil is to be imported, the ENGINEER shall be notified of the source of topsoil, a minimum of 10 days prior to installation, to be furnished by the CONTRACTOR. The topsoil shall be inspected to determine if the selected soil meets the requirements specified and to determine the depth to which stripping will be permitted. At this time, the CONTRACTOR may be required to take representative soil samples from several locations within the area under consideration and to the proposed stripping depths, for testing purposes as specified in Section 1201-2.1.

### 1201-3 CONSTRUCTION REQUIREMENTS

**1201-3.1 GENERAL.** Areas to be topsoiled shall be shown on the plans. If topsoil is available on the site, the location of the stockpiles or areas to be stripped of topsoil and the stripping depths shall be shown on the plans.

Suitable equipment necessary for proper preparation and treatment of the ground surface, stripping of topsoil, and for the handling and placing of all required materials shall be on hand, in good condition, and approved by the ENGINEER before the various operations are started.

**1201-3.2 PREPARING THE GROUND SURFACE.** Immediately prior to dumping and spreading the topsoil on any area, the surface shall be loosened by disks or spike-tooth harrows, or by other means approved by the ENGINEER, to a minimum depth of 2 inches to facilitate bonding of the topsoil to the covered subgrade soil. Unless otherwise approved by the ENGINEER, the surface of the area to be topsoiled shall be cleared of all stones larger than 2 inches in diameter. All litter or other material which may be detrimental to proper bonding shall be removed.

Grades on the area to be topsoiled, when established by others as per plans, shall be maintained in a true and even condition. Where grades have not been established, the areas shall be smooth-graded and the surface left at the prescribed grades in an even and properly compacted condition to prevent, insofar as practical, the formation of low places or where water will stand.

**1201-3.3 OBTAINING TOPSOIL.** Prior to the stripping of topsoil from designated areas, any vegetation, briars, stumps and large roots, rubbish, or stones found on such areas, which may interfere with subsequent operations, shall be removed using methods approved by the ENGINEER. Heavy sod or other cover, which cannot be incorporated into the topsoil by disking or other means, shall be removed.

When suitable topsoil is available on the site, the CONTRACTOR shall remove this material from the designated areas and to the depth as directed by the ENGINEER. The topsoil shall be spread on areas already tilled and smooth graded, or stockpiled in areas approved by the ENGINEER. Any topsoil stockpiled by the CONTRACTOR shall be rehandled and placed without additional compensation. Any topsoil that has been stockpiled on the site by others, and is required for topsoiling purposes, shall be removed and placed by the CONTRACTOR. The sites of all stockpiles and areas adjacent thereto, which have been disturbed by the CONTRACTOR, shall be graded if required and put into a condition acceptable for seeding.

When suitable topsoil is secured off the project site, the CONTRACTOR shall locate and obtain the supply, subject to the approval of the ENGINEER. The CONTRACTOR shall notify the ENGINEER sufficiently in advance of operations in order that necessary measurements and tests can be made. The CONTRACTOR shall remove the topsoil from approved areas and to the depth as directed. The topsoil shall be hauled to the site of the work and placed for spreading or spread as required. Any topsoil hauled to

## SECTION 1201 – TOPSOIL

the site of the work and stockpiled shall be rehandled and placed without additional compensation.

**1201-3.4 PLACING TOPSOIL.** The topsoil shall be evenly spread on the prepared areas to a uniform depth of 4 inches after compaction unless otherwise shown on the plans or stated in the special provisions. Spreading shall not be done when the ground or topsoil is frozen, excessively wet, or otherwise in a condition detrimental to the work. Spreading shall be carried on so that turving operations can proceed with a minimum of soil preparation or tilling.

After spreading, any large, stiff clods and hard lumps shall be broken with a pulverizer or by other effective means. All roots, litter, foreign matter, and stones or rocks 2 inches or more in diameter, unless otherwise approved by ENGINEER, shall be removed and disposed of by the CONTRACTOR. After spreading is completed, the topsoil shall be satisfactorily compacted by rolling with a cultipacker or by other means approved by the ENGINEER. The compacted topsoil surface shall conform to the required lines, grades, and cross sections. Any topsoil or other dirt falling upon pavements as a result of hauling or handling of topsoil shall be promptly removed.

When placing topsoil in pasture, agricultural or similar land use areas, final restored topsoil conditions shall be similar or equal to condition prior to disturbance or to adjacent undisturbed land as determined by ENGINEER. These conditions shall include, but are not limited to, rock size and frequency, roots, weeds, grade and roughness of area.

### **1201-4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107 and as follows:

**1201-4.1 TOPSOIL.** When topsoil is weighed for final quantity, it shall be converted to cubic yards at the rate of 1.3 tons per cubic yard or at a rate approved by the ENGINEER.

## SECTION 1202 – SEEDING

### 1202-1 DESCRIPTION

This item shall consist of seeding the areas shown on the plans or as directed by the ENGINEER in accordance with these specifications.

### 1202-2 MATERIALS

**1202-2.1 SEED.** All seed shall be of certified class quantity and shall be certified by the state in which the seed variety was grown. All seed containers must be sealed and labeled to comply with existing North Dakota Seed Laws and Regulations or in accordance with U.S. Department of Agriculture Rules and Regulations under the Federal Seed Act, if shipped in Interstate Commerce. Seed shall be furnished separately or in mixtures in standard containers with the seed name including variety and species, lot numbers net weight, and percentages of maximum weed seed content clearly marked for each kind of seed. The CONTRACTOR shall furnish the ENGINEER duplicate signed copies of a statement by the vendor certifying that each lot of seed has been tested by a recognized laboratory for seed testing within nine months of date of delivery. Seed not planted within the nine month period shall be retested for dormant seed, hard seed, and germination, and a new certified test report furnished. This statement shall include: Name and address of laboratory, date of test, lot number for each kind of seed, and the results of tests as to name, percentages of purity and of germination, and percentage of weed content for each kind of seed furnished and, in case of a mixture, the proportions of each kind of seed. The minimum acceptable purity, germination, weed seed, and other crop seed are those of certified class seed.

Seed which has become wet, moldy, or otherwise damaged in transit or in storage will not be acceptable.

Alternate seed mixes will be considered by the Engineer. Contractor shall submit alternate mixes for approval prior to installation.

Seed mixture shall contain not less than 85 percent pure live seed (PLS) and shall be uniformly mixed by weight as per the following:

#### CLASS I

Use: Pasture or Hay land, fairly level surface

Application Rate: 10 PLS/acre

Seed	% by Weight
Pubescent Wheatgrass	40
Hycrest Crested Wheatgrass	40
Intermediate Wheatgrass	20

## SECTION 1202 – SEEDING

### CLASS II

Use: Boulevards and other areas requiring salt resistance or high drought tolerance

Application Rate: 6 PLS/1000 sf

Seed	% by Weight
Fairway Crested	50
Sheep Fescue	30
Perennial Ryegrass	20

### CLASS IIB

Use: Restoration of established lawns with irrigation requiring less salt resistance

Application Rate: 6 PLS/1000 sf

Seed	% by Weight
Fairway Crested	60
Creeping Red Fescue	10
Fineleaf Perennial Ryegrass*	30

\*For quick establishment, replace a portion of perennial with annual, consult supplier and submit to Engineer for approval prior to installation.

### CLASS III

Use: Ditches and side slopes

Application Rate: 2.5 PLS/1000sf

Seed	% by Weight
Fairway Crested	30
Sheep Fescue	30
Perennial Ryegrass	40

### CLASS IV

Use: Natural and/or Native Grass Areas

Application Rate: 15 PLS/1 acre if broadcast seeding

10 PLS/acre if drilled

Seed	% by Weight
Canada Wildrye	30
Western Wheatgrass	20
Northern Wheatgrass	20
Green Needle	6.5
Sideoats	6.5
Little Bluestem	5
Slender Wheatgrass	5
Switchgrass	5
Blue Grama	2

## SECTION 1202 – SEEDING

### CLASS V

Use: Critical, Saline Area  
Application Rate: 25 lbs/acre  
Note: Additional requirements below

Seed	% by Weight
Tall Wheat Grass	40
Western Wheatgrass	35
Slender Wheatgrass	15
Canada Wildrye	10

### CLASS VI

As specified on the plans or in the special provisions

When Class V seed mixture is specified, it shall be sown at the rate of 25 pounds per acre; 40 to 60 pounds of phosphorus and 20 to 30 pounds of actual nitrogen per acre shall be mixed into the upper three inches of the soil or spread on the soil prior to seeding or by means of fertilizer attachment on the drill. Fertilizer shall not be mixed with the seed.

When Class I, III, IV, or V seed mixture is specified and seeding is performed between August 20 and September 20, or when dormant seeding in late fall, 30 pounds of oats or rye seed per acre shall be added to the mixture as a nurse crop. This nurse crop shall be mowed before it reaches six inches in height.

If seed with the specified percentage of pure live seed cannot be obtained, additional seed may be used to bring the amount of live seed up to the amount specified. Seed and seeding mixtures shall be free of all prohibited noxious weed seed and shall not contain more than .5 percent by weight of restricted noxious weed seeds. Prohibited and restricted noxious weeds shall be those as classified by the State Seed Department.

**1202-2.2 TOPSOIL.** Topsoil shall conform to Section 1201.

**1202-2.3 LIME.** Lime, if specified, shall be ground limestone containing not less than 85 percent of total carbonates, and shall be ground to such fineness that 90 percent will pass through a No. 20 mesh sieve and 50 percent will pass through a No. 100 mesh sieve. Coarser material will be acceptable, providing the rates of application are increased to provide not less than the minimum quantities and depth specified by an approved testing laboratory based on the sieve requirements above. Dolomitic lime or high magnesium lime shall contain at least 10 percent of magnesium oxide.

**1202-2.4 FERTILIZER.** Fertilizer, if specified, shall be standard commercial fertilizers supplied separately or in mixtures containing the percentages of total nitrogen, available phosphoric acid, and water soluble potash. They shall be applied at the rate and to the

## SECTION 1202 – SEEDING

depth specified and shall meet the specified requirements of the applicable state and federal laws. They shall be furnished in standard containers with name, weight, and guaranteed analysis of contents clearly marked thereon. No cyanamide compounds of hydrated lime shall be permitted in mixed fertilizers.

The fertilizers may be supplied prior to seeding in one of the following forms:

- a. A dry, free-flowing fertilizer suitable for application by a common fertilizer spreader;
- b. A finely ground fertilizer soluble in water, suitable for application by power sprayers; or
- c. A granular or pellet-form suitable for application by blower equipment.
  1. Fertilizer shall not be applied after seeding.
  2. The fertilizer shall not be mixed with the seed, but it may be applied at the same time as the seed if a suitable fertilizer attachment on the equipment is used.
  3. The fertilizer may be mixed into the hydro mulch mixture as it is applied.

**1202-2.5 SOIL FOR REPAIRS.** The soil for fill and topsoil of areas to be repaired shall be at least of equal quantity to that which exists in areas adjacent to the area to be repaired. The soil shall be relatively free from large stones, roots, stumps, or other materials that will interfere with subsequent sowing of seed, compacting, and establishing turf, and shall be approved by the ENGINEER before being placed.

**1202-2.6 RESEEDING AND REPAIR.** Damage caused from wind or water erosion, CONTRACTOR's operation, or traffic, which can be repaired with equipment normally used for seeding work, shall be repaired at the CONTRACTOR's expense. The CONTRACTOR shall make any repairs as directed by the ENGINEER prior to final acceptance.

### 1202-3 CONSTRUCTION REQUIREMENTS

**1202-3.1 SEEDING DATES.** Seeding shall be done at such times of the year when the climatic conditions of temperature and moisture are most adaptable for growth and work of this nature. It is preferred that seeding shall be accomplished before May 20 and after October 20 of each year. Plant after October 20 when there is no chance of fall germination as dormant seedings are made for spring germination. Also plant early enough in fall to allow at least 40 days for seedlings to develop before they go dormant in the fall, preferably before September 10. Planting between May 20 and September 10 will be allowed if adequate moisture can be provided.

**1202-3.2 SEEDBED PREPARATION.** The areas to be seeded shall be cleared of all debris, rank vegetation, and other material that is detrimental to the preparation of a seed bed. The areas thus cleared shall be shaped or bladed by approved equipment to the plan's cross section or to such cross section that best fits the existing conditions. The areas thus prepared shall be disked, harrowed, raked, or worked by some other approved method, into a reasonably smooth, even seed bed. The surface of the

## SECTION 1202 – SEEDING

prepared seed bed shall be firm enough so that adult footprints are hardly visible and will limit seeding depth to a maximum of 3/4 of an inch. If rolling is necessary to secure this, it shall be done prior to the seeding and with an approved roller, the weight of which shall be dependent upon the particular soil conditions.

All slopes shall be worked on the contour, or as directed by the ENGINEER.

Fertilizer and/or lime, when specified, shall be spread and worked into the soil during the final preparation of the seed bed.

The CONTRACTOR shall take four representative and suitably sized samples of the soils which are to form the seed bed and shall submit these samples to an approved testing laboratory for analysis and recommendation of fertilizer to be used. Sampling and testing shall be done with sufficient promptness as to avoid delaying the work. Test results shall be submitted to the ENGINEER.

**1202-3.3 SEED APPLICATION.** Seed shall be sown by means of a force feed drill with a grass seed attachment which provides a uniform flow and depth of seed placement (1/4 to 1/2 inch), except that on slopes steeper than three to one or on areas too small to be seeded with a force feed drill, seed may be sown by power sprayers, blowers, or other approved methods. Grass drills shall be calibrated to ensure proper seeding rates (pure live seed rate divided by purity and germination percentages) for calibrating the drill. The soil shall be repacked immediately after the seed is applied to firm the soil around the seed. All equipment shall be in good working order and shall be approved by the ENGINEER.

Kentucky Bluegrass shall be seeded a very shallow depth or on the surface and cultipacked.

No seed shall be sown during winds that are strong enough to prevent it from being properly imbedded into the surface.

No seed shall be sown in standing water or frozen ground.

When specified, mulching shall be applied immediately or within 24 hours after seed application in accordance with Section 1204.

**1202-3.4 ESTABLISHING GRASS STAND.** The seeded area shall be kept moist until it has germinated and its continued growth assured. In all cases, watering shall be done in a manner which will avoid erosion from the application of excessive quantities and will avoid damage to the finished surface. Water will be considered incidental to the item "Seed."

All seeded areas shall be protected against traffic or other use by warning signs or barricades approved by the ENGINEER.

## SECTION 1202 – SEEDING

Additional watering during dry periods and mowing of seeded areas shall be performed until the stand is firmly established. Weeds or other undesirable vegetation shall be rotary mowed above the new grass seedlings before they reach a height of six inches, and the clippings shall be raked and removed from the area.

Broadleaf weeds shall be controlled by rotary mowing or by applying a post emergence herbicide in accordance with North Dakota State University Weed Control Guide and manufacturer's recommendations after majority of grass plants have three leaves or more and weeds reach a four inch height.

**1202-3.5 GRASS STAND ACCEPTANCE.** To determine adequacy of stands and to determine if reseeding or reinforcement seeding is required, the stand shall be evaluated by the ENGINEER and shall meet the following requirements before the grass stand is accepted: Seedling emergence shall be uniform over the entire area. Stand counts shall indicate a density of at least 20 to 30 seedlings per square foot of area. Twenty seedlings per square foot for rhizomatous-type species and 30 for a bunch-type or a mixture of bunch-type and rhizomatous-type.

The CONTRACTOR shall furnish and replace without compensation therefor, any seed for areas that have not germinated, have died, or are damaged to the extent that replacement is required to conform to the requirements outlined above. The contract warranty period shall also apply to this item.

**1202-3.6 GRASS MAINTENANCE.** The intent of this specification is to provide for maintenance of the new growth of grass beyond the date of grass stand acceptance. During the maintenance period, which is from the date of the grass stand acceptance to the date of acceptance of the contract for final payment, the grass stand shall be mowed, watered, fertilized, and/or protected from damage by erosion, traffic, or weeds in order to maintain a healthy regrowth of grass in the seeded area. This maintenance shall be paid for under a separate bid item from the seeding.

### **1202-4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107.

## **SECTION 1203 – SODDING**

### **1203-1 DESCRIPTION**

This item shall consist of furnishing, hauling, and placing approved live sod on prepared areas in accordance with this specification at the locations shown on the plans or as directed by the ENGINEER.

### **1203-2 MATERIALS**

**1203-2.1 SOD.** Sod furnished by the CONTRACTOR shall have a good cover of living or growing grass. This shall be interpreted to include grass that is seasonally dormant during the cold or dry seasons and capable of renewing growth after the dormant period. All sod shall be obtained from where the soil is reasonably fertile and contains a high percentage of loamy topsoil. Sod shall be cut or stripped from living, thickly matted turf relatively free of weeds or other undesirable foreign plants, large stones, roots, or other materials which might be detrimental to the development of the sod or to future maintenance. At least 70 percent of the plants in the cut sod shall be composed of the species stated in the special provisions, and any vegetation more than 6 inches in height shall be mowed to a height of 3 inches or less before sod is lifted. Sod, including the soil containing the roots and the plant growth shown above, shall be cut uniformly to a thickness not less than that stated in the special provisions.

**1203-2.2 LIME.** Lime, if specified, shall conform to the requirements of Section 1202.

**1203-2.3 FERTILIZER.** Fertilizer, if specified, shall conform to the requirements of Section 1202.

**1203-2.4 WATER.** The water shall be sufficiently free from oil, acid, alkali, salt, or other harmful materials that would inhibit the growth of grass. It shall be subject to the approval of the ENGINEER prior to use.

**1203-2.5 SOIL FOR REPAIRS.** The soil for fill and topsoiling of areas to be repaired shall conform to the requirements of Section 1202.

### **1203-3 CONSTRUCTION REQUIREMENTS**

**1203-3.1 GENERAL.** Areas to be solid, strip, or spot sodded shall be shown on the plans. Areas requiring special ground surface preparation such as tilling and those areas in a satisfactory condition which are to remain undisturbed shall also be shown on the plans.

Suitable equipment necessary for proper preparation of the ground surface and for the handling and placing of all required materials shall be on hand, in good condition, and

## SECTION 1203 – SODDING

shall be approved by the ENGINEER before the various operations. The CONTRACTOR shall demonstrate to the ENGINEER before starting the various operations that the application of required materials will be made at the specified rates.

**1203-3.2 PREPARING THE GROUND SURFACE.** After grading of areas has been completed and before applying fertilizer and limestone, areas to be sodded shall be raked or otherwise cleared of stones larger than 2 inches in any diameter, sticks, stumps, and other debris which might interfere with sodding, growth of grasses, or subsequent maintenance of grass covered areas. If any damage by erosion or other cause occurs after grading of areas and before beginning the application of fertilizer and ground limestone, the CONTRACTOR shall repair such damage. This may include filling gullies, smoothing irregularities, and repairing other incidental damage.

**1203-3.3 APPLYING FERTILIZER AND GROUND LIMESTONE.** Following ground surface preparation, fertilizer shall be uniformly spread at a rate which will provide not less than the minimum quantity of each fertilizer ingredient, as stated in the special provisions. If use of ground limestone is required, it shall then be spread at a rate which will provide not less than the minimum quantity stated in the special provisions. These materials shall be incorporated into the soil at a depth of not less than 2 inches by disking, raking, or other methods acceptable to the ENGINEER. Any stones larger than 2 inches in any diameter, large clods, roots, and other litter brought to the surface by this operation shall be removed.

**1203-3.4 OBTAINING AND DELIVERING SOD.** After inspection and approval of the source of sod by the ENGINEER, the sod shall be cut with approved sod cutters to such a thickness that after it has been transported and placed on the prepared bed, but before it has been compacted, it shall have a uniform thickness of not less than 2 inches. Sod sections or strips shall be cut in uniform widths, not less than 10 inches, and in lengths of not less than 18 inches, but of such length as may be readily lifted without breaking, tearing, or loss of soil. Where strips are required, the sod must be rolled without damage with the grass folded inside. The CONTRACTOR may be required to mow high grass before cutting sod.

The sod shall be transplanted within 24 hours from the time it is stripped, unless circumstances beyond the CONTRACTOR's control make storing necessary. In such cases, sod shall be stacked, kept moist, and protected from exposure to the air and sun and shall be kept from freezing. Sod shall be cut and moved only when the soil moisture conditions are such that favorable results can be expected. Where the soil is too dry, permission to cut sod may be granted only after it has been watered sufficiently to moisten the soil to the depth the sod is to be cut.

**1203-3.5 LAYING SOD.** Sodding shall be performed only during the seasons when satisfactory results can be expected. Frozen sod shall not be used and sod shall not be placed upon frozen soil. Sod may be transplanted during periods of drought with the approval of the ENGINEER, provided the sod bed is watered to moisten the soil to a depth of at least 4 inches immediately prior to laying the sod.

## SECTION 1203 – SODDING

The sod shall be moist and shall be placed on a moist earth bed. Pitchforks shall not be used to handle sod and dumping from vehicles shall not be permitted. The sod shall be carefully placed by hand, edge to edge and with staggered joints, in rows at right angles to the slopes, commencing at the base of the area to be sodded and working upward. The sod shall immediately be pressed firmly into contact with the sod bed by tamping or rolling with approved equipment to provide a true and even surface, and ensure knitting without displacement of the sod or deformation of the surfaces of sodded areas. Where the sod may be displaced during sodding operations, the workmen when replacing it shall work from ladders or threaded planks to prevent further displacement. Screened soil of good quality shall be used to fill all cracks between sods. The quantity of the fill soil shall not cause smothering of the grass. Where the grades are such that the flow of water will be from paved surfaces across sodded areas, the surface of the soil in the sod after compaction shall be set approximately 1 inch below the pavement edge. Where the flow will be over the sodded areas and onto the paved surfaces around manholes and inlets, the surface of the soil in the sod after compaction shall be placed flush with the pavement edges.

On slopes steeper than 1 vertical to 2½ horizontal and in V-Shaped or flat bottom ditches or gutters, the sod shall be pegged with wooden pegs not less than 12 inches in length and have a cross-sectional area of not less than ¾ square inch. The pegs shall be driven flush with the surface of the sod.

**1203-3.6 CLEANUP.** After the staking has been completed, the surface shall be cleaned of loose sod, excess soil, or other foreign materials before watering.

**1203-3.7 WATERING.** Adequate water and watering equipment must be on hand before sodding begins. Sod shall be kept moist until it has become established and its continued growth assured. In all cases, watering shall be done in a manner which will avoid erosion from the application of excessive quantities and will avoid damage to the finished surface.

### **1203-3.8 ESTABLISHING TURF.**

**(a) General.** The newly placed sod shall be kept in good condition during the care period following placement. The care period after placement of the sod shall be 14 days' duration for sod placed before July 15 and after September 15; and shall be 21 days' duration for sod placed between July 15 and September 15.

The time between October 15 of any year and April 15 of the following year shall not be considered to be a part of the required care period for sod. Sod replaced after October 15 of any year, or sod placed at a time when the care period for that sod extends past October 15, shall show evidence of establishing growth after April 15 of the following year before its care period will be considered concluded.

## SECTION 1203 – SODDING

Water shall be applied to the sod during the care period, at a rate of 5 gallons per square yard, immediately after placement and again at 7 days and 14 days after placement.

For sod placed between July 15 and September 15, an additional 5 gallons per square yard shall be applied 21 days after sod placement.

Water shall be applied by sprinkling or any method approved by the ENGINEER that prevents wasting the water by runoff from the sod area. If necessary to prevent runoff, several hours of application of the water may be required. The amount of water to be applied may be reduced by the ENGINEER if in his opinion there has been enough rainfall to warrant a reduction.

The CONTRACTOR shall furnish and replace, without any compensation therefor, any sod that dies or is damaged to the extent replacement is required during the care period. Replacement sod shall be installed under the same specification requirements as those for the original sod being replaced, including the care period.

Water will be considered incidental to the item "Sodding."

**(b) Protection.** All sodded areas shall be protected against traffic or other use by warning signs or barricades approved by the ENGINEER.

**(c) Mowing.** The CONTRACTOR shall mow the sodded areas with approved mowing equipment, depending upon climatic and growth conditions and the needs for mowing specific areas. In the event weeds or other undesirable vegetation are permitted to grow to such an extent that, either cut or uncut, they threaten to smother the sodded species, they shall be mowed and the clippings raked and removed from the area.

**1203-3.9 REPAIRING.** When the surface has become gullied or otherwise damaged during the period covered by the contract, the affected areas shall be repaired to re-establish the grade and the condition of the soil, as directed by the ENGINEER, and shall then be re-sodded as specified in Section 1203-3.5.

### **1203-4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107.

## SECTION 1204 – MULCHING

### 1204-1 DESCRIPTION

This item shall consist of furnishing, hauling, placing, and securing mulch on surfaces indicated on the plans or designated by the ENGINEER. The mulch is used to conserve moisture, prevent surface compaction or crushing, reduce runoff and erosion, control weeds, and help hasten establishment of plant cover.

### 1204-2 MATERIALS

**1204-2.1 MULCH MATERIAL.** Acceptable mulch shall be the materials listed below or any approved locally available material similar to those specified. Low-graded, musty, spoiled, partially rotted hay, straw, or other materials unfit for animal consumption will not be acceptable. Mulch materials which contain matured seed of species which would volunteer and be detrimental to the proposed over seeding, or to surrounding farmland, will not be acceptable. Straw or other mulch material which is fresh and/or excessively brittle, or which is in such an advanced stage of decomposition as to smother or retard the planted grass, will not be acceptable.

- (a) **Hay.** Hay shall be native hay, Sudan grass hay, broomsedge hay, legume hay, or similar hay or grass clippings. Average length shall be 10 inches. Leguminous plants shall not exceed 25 percent of the dry weight of the mulch.
- (b) **Straw.** Straw shall be the threshed plant residue of oats, wheat, barley, rye, or rice from which the grain has been removed. Average length shall be 6 inches if anchored by asphalt or netting or 10 inches if anchored mechanically.
- (c) **Stalks.** Stalks shall be the whole or shredded stems of corn, cane, sorghum, flax, sunflowers, potato vines, or other coarse stemmy material.
- (d) **Manure.** Manure shall be fresh or partially decomposed strawy stable manure containing not over 25 percent of solid material by volume.
- (e) **Hay Mulch Containing Seed.** Hay mulch shall be mature hay containing viable seed of native grasses or other desirable species stated in the special provisions or as approved by the ENGINEER. The hay shall be cut and handled so as to preserve the maximum quantity of viable seed. Hay mulch which cannot be hauled and spread immediately after cutting shall be placed in weather-resistant stacks or baled and stored in a dry location until used.
- (f) **Manufactured Mulch.** Cellulose-fiber or wood pulp mulch shall be products commercially available for use in spray applications. Wood cellulose fiber mulch shall consist of wood cellulose fiber pulp and fiber coatings which shall contain no germination or growth inhibiting factors. This mulch shall be free of contamination from

## SECTION 1204 – MULCHING

noxious weed seed, seed from other competitive plants, mold, or fungus. It shall be dyed an appropriate color to allow visual metering of its application, and shall have the property of becoming dispersed and suspended when agitated in water. When sprayed uniformly on the surface of the soil, the fibers shall form a blotter-like ground cover that readily absorbs water and allows infiltration to the underlying soil.

Weight specifications from suppliers, and for all applications, shall refer only to air-dry weight of the fiber, a standard equivalent to 10 percent moisture. Each package of the cellulose fiber shall be marked by the manufacturer to show the air dry weight content. Suppliers shall certify, upon request of the ENGINEER, that laboratory and field testing of their product has been accomplished and that it meets the foregoing requirements and intent. Sampling and testing for moisture content will be in accordance with ASTM D2016, Over-Drying Method.

(g) **Asphalt Binder.** Asphalt binder material shall conform to the requirements of ASTM D977, Type SS-1 or RS-1, as appropriate.

(h) **Mulch Blanket.**

1. The excelsior blanket shall consist of a machine-produced mat of curled wood excelsior of 80 percent 6-inch or longer fiber length with consistent thickness and the fiber evenly distributed over the entire area of the blanket. The top side of each blanket shall be covered with a 2-inch by 1-inch biodegradable mesh. The blanket shall be smolder resistant. The blanket shall be secured to the ground with wire staples .091-inch diameter or greater. Staples will be "U" shaped with legs 6 inches in length with a one inch crown.

The excelsior erosion blankets will be equivalent to the "Curlex" (trademark) blanket manufactured by the American Excelsior Company, Arlington, Texas.

2. Paper fabric blanket shall consist of a knitted construction of yarn interwoven with strips of biodegradable paper as manufactured by Gulf States Paper Corporation or approved equivalent. The paper strips and yarn shall degrade without residue. Staples shall be high carbon iron 6 to 12 inches long. Paper fabric shall be 0.05 to 0.30 pounds per square yard ( $\pm 10\%$ ) per manufacturer's recommendation for fabric degradation timing to produce grass stand specified.

(i) **Mulch Net.** Mulch net shall consist of a biodegradable net made from extruded oriented polypropylene as manufactured by American Excelsior Company or approved equivalent. Mulch netting shall be stranded with approximately 5/8 x 3/4 inch mesh opening (maximum 1½ x 3 inches) to hold loose straw, hay, bark, wood chips, and other loose mulches in place.

(j) **Hydro-mulch.** Mulch to be used shall consist of a wood cellulose fiber that has not been treated with any germination or growth inhibitive substances. The mulch shall be treated with a tack and fiber to enhance seed and mulch placement and adherence to

## SECTION 1204 – MULCHING

the soil. The mulch shall be free of contamination from noxious weed seed and seed from competitive plants.

**1204-2.2 INSPECTION.** Within five days after acceptance of the bid, the ENGINEER shall be notified of sources and quantities of mulch materials available, and the CONTRACTOR shall furnish the ENGINEER with representative samples of the materials to be used. These samples may be used as standards with the approval of the ENGINEER, and any materials brought on the site which do not meet these standards shall be rejected.

### 1204-3 CONSTRUCTION REQUIREMENTS

**1204-3.1 MULCHING.** Before spreading mulch, all large clods, stumps, stones, brush, roots, and other foreign material shall be removed from the area to be mulched. Mulch shall be applied immediately after seeding or within 24 hours. The spreading of the mulch may be by hand methods, blower, or other mechanical methods, provided a uniform covering is obtained. When spread by hand, the bales of hay must be torn apart, "fluffed up," and spread uniformly over the area. Mulches shall not be applied when velocities exceed 15 miles per hour. If excessive breakage of mulch occurs during spreading or anchoring, mulch shall be "wet down" with sprinkler or other suitable means.

Straw or hay shall be spread over the surface to form a uniform thickness to provide a loose depth of not less than 1½ inches nor more than three inches. Other organic material shall be spread at the rate directed by the ENGINEER. Mulch may be blown on the slopes, and the use of cutters in the equipment for this purpose will be permitted to the extent that at least 95 percent of the mulch in place on the slope shall be 6 inches or more in length. When mulches applied by the blowing method are cut, the loose depth in place shall not be less than 1 inch nor more than 2 inches.

TABLE OF MULCH APPLICATION RATES

<u>Mulch</u>	<u>Anchoring Method</u>	<u>Rate (lbs/acre)</u>	<u>Rate of Asphalt Emulsion Track Gal/Acre</u>
Native or Tame Hay	Mulch Tiller	3000-4000*	-
Native or Tame Hay	Asphalt or Resin Emulsion	3000	300
Small Grain Straw	Mulch Tiller	4000-5000*	-
Small Grain Straw, Flax	Asphalt or Resin Emulsion	3000	300

## SECTION 1204 – MULCHING

Flax	Mulch Tiller	3000-5000*	-
Manure	None	30,000-40,000	-
Manure	Disk	60,000-80,000	-
Wood Cellulose Fiber	Hydraulic Spray Equipment	1500-2000	-
Hydro	Spray Equipment	2000	-

\*Other methods as hand anchorage, netting, and peg and string method use 3,000 lbs/acre.

**1204-3.2 SECURING MULCH.** The mulch shall be held in place by light disking, a very thin covering of topsoil, small brush, pins, stakes, wire mesh, asphalt binder, or other adhesive material approved by the ENGINEER. Where mulches have been secured by either of the asphalt binder methods, it will not be permissible to walk on the slopes after the binder has been applied. The CONTRACTOR is warned that in the application of asphalt binder material, he must take every precaution to guard against damaging or disfiguring structures or property on or adjacent to the areas worked and that he will be held responsible for any such damage resulting from his operations.

(a) If the "peg and string" method is used, the mulch shall be secured by the use of stakes or wire pins driven into the ground on 5-foot centers or less. Binder twine shall be strung between adjacent stakes in straight lines and crisscrossed diagonally over the mulch, after which the stakes shall be firmly driven nearly flush to the ground to draw the twine down tight onto the mulch.

(b) Mulch Nettings - Staple paper, cotton, or plastic netting to the soil surface according to manufacturer's recommendations.

(c) Hand Anchorage - With a square pointed spade, punch mulch into the surface soil in contour rows 12 inches apart.

(d) Mechanical Mulch Anchoring or Crimping -

1. Tools - Use a heavy, straight coulter type mulch tiller (Imco). The coulters should be 1/4-inch thick and be of sufficient diameter to prevent the frame from dragging the mulch. The edges should be dull so as not to cut the mulch during the anchoring operation. The edges may be serrated or smooth; if serrated, the scallops should not be more than three inches in length and 3/4 inch in depth. The rows or furrows made by the mulch tiller shall be spaced 6 to 12 inches apart. Penetration depth should be 2 to 3 inches. The mulch should not be covered with excessive amounts of soil. Limit to no more than two passes by the mulch tiller. All mulching operations will be done on the approximate contour.

## SECTION 1204 – MULCHING

2. Site Preparation - When using a mulch anchoring tool, the seed bed must be loosened to a minimum depth of three inches prior to placing and anchoring mulch material. This is necessary for the 2 or 3 inch preparation required for mulch anchorage. (Drill or seeding equipment used at this time must be equipped with depth bands as the ability to obtain a firm seed bed is improbable.)

(e) Asphalt Emulsion Mulch Tack - Asphalt emulsion shall be continuously applied with an emulsion spray system equipment with a mechanical mulch hay blower. Application temperature shall be 50°F or greater (air temperature). The asphalt shall be applied with a mechanical mulch blower equipped with an emulsion sprayer system having a heating unit.

(f) Resin Emulsion Mulch Tack - The resin shall be applied with a mechanical mulch blower equipped with an emulsion spray system having a heating unit.

(g) Wood cellulose fiber mulch shall be applied with hydraulic spray equipment at the rate of 1,500 to 2,000 pounds per acre. The fiber shall be added to the water slurry in a hydraulic seeder along with the proportionate quantities of seed, fertilizer, and other approved materials. All ingredients shall be mixed to form a homogeneous slurry. Using the color of the mulch material as a metering agent, one shall uniformly spray the slurry mixture on the prepared seed bed.

A non-toxic, organic soil stabilizer may be included or added to the wood cellulose fiber where there is a high probability of wind or water erosion. Application rates of such soil stabilizers will be at the manufacturer's recommendation rates.

Since this method is basically a broadcast (surface) application of seed, the mulched area shall be kept moist by sprinkler or other means for a period of 30 days. Under conditions of extreme winds, some peeling may occur. The mulch also is subject to washing away under intense or prolonged rains. These factors should be considered in selecting this method of mulching.

(h) Mulch blankets may be primarily used to mulch small critical areas (such as ditch bottoms and slopes greater than 3:1) and shall be applied in accordance with the manufacturer's recommendations. When the blanket is unrolled, the netting shall be on top and the fibers in contact with the soil over the entire area. In channels, the blankets shall be applied in the direction of the flow of water. On slopes, the blankets shall be applied across the slope. Ends and sides shall be butted snugly and stapled, in both instances.

The staples shall be driven vertically into the ground, spaced approximately 2 linear yards apart, on each side of the blanket, and one row in the center alternately spaced between each side. Use a common row of staples on adjoining blankets.

(i) If the "asphalt spray" method is used, all mulched surfaces shall be sprayed with asphalt binder material so that the surface has a uniform appearance. The binder shall be uniformly applied to the mulch at the rate of approximately 8 gallons per 1,000

## SECTION 1204 – MULCHING

square feet, or as directed by the ENGINEER, with a minimum of 6 gallons and a maximum of 10 gallons per 1,000 square feet depending on the type of mulch and the effectiveness of the binder securing it. Bituminous binder material may be sprayed on the mulch's slope areas from either the top or the bottom of the slope. An approved spray nozzle shall be used. The nozzle shall be operated at a distance of not less than 4 feet from the surface of the mulch, and a uniform distribution of the bituminous material shall be required. A pump or an air compressor of adequate capacity shall be used to ensure uniform distribution of the bituminous material.

(j) If the "asphalt mix" method is used, the mulch shall be applied by blowing, and the asphalt binder material shall be sprayed into the mulch as it leaves the blower. The binder shall be uniformly applied to the mulch at the rate of approximately 8 gallons per 1,000 square feet or as directed by the ENGINEER, with a minimum of 6 gallons and a maximum of 10 gallons per 1,000 square feet depending on the type of mulch and effectiveness of the binder securing it.

(k) If the "hydromulch" method is used, the mulch shall be uniformly applied at the application rate shown and shall cover a minimum of 95 percent of the seedbed area. After application, the mulch shall permit percolation of water to the underlying soil.

### **1204-3.3 CARE AND REPAIR**

(a) The CONTRACTOR shall care for the mulched areas until final acceptance of the project. Such care shall consist of providing protection against traffic or other use by placing warning signs as approved by the ENGINEER, and erecting any barricades that may be shown on the Plans before or immediately after mulching has been completed on the designated areas.

(b) The CONTRACTOR shall be required to repair or replace any mulching that is defective or becomes damaged until the project is finally accepted. When, in the judgment of the ENGINEER, such defects or damages are the result of poor workmanship or failure to meet the requirements of the Specifications, the cost of the necessary repairs or replacement shall be borne by the CONTRACTOR. However, once the CONTRACTOR has completed the mulching of any area in accordance with the provisions of the Specifications and to the satisfaction of the ENGINEER, no additional work at his expense will be required, but subsequent repairs and replacements deemed necessary by the ENGINEER shall be made by the CONTRACTOR and will be paid for as additional or extra work.

### **1204-4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107.

## SECTION 1205 – MANHOLES AND INLETS

### 1205-1 DESCRIPTION

These items shall consist of the construction or installation of manholes and inlets, in accordance with these specifications, at the specified locations and Standard Details and conforming to the lines, grades, and dimensions shown on the plans or required by the ENGINEER.

### 1205-2 MATERIALS

**1205-2.1 CONCRETE.** Plain and reinforced concrete used in this work shall conform to the requirements of Section 501 "Portland Cement Concrete Pavement."

**1205-2.2 MORTAR.** Mortar shall be a compound of 1 portland cement to 2 parts of sand by volume to which lime may be added not to exceed 10 percent of the cement by weight.

**1205-2.3 PRECAST REINFORCED CONCRETE PIPE MANHOLE.** Precast reinforced concrete manhole risers and top sections shall conform to ASTM C478.

All barrel-to-barrel joints shall be sealed using a P2 gasketed joint for 48-inch manholes, a CX-4 joint for all other sizes of manholes, and an exterior seal by Press-Seal Gasket Corporation EZ Wrap and EZ Stik No. 4 primer, for all sizes of manholes, or approved equivalent. The height of the manhole shall be shown on the plans, and the diameter shall be 48 inches minimum or larger if recommended by the manhole fabricator and approved by the ENGINEER.

Steps shall not be placed in sanitary sewer, storm sewer, or air release manholes or inlets unless specified. If specified, the manhole steps to be furnished and installed shall be rubber-coated over steel reinforcing of the type manufactured by the Delta Products (Delta-Surefoot Company), or approved equivalent.

**1205-2.4 PRECAST REINFORCED CONCRETE PIPE MANHOLE WITH MONOLITHIC BASE.** Precast reinforced concrete risers and top sections shall conform to ASTM C478. Manhole bases shall extend a minimum of 6 inches past the exterior manhole wall, except bases below M.S.L. elevation 1626 (NGVD88) or manholes 18 feet (from rim to top of pipe) or greater in depth, which shall extend 12 inches past the exterior manhole wall. The base and the bottom section shall be cast monolithically with precast flow lines.

The pipe connections to the manhole shall be sealed with Press-Seal Gasket Corporation Model PSX-Boot with 2 stainless steel bands or approved equivalent. Connection boots and bands are not required on storm sewer manholes. All barrel-to-barrel joints shall be sealed using a P2 gasketed joint for 48-inch manholes, a CX-4 joint

## SECTION 1205 – MANHOLES AND INLETS

for all other sizes of manholes, and an exterior seal by Press-Seal Gasket Corporation EZ Wrap and EZ Stik No. 4 primer, Infi-Shield External Gator Wrap for all sizes of manholes, or approved equivalent. All barrel sections below M.S.L. elevation 1626 (NGVD88) or 18 feet or greater in depth (from rim to top of pipe) shall be restrained using three outside pipe joint ties equally spaced or approved equivalent. The height of the manhole shall be shown on the Plans, and the diameter shall be 48 inches minimum or larger if recommended by the manhole fabricator and approved by the ENGINEER.

Steps shall not be placed in sanitary sewer, storm sewer, or air release manholes or inlets unless specified. If specified, the manhole steps to be furnished and installed shall be rubber-coated over steel reinforcing of the type manufactured by the Delta Products (Delta-Surefoot Company), or approved equivalent.

**1205-2.5 MANHOLE CASTINGS.** Materials shall conform to the requirements of Section 1206.

**1205-2.6 INLET CASTINGS.** Materials shall conform to the requirements of Section 1206.

**1205-2.7 SLOTTED DRAIN INLET.** Slotted drain inlets shall be of a quality equal to the type manufactured by Contech Construction Products with the modified hugger band under the minimum requirements in design, material, and workmanship conforming to the latest standards of AASHTO M36 and AASHTO M111.

**1205-2.8 REINFORCING STEEL.** Reinforcing steel used in this work shall conform to Section 501.

**1205-2.9 AIR RELEASE VALVE.** All air release valve taps, made into all sizes and classes of PVC and ductile iron water mains, shall be reinforced with a tapping saddle. Tapping saddles shall be a minimum of 2-bolt stainless steel skirted or complete gasket type. An O-ring single bolt stainless steel saddle is not acceptable.

The automatic air release valve shall be a 2-inch APCO No. 200, Valmatic Model 38, or H-TEC Model 986-01, or approved equivalent for water. Connection type shall be threaded FNTF.

The automatic air release valve shall be a 2-inch H-TEC Model 986-01 or approved equivalent for sewer. Connection type shall be threaded FNTF.

The corporation stop shall be a Mueller No. H-15000 for copper water pipe, or approved equivalent. Any fittings required for connection to the outlet pipe shall be brass or stainless steel. See Standard Detail 1205-11.

**1205-2.10 PRECAST REINFORCED CONCRETE MANHOLE BASES.** Precast reinforced concrete manhole bases shall conform to ASTM C478. The bases shall extend a minimum of 6 inches past the exterior manhole wall, except bases below M.S.L. elevation 1626 (NGVD88), which shall extend 12 inches past the exterior

## SECTION 1205 – MANHOLES AND INLETS

manhole wall. Base thickness shall be as follows: Manholes with inside diameters up to and including 48 inch – 6 inch thick, 54 inch through 102 inch – 8 inch thick, 108 inch and 120 inch – 12 inch thick. Precast air release manhole bases shall be 2 inches thicker than the base thicknesses listed above.

**1205-2.11 PRECAST REINFORCED CONCRETE MANHOLE COVERS.** Precast reinforced concrete manhole covers shall conform to ASTM C478. Cover thickness shall be as follows: Manholes with inside diameters up to and including 48 inch – 6 inch thick, 54 inch through 102 inch- 8 inch thick, and 108 inch and 120 inch – 12 inch thick.

**1205-2.12 CONCRETE ADJUSTMENT RINGS.** Concrete adjustment rings shall have a minimum compressive strength of 4000 psi, steel reinforced and meet AASHTO H-20 loading requirements.

Concrete adjusting rings shall have an internal dimension that does not restrict the opening size of the manhole or inlet casting.

Rings shall be 2 inches thick unless otherwise approved by Engineer.

**1205-2.13 POLYMER ADJUSTMENT RINGS.** Polymer adjustment rings shall be injection molded High Density Polyethylene (HDPE) as manufactured by Ladtech, Inc or IPEX Inc conforming to ASTM D4976, Expanded Polypropylene as manufactured by Cretex Specialty Products, or approved equal.

Polymer adjusting rings shall have an internal dimension that does not restrict the opening size of the manhole or inlet casting.

Rings shall be 2 to 6 inches thick, cross slope adjusting rings may be allowed with approval by Engineer.

### **1205-3 CONSTRUCTION REQUIREMENTS.**

**1205-3.1 EXCAVATION.** Excavation for catch basins, manholes, inlets, and pipe junctions shall be done in a manner to provide adequate room for the construction of the item according to details shown on the plans. When necessary the excavation shall be adequately shored or sheeted to ensure safe and satisfactory construction and backfilling.

**1205-3.2 PRECAST REINFORCED CONCRETE PIPE MANHOLES AND INLETS.** Unless otherwise specified, standard reinforced concrete sewer pipe shall be used for this purpose. When this type of construction is used, the bottom precast section shall be set in a full mortar bed, and the joints between sections and around pipes shall be filled with mortar.

**1205-3.3 CONCRETE CONSTRUCTION (CAST IN PLACE).** The composition, consistency, placing, form work, curing, and protection of the concrete shall conform to

## SECTION 1205 – MANHOLES AND INLETS

the plans. No finishing of the concrete will be required except the filling of honeycombed areas.

**1205-3.4 CONCRETE BASE.** The bottoms of all manholes and inlets shall be of concrete. The thickness and other dimensions of the base shall be as specified on the plans. The invert channel shall be the true shape of the lower half of the pipe or sewer. Pipe or tile placed in concrete for inlet or outlet connections shall extend through the walls a sufficient distance to allow for connections, and the concrete shall be carefully constructed around them so as to prevent leakage along their outer surface. The inside ends shall be flush with the inside walls, and the pipe shall be of the same size and kind as those with which they connect on the outside.

**1205-3.5 CASTINGS.** The methods of construction shall conform insofar as applicable to the requirements of Section 1206.

**1205-3.6 SLOTTED DRAIN INLET.** Slotted drain inlets shall be constructed in compliance with Standard Details 1205-9 and 1205-10. The CONTRACTOR shall furnish all equipment, labor, and materials, including the connection to the inlet or manhole, flowable fill for bedding and curb and gutter, all of which shall be considered incidental to the price for slotted drain.

**1205-3.7 BACKFILL.** Backfill shall be deposited in horizontal layers not over 6 inches in depth (loose) and each layer compacted, this process being repeated to the elevation of the finished grade as designated on the plans. Compaction shall be secured by watering each layer if dry (the water content of the material used shall not exceed the optimum moisture content) and tamping with approved mechanical rammers. The backfill shall be compacted to a density equal to the requirements specified for the pipe trench common to the manhole or inlet.

**1205-3.8 CLEANING.** All manholes and inlets shall be thoroughly cleaned of any accumulation of silt, debris, or foreign matter of any kind, and shall be free from such accumulations at the time of the final inspection.

**1205-3.9 REMOVE INLET.** Removal shall include entire concrete structure and backfilling excavation with bedding material, or material approved by ENGINEER. The casting shall be delivered to the salvage yard at the City of Bismarck Department of Public Works at 601 South 26<sup>th</sup> Street.

**1205-3.10 MARKING MANHOLES AND INLETS.** The CONTRACTOR will be required to furnish and install a "Tee" or "U" steel fence post having a minimum length of 5½ feet located 1 foot from the edge of the casting on a line perpendicular to the face of the curb.

The cost of the steel fence post and installation shall be considered incidental to other bid items.

## SECTION 1205 – MANHOLES AND INLETS

**1205-3.11 POLYVINYL CHLORIDE PIPE TO MANHOLE ADAPTERS.** All connections shall be made using manhole connector (rubber boot) or a PVC to MH adapter (sand collar) in the wall of any manhole connected to PVC sewer pipe. Manhole connectors shall be PSX Press Boot as manufactured by Press-Seal Gasket Corporation, or approved equivalent, and shall be connected with 2 pipe bands.

The cost of the PVC manhole adaptor and the installation shall be considered incidental to the bid item for "Concrete Manhole."

**1205-3.12 INLET STAKES.** Section 104 "Monuments, Bench Marks, Witness and Grade Stakes" shall be strictly followed. The same line and grade stakes set by the ENGINEER for the construction of each inlet shall be saved and used by the CONTRACTOR to set the inlet castings to line and grade.

### **1205-4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107 and as follows:

**1205-4.1 CASTINGS FOR MANHOLES, INLETS, CATCH BASINS AND OTHER STRUCTURES.** All manhole, inlet, and catch basin bid items shall include installation of casting(s) unless otherwise noted. Contractor shall supply castings and covers and include in bid price for structures unless otherwise noted.

## **SECTION 1206 – CASTINGS AND ADJUSTMENT**

### **1206-1 DESCRIPTION**

This item shall consist of furnishing and adjusting new castings on existing manholes in accordance with this section, the details and plans at the locations indicated on the plans, or as directed by the ENGINEER. This item includes adjusting new castings installed within the same project.

This item shall include the resetting of manhole frames and covers, inlet frames and covers, City water works valve boxes, or other accessories requiring adjustment to new lines and grades where such accessories are public property. Unless otherwise indicated on the plans, adjustments, replacements, and repairs to private property shall be exempt from this item.

This item shall include the furnishing of new castings, grating, I & I barriers, or covers specifically indicated on the plans. The CONTRACTOR, however, will be required to replace, at its own expense, any damaged parts resulting from its operations.

### **1206-2 MATERIALS**

**1206-2.1** Materials shall conform insofar as applicable to the requirements of Section 1205.

**1206-2.2 MANHOLE CASTINGS.** Sanitary Sewer, Storm Sewer, and Water Main Manhole Castings shall conform to the following:

(a) **MANHOLE CASTINGS.** Manhole frames and covers shall be of the type manufactured by the Neenah Foundry Company Number R-1733, East Jordan Iron Works Number 1205, or Municipal Castings, Inc. Number 301 with concealed pick holes and self-sealing platen lid, or approved equivalent.

(b) **FLOATING MANHOLE CASTINGS.** Floating manhole frames and covers shall be of the type manufactured by Neenah Foundry Company Number R-1955-1 or East Jordan Iron Works Number 3025 with concealed pick holes and self-sealing platen lid, or approved equivalent. See Standard Details 1206-3 and 1206-4.

Type (b) shall be used with all new and existing manholes located in concrete pavement surfaces unless noted in plans, type (a) shall be used in all other instances unless noted in plans.

Manhole lids shall be labeled, with applicable utility type, "SANITARY SEWER", "STORM SEWER" or "WATER" in two-inch raised lettering.

## SECTION 1206 – CASTING AND ADJUSTMENT

**1205-2.3 INLET CASTINGS.** Inlet castings shall be of the type manufactured by Neenah Foundry Company with Type V Grates and NDDOT Style Backs, East Jordan Iron Works with M6 Type Grate and Type T2 Back for Type 24-inch and with type M4 Grate and Type T5 Back for Type 36-inch or larger, or approved equivalent. All bolts to be temper finish, double heat-treated 1038 S.A.E., Grade 5, Cad-Dichromate plated.

**(a) Type 24” Castings.** Type 24-Inch Castings shall be Neenah Foundry Number R-3030, East Jordan Iron Works Number 7010 with round base, or approved equivalent.

**(b) Type 36” Castings.** Type 36-Inch Inlet Castings shall be a Neenah Foundry Number R-3295, East Jordan Iron Works Number 7030, or approved equivalent.

**(c) Type 72” Castings.** Type 72-Inch Castings shall be Neenah Foundry Number R-3295-2, East Jordan Iron Works Number 7031, or approved equivalent.

**(d) Type 108” or Larger Castings.** Type 108-Inch or Larger Castings shall be Neenah Foundry Number R-3295-3, or East Jordan Iron Works Number 7032 with additional inner sections, or approved equivalent.

**(e) Catch Basin Castings.** Catch Basin Castings shall be Neenah Foundry Number R-2573 with concave grate, Neenah Foundry Number R-2561 with “beehive” grate, or approved equivalent.

**1206-2.4** Flexible foam expansion joint materials shall meet the requirements of ASTM D5249, TYPE 2 and ASTM D1752, Sections 5.1 through 5.4 with the compression required modified to 10 psi and 25 psi maximum. This material shall be non-gassing and shall be compatible with hot pour joint sealants.

### 1206-3 CONSTRUCTION REQUIREMENTS

**1206-3.1 GENERAL.** The methods of construction shall conform insofar as applicable to the requirements of Section 1205.

Existing manholes, inlets, and valve boxes shall be adjusted to the elevation, grade, or dimensions as indicated on the plans and standard details, or as ordered by the ENGINEER. The structures are assumed to be clean prior to the beginning of the adjustment construction unless otherwise agreed to by the CONTRACTOR and the ENGINEER. Castings shall be carefully removed and reinstalled by the CONTRACTOR as indicated. If the height of a rectangular casting is to be increased, the addition may be of solid concrete block or concrete as specified in Section 501. Solid concrete block shall not be used to increase the height of circular castings. In the event the top part of the existing structure is weak and faulty, it shall be replaced as directed by the ENGINEER and the extension completed. Where the casting, grating, I & I barrier, or cover is to be lowered, the masonry or concrete shall be removed to sufficient depth so that a seat of proper dimensions may be reconstructed to receive the casting, grating, I & I barrier, or cover at the new grade. Castings shall be set in full mortar beds or

## SECTION 1206 – CASTING AND ADJUSTMENT

otherwise secured as shown on the plans. Mortar shall be in accordance with Section 1205. Casting shall be set accurately to correct elevation and line so that no subsequent adjustment will be necessary. If necessary, the CONTRACTOR shall use tapered or sloped adjusting risers.

Upon completion of the adjustment, all surplus material shall be removed, and the structure and the site of the work shall be left in a neat and clean condition. The entire structure shall be thoroughly cleaned of any accumulation of silt, debris, or foreign matter of any kind and shall be free from such accumulations at the time of final inspection.

**1206-3.2 WATER STOP BOX EXTENSION.** Water service stop boxes are found within the area of construction very frequently. Adjustments in elevation that can be accomplished within the range of the adjustment sleeve of the stop box shall be considered incidental to the contract bid items. The CONTRACTOR is required to use due care in making these adjustments.

If the stop box cannot be extended to the proper grade within the above limits, it shall be adjusted by removing the lid and adding the required length and diameter of standard weight pipe with a standard pipe coupling and replacing the lid. The adjustment shall be paid under Bid Item "Water Stop Box Extension".

**1206-3.3 WRAPPED UTILITY BOXES.** Utility structures, excluding manholes, encased in concrete sidewalks and pavements, shall be wrapped with a flexible foam expansion joint. Wrapped structures include valve boxes, hydrants, curb stop boxes, street light poles and foundations, traffic signal foundations, pedestrian signal pole foundations, and street signs.

Minimum thickness of the flexible joint will be 1/2 inch used on curb stop boxes, hydrants, street signs, pedestrian signal foundations, and valve boxes. Minimum thickness for larger structures shall be 3/4 inch to 1 inch maximum. Wrapped utility boxes shall be considered incidental.

**1206-3.4 CASTINGS.** All manhole, inlet, and catch basin castings shall be placed with a minimum of 1/2 inch of grout between the manhole inlet or catch basin, but not adjusted to grade unless specified on the plans. Total allowance for adjustment shall be from 0 to 6 inches. Castings requiring adjustment to grade shall be paid for under Section 1206 "Castings and Adjustment." All inlet castings shall be placed on the inlet facing the roadway with bolts, washers, and nuts installed in accordance with Standard Detail 1206-1.

**1206-3.5 FLOATING MANHOLE CASTINGS.** All new and existing manholes located in concrete pavement surfaces shall have floating manhole castings installed as shown in standard details 1206-3 and 1206-4.

**1206-3.6 ADJUSTING MANHOLE CASTING WITH RING AND I/I BARRIER.** I/I barriers shall be installed on all new manholes outside of pavement areas. Manholes

## SECTION 1206 – CASTING AND ADJUSTMENT

installed in future paved areas shall have I/I barriers installed unless the roadway is scheduled to be paved within the same construction season. I/I barriers will not be required when casting, all rings and top of cone are encased in concrete and located in a paved roadway, including roadways scheduled to be paved in the same construction season.

All newly installed manholes requiring adjustment under this bid item shall use the precast concrete adjusting rings with the AP/M PERMAFORM I/I BARRIER as manufactured by Strike Products, or approved equivalent, installed and field tested according to the manufacturers' specifications. This item shall be paid for under Section 1206 "Castings and Adjustment." All inlet castings shall be placed on the inlet facing the roadway with bolts, washers, and nuts installed in accordance with Standard Detail 1206-1.

The I/I Barrier shall have a watertight seal to the top of manhole barrel using butyl sealant, or approved equivalent, as specified by the manufacturer of the I/I Barrier. The top of manhole barrel shall be free of dust and debris before applying the sealant and the I/I Barrier. A sufficient quantity of sealant must be used to accommodate any flaws in the top of manhole barrel.

If deemed necessary by the ENGINEER, to check the seal of the I/I Barrier, the excavated area around the I/I Barrier shall be filled with water to a level above the joint between the I/I Barrier and the top of manhole barrel. If any leakage or moisture is present in the area inside the manhole around the seal, the CONTRACTOR shall remove the I/I Barrier and reseal at no additional cost.

The bottom ring placed on the I/I Barrier shall not be sealed to the I/I Barrier to allow infiltrated water to escape. All successive rings above the bottom ring shall be sealed together per manufacturer's recommendations. The I/I Barrier shall extend a minimum of 2 inches above the top ring. If a floating manhole casting is used, the I/I Barrier extending above the top ring shall be trimmed so that the I/I Barrier does not interfere with the manhole casting's ability to function. All pressure-reducing valve and air release valve manholes shall include a Cap 'N Seal as manufactured by Strike Products.

All existing manholes outside the roadway surface that require adjustment shall be paid for under Section 1206-4.17 "Adjust Manhole Casting in Unpaved Area." All existing manholes outside the roadway surface that require a new manhole casting shall have standard castings and shall be paid for under Section 1206-4.18 "Furnish and Adjust Manhole Casting in Unpaved Area."

**1206-3.7 CASTING ADJUSTMENTS.** All manhole and inlet castings shall be adjusted to final grade with concrete or poly adjustment rings. Rings shall be installed per manufacturer's recommendations and City of Bismarck Standard Details. Use of other methods to adjust castings to final grade may be allowed with approval by Engineer in Field. All adjustments requiring more than two adjustment rings shall have all rings sealed together.

## SECTION 1206 – CASTING AND ADJUSTMENT

When concrete adjustment rings are used, installation shall include using a concrete glue between all rings.

Casting adjustments for 72” and larger inlets shall use concrete adjustment rings only.

### **1206-4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107 and as follows:

**1206-4.1 ADJUST VALVE BOX IN ASPHALT PAVEMENT.** Valve boxes contracted under this bid item which are found to be located outside of concrete or paved areas, such as in street boulevards, shall be measured and paid for at one-half the unit price if no bid price for adjust valve box in unpaved area is contracted.

**1206-4.2 ADJUST VALVE BOX IN CONCRETE.** Valve boxes contracted under this bid item which are located outside of concrete or paved areas, such as in street boulevards, shall be measured and paid for at one-half the unit price if no bid price for adjust valve box in unpaved area is contracted.

## SECTION 1207 – GEOSYNTHETICS

### 1207-1 DESCRIPTION

Geosynthetics shall consist of geogrids or geotextile fabrics.

The work shall consist of furnishing and installing geosynthetic materials at the locations and dimensions shown in the contract documents, or as directed by the ENGINEER.

### 1207-2 MATERIAL

**1207-2.1 GENERAL.** Package, label, identify, handle, and store geosynthetic according to ASTM D4873. Each geosynthetic roll shall be wrapped with a material that will protect the roll, including the ends of the rolls, from any damage due to shipment, water, sunlight, and contaminants. Protective wrapping shall be maintained during periods of shipment and storage.

Certificate of compliance shall be submitted and approved by the ENGINEER prior to any placement of the geosynthetic material.

**1207-2.2 GEOGRID.** Geogrid shall be a geosynthetic material formed by a regular network of integrally connected elements with apertures of sufficient size to allow interlocking with surrounding soil, stone, or other geotechnical material to function primarily as reinforcement.

Geogrid shall be dimensionally stable and able to retain its geometry under manufacture, transport, and installation stresses.

The CONTRACTOR shall submit data sheet, product sample approximately 4 inches by 7 inches or larger, and certification from the manufacturer that the geogrid product supplied meets the following requirements. The CONTRACTOR shall submit manufacturer's installation instructions and general recommendations. The manufacturer's certificate shall certify that the furnished geogrid meets minimum average roll values (MARV) based on test data from an independent testing laboratory. All geogrids supplied shall be clearly labeled as meeting all specified minimum values and as being from the same production run.

Geogrid Properties	Test Method	Geogrid
Ultimate Tensile Strength <sup>1</sup> ,	ASTM D 6637	1,000
Tensile Strength <sup>1</sup> , 2% strain,	ASTM D 6637	400
Tensile Strength <sup>1</sup> , 5% strain,	ASTM D 6637	800
Junction Strength, lb, min	GRI <sup>2</sup> GG2	25

SECTION 1207 – GEOSYNTHETICS

UV Resistance (after 500 hrs), % Strength Retained	ASTM D 4355	70
Aperture Size, inch	Direct	0.5 – 1.5
<sup>1</sup> Strength values represents weakest principal direction		
<sup>2</sup> Geosynthetic Research Institute.		

**1207-2.3 GEOTEXTILE FABRIC.** Geotextile fabric shall be a fabric consisting of polymeric filament or yarns such as polypropylene, polyethylene, polyester, polyamide, or polyvinylidene chloride. The filaments or yarns shall be formed into a stable network so they retain their relative position to each other. The CONTRACTOR shall submit data sheet, product sample approximately 4 inches by 7 inches or larger, and certification from the manufacturer that the fabric product supplied meets the following requirements. The CONTRACTOR shall submit Manufacturer’s installation instructions and general recommendations. Riprap fabric shall be nonwoven geotextile fabric. The geotextile shall be inert to commonly encountered chemicals and meet the properties in the following table:

Fabric Properties	Test Method	Separation	Underdrain	RipRap	Reinforcement
Ultimate Grab Strength <sup>1</sup> , lbs, min	ASTM D 4632	180	180	200	350
Ultimate Grab Elongation <sup>1</sup> , %	ASTM D 4632	N/A	N/A	15 (min)	25 (max)
Trapezoid Tearing Strength, lbs, min (any direction)	ASTM D 4533	50	50	50	100
Static Puncture Strength, lbs, min	ASTM D 6241	405	435	435	1000
AOS less than mm, (greater than US STD. Sieve)	ASTM D 4751	0.212 (70)	0.3 (50)	0.3 (50)	0.6 (30)
Permittivity, sec <sup>-1</sup> , min	ASTM D 4491	0.1	0.5	0.2	0.05
UV Resistance (after 500 hrs) % min Strength Retained	ASTM D 4355	70	70	70	70
Sewn-Seam Strength, lbs	ASTM D 4632	160	160	180	310
<sup>1</sup> Strength values represents weakest principal direction					

**1207-3 CONSTRUCTION REQUIREMENTS**

**1207-3.1 GENERAL.** The CONTRACTOR shall furnish all labor, materials, and equipment necessary for completion of all work as shown on the plans and specified herein. All work shall be subject to the inspection and approval of the ENGINEER. A representative of the geosynthetic material manufacturer shall be available to be on site to provide technical assistance as required by the CONTRACTOR or ENGINEER.

The CONTRACTOR shall prepare the surface as indicated on the plans or as directed by the ENGINEER. The surface receiving the geosynthetic material shall be smooth and free of stones, sticks, and other debris or irregularities that might puncture or tear the geosynthetic material. The geosynthetic material shall be installed in accordance with the lines and grades as shown on the plans. The geosynthetic material shall be placed free of wrinkles and shall be protected at all times during construction. Construction equipment shall not be operated on the geosynthetic material.

**1207-3.2 GEOGRID.** Longitudinal and transverse joints shall, be overlapped a minimum of one foot or as directed by the ENGINEER or manufacturers recommendations. Overlap joints shall be secured together with plastic tires, placement of aggregate, or approved method to prevent wrinkling or movement. Aggregate placement or mechanically tied transverse joints shall be tied at 3-foot intervals and longitudinal joints at 15-foot intervals. Placement of geogrid around corners may require cutting a diagonal and lapping. Geogrid shall be pinned at the beginning of the backfill section or approved method to prevent the geogrid from moving. The beginning of each new roll shall be placed beneath the previous roll to prevent the advancing fill from lifting the geogrid. Geogrid end overlaps shall be staggered at least 10-feet from other end in adjacent rolls. Geogrid shall be kept taut at the beginning of the backfilling section but not restrained from stretching or flattening.

Torn or damaged geogrid shall be repaired at no additional cost. Repair areas shall be lapped a minimum of 3 feet in all directions. Each side of the repaired geogrid shall be mechanically tied to the existing geogrid.

**1207-3.3 GEOTEXTILE FABRIC.** Overlap joints shall be tied together per manufacture's recommendations or approved method. Placement of fabric around corners may require cutting a diagonal and lapping. The fabric shall be secured using pins or manufacturer's recommended methods to hold the fabric in place during the construction activities. The beginning of each new roll shall be placed beneath the previous roll to prevent the advancing fill from lifting the fabric. Fabric end overlap shall be staggered at least 10 feet from other end in adjacent rolls. Fabrics shall be kept taut at the beginning of the backfilling section but not restrained from stretching or flattening. Torn or punctured geotextile fabric shall be patched with minimum overlap of 3 feet in all directions. Patches shall be secured around the perimeter with pins. No allowances shall be made for overlap or repairs.

Fabric shall not be left uncovered for longer than 5 days. Fabric that is not covered within 5 days shall be removed and replaced at the CONTRACTOR's expense.

- a. **Geotextile Reinforcement Fabric.** Reinforcement shall be unrolled parallel to the centerline of the road and shall be placed as shown in the plans. The fabric shall be placed such that it is taut and pinned, using a minimum of 6-inch pins, or as directed by the ENGINEER. The pins shall be placed at a nominal 15 foot spacing along all edges

## SECTION 1207 – GEOSYNTHETICS

and at all corners, prior to placing any material on the fabric.

The fabric shall be overlapped a minimum of 2-feet at all splices or joints or as directed by the ENGINEER or manufacture's recommendations.

- b. Geotextile Separation Fabric.** When placing the fabric, the geotextile shall be unrolled in line with the placement of the new aggregate. The fabric shall not be dragged across the subgrade. Separation fabric shall be secured according to manufacturer's recommendations.

The fabric shall be overlapped a minimum of 2 feet at all splices or joints or as directed by the ENGINEER or manufacturer's recommendations.

- c. Geotextile Underdrain Fabric.** After the fabric had been secured in place per manufacturer's recommendations, the aggregate shall be deposited by methods that will not tear, puncture, or reposition the fabric. The aggregate shall not be dropped on the fabric from a height greater than 3 feet.

The fabric shall be overlapped a minimum of 1 foot at all splices or joints or as directed by the ENGINEER or manufacturer's recommendations.

- d. Geotextile RipRap Fabric.** When the fabric is used for scour or stream bank protection it shall be placed loosely and be unrolled in the direction of the anticipated water flow. Riprap fabric overlaps shall be pinned in place at 3-foot intervals.

The fabric shall be overlapped a minimum of 3 feet at all splices or joints or as directed by the ENGINEER or manufacturer's recommendations.

The riprap or cover material shall be deposited and spread over the fabric by methods that do not tear, puncture, or reposition the fabric. Riprap stones shall not be dropped on the fabric from a height greater than 3 feet. Stones shall not be rolled along the fabric. Placement of the stones shall begin at the base of the slope and at the center of the geotextile covered area.

**1207-3.4 AGGREGATE SUBBASE PLACEMENT.** Aggregate subbase shall be placed on the geosynthetic material in lifts and compacted as directed in Section 302. Aggregate shall be placed, spread, and compacted in such a manner that minimizes the development of wrinkles or movement in the geosynthetic material. Before placing aggregate material on the geosynthetic material, the CONTRACTOR shall demonstrate that the placement method will not damage the geosynthetic material. The ENGINEER may order the removal of at least 4 square yards of material to inspect for damage to the geosynthetic material. Tears or rips in the geosynthetic material shall be repaired.

A minimum loose fill aggregate thickness of 6 inches, or as directed by the ENGINEER, is required prior to the operation of tracked vehicles over the geosynthetic material. Turning of tracked vehicles shall be kept to a minimum to prevent tracks from displacing

## SECTION 1207 – GEOSYNTHETICS

the fill and damaging the geosynthetic material. Sudden braking and sharp turning movements shall be avoided.

### **1207-4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107 and as follows:

No allowance or payment shall be made for overlaps or repairs.

## **SECTION 1208 – CHAIN LINK FENCING**

### **1208-1 DESCRIPTION**

This item covers the requirements for furnishing materials and constructing new chain-link fences and gates in accordance with the details included herein and as shown on the plans.

The fence shall be the product of a manufacturer who has demonstrated by actual installations of a similar nature that its product is of the type required. The CONTRACTOR shall include all supplementary parts necessary or required for a complete and satisfactory installation within the true meaning and intent of the drawings. All runs of the fence shall present the same general appearance, and the product of one manufacturer only will be accepted, except for items which do not influence the appearance of the completed fence. No used, rerolled, or open seam steel shall be permitted in posts, gate frames, rails, or braces.

### **1208-2 MATERIALS**

**1208-2.1 FABRIC.** The chain-link fence fabric shall conform to AASHTO M181, Type 1. The size of mesh shall be 2 inches, and the wire shall be No. 9 gauge basic open hearth steel hot dip galvanized after weaving with a minimum of 1.20 ounces of zinc per square foot of uncoated wire surface. The wire shall have a minimum tensile strength of 80,000 psi and shall be standard finish with the top and bottom selvage knuckled.

**1208-2.2 WIRE FABRIC TIES.** Wire fabric ties shall be No. 9 gauge hot dip galvanized steel wire, conforming to ASTM A112, or No. 9 gauge aluminum ties, spaced 12 inches center to center on all posts and 24 inches center to center on all rails.

**1208-2.3 POSTS, RAILS, AND BRACES.** All posts, rails, and braces shall be hot dipped galvanized steel in accordance with AASHTO M181, Grade 2. Line and brace posts shall be 2-inch O.D., 2.75 pounds per linear foot for fabric 6 feet or less, and 2 3/8-inch O.D., 3.65 pounds per linear foot for fabric from 7 feet to 10 feet. Corner posts shall be 2 3/8-inch O.D., 3.65 pounds per linear foot for fabric 6 feet or less, and 2 7/8-inch O.D., 5.79 pounds per linear foot for fabric from 7 feet to 10 feet. Top rails and braces shall be 1 5/8-inch O.D., 2.27 pounds per linear foot for all sizes fabric. Each brace section shall be diagonally trussed with 3/8-inch round hot dip galvanized steel rod with truss tightener and fittings. All posts shall be furnished with tops and required fittings for attaching fabric and rail. Fittings shall be of malleable iron or pressed steel.

**1208-2.4 MISCELLANEOUS FITTINGS AND HARDWARE.** Miscellaneous fittings and hardware shall be of design standard with the manufacturer. Miscellaneous fittings and hardware shall be zinc-coated steel.

## SECTION 1208 – CHAIN LINK FENCING

**1208-2.5 WELDING.** Structural members of gates which are in contact shall be fully welded by a method that will procure a continuous weld on all sides and faces of joints at exposed edges. Surplus welding material shall be removed. All factory or field welds shall be coated with a rust preventive primer and a second coat of paint.

**1208-2.6 CONCRETE.** Concrete for posts shall be a 6 bag mix of approved materials.

### 1208-3 CONSTRUCTION REQUIREMENTS

**1208-3.1 GENERAL.** The fence shall be constructed in accordance with the details on the plans and as specified herein using new materials, and all work shall be performed in a workmanlike manner satisfactory to the ENGINEER. Prior to the beginning of the work or upon the request of the CONTRACTOR, the ENGINEER shall locate the position of the work by establishing and marking the property line or fence line. When directed, the CONTRACTOR shall span the opening below the fence with barbed wire fastened to stakes of the required length at locations of small drainage ditches where it is not practical to conform the fences to the general contour of the ground surface, as required. The new fence shall be permanently tied to the terminals of existing fences whenever required by the ENGINEER. The finished fence shall be plumb, taut, true to line and ground contour, and complete in every detail. When directed, the CONTRACTOR shall be required to stake down the chain link fence at several points between posts.

**1208-3.2 CLEARING FENCE LINE.** The site of the fence shall be sufficiently cleared of obstructions, and surface irregularities shall be graded so that the fence will conform to the general contour of the ground. The fence line shall be cleared to a minimum width of 2 feet on each side of the centerline of the fence. This clearing shall consist of the removal of all stumps, brush, rocks, trees, or other obstructions which will interfere with proper construction of the fence. Stumps within the cleared area of the fence line shall be grubbed or excavated. The bottom of the fence shall be placed a uniform distance above the ground as specified on the plans. When shown on the plans, or as directed by the ENGINEER, the existing fences which coincide with or are in a position to interfere with the new fence location shall be removed by the CONTRACTOR as a part of the construction work, unless such removal is listed as a separate item in the bid schedule. All holes remaining after post and stump removal shall be refilled with suitable soil, gravel, or other material acceptable to the ENGINEER and shall be compacted properly with tampers.

The work shall include the handling and disposal of all material cleared, excavated, or removed, regardless of the type, character, composition, or condition of such material encountered.

**1208-3.3 INSTALLING POSTS.** All posts shall be spaced not more than 10 feet apart as shown on the plans. Terminal (end, corner, pull, and brace) and gate posts shall be set 36 inches in concrete bases as shown on the plans. All line posts shall be set 30 inches in concrete bases as shown on the plans. CONTRACTOR may optionally

## SECTION 1208 – CHAIN LINK FENCING

choose to direct drive line end or corner posts in lieu of concreting. Line posts shall be driven to a minimum depth of 48-inches for fencing up to 8 feet in height. Corner or end posts shall be driven to a minimum depth of 60-inches for fencing up to 8 feet in height. Pull, brace, and gate posts shall be concreted for all fencing. The top of the concrete bases shall be slightly above the ground, trowel finished, and sloped to drain away from the posts. Holes of full depth and size for the concrete bases for posts shall be dug to the size and depth as shown on the plans. All post settings shall be done carefully so that all posts shall be vertical and in true alignment and rigidly secured in position.

On terminal (end, corner, pull, and brace) and gate posts, the post tops and brace rail clamps around the posts shall be placed before setting the posts in concrete bases. In setting the gate posts, great care must be taken to make sure gate posts are set the exact distance apart as shown on the plans. For example, posts for a 6-foot gate must be set so as to leave an opening exactly 6 feet wide. A line drawn across from the top of one gate post to the other must be level, regardless of the grade at the ground line. If the ground is not level, the upgrade gate post shall be set first to get the proper height for the downgrade gate post. The concrete bases for end, corner, pull, brace, and gate posts shall be placed first and allowed to cure for 7 days. The concrete bases for line posts shall be allowed to cure for 3 days. Stretcher bar bands and truss bands as specified on the plans shall be spread and slipped on end, corner, pull, brace, and gate posts as the next operation. Post tops are then inserted on all other posts. No extra compensation shall be made for rock excavation. Rock excavation shall not be grounds for extension of time.

**1208-3.4 INSTALLING TOP RAILS.** To start the installation, a length of top rail shall be run through the first couple of post tops; a rail clamp shall be assembled on the end, corner, or gate post, as the case may be. The end of the rail already placed shall be butted into the clamp and fastened. The top rail shall be installed along the run of the fence and the various sections joined with sleeve couplings. At not more than every 100 feet, an expansion coupling shall be placed to take care of expansion and contraction of the rail. The rail shall be clamped in the end, corner, or gate post at the end of the run of the installation of top rail. The fence shall be constructed in such a manner that the top rail appears straight on line and grade or flows smoothly over contours and/or around curves.

**1208-3.5 INSTALLING BRACES.** All horizontal braces shall be attached together with truss rods at all terminal (end, corner, and pull) and gate posts to the brace posts as shown on the plans.

**1208-3.6 INSTALLING FABRIC.** The fabric shall be unrolled on the outside of the fence line with the bottom edge of the fabric against the posts. The various rolls shall be spliced by bringing the ends close together and weaving in a picket in such a way that it will engage both of the roll ends and catch with each twist each separate mesh of the end pickets of both rolls of fabric. The fabric shall be raised and tied loosely to the top rail with a temporary tie wire at intervals of about 20 feet. The fabric shall be installed by a method approved by the ENGINEER. One method used is given below.

## SECTION 1208 – CHAIN LINK FENCING

- a. At end, corner, or gate posts, the stretcher bar shall be slipped through the end picket of the fabric and the stretcher bar bands at the same time. Then the bolts in the stretcher bar bands shall be tightened. Additional rolls of fabric shall be spliced and placed as the erection progresses along the fence.
- b. In the long sections, the fence shall be stretched at intervals of about 100 feet. After the stretching is complete, the fabric shall be tied to the top rails with ties securely clinched at the back of the rail. The fastenings shall be spaced not more than 24 inches on centers for the top rail.
- c. The fabric shall be attached to the line posts with ties securely clinched to the back of the line posts. The fastenings shall be spaced not more than 12 inches on centers for line posts. The topmost tie shall be placed on the line post as near the top of the fabric as possible and the lowest tie as near the bottom of the fabric as possible.
- d. At terminal (end, corner, and pull) and gate posts, the fabric shall be fastened with stretcher bars and bands. The fastenings shall be spaced not more than 12 inches on centers for terminal (end, corner, and pull) and gate posts. The topmost band shall be placed on these posts as near the top of the fabric as possible and the lowest band as near the bottom of the fabric as possible.

Standard chain link fence stretching equipment shall be provided for stretching the fabric before tying it to the rails and posts. The stretching and tying operations shall be repeated about every 100 feet until the run of fence is completed. Equipment of one type for performing the stretching operation may be composed of 4 pieces of lumber (2x4s or larger) cut into a slightly shorter length than the width of the fabric. The pieces shall be bored for 6 bolts of about 1/2-inch or 5/8-inch diameter and shall be assembled as shown on the Plans. 1 pair shall be used for stretching the fabric, and both pairs shall be used for making a closure of a run of the fence.

Before making a closure, the other end of the run shall be fastened to the end, corner, or gate post as described previously. The operation of making a closure of a run shall be as follows: The stretching equipment as described above shall be clamped on the ends of the fabric parallel to each other and about 5 feet apart when the tension is first applied. The stretching shall continue until the slack has been removed from both sections of the fabric. If the ends overlap, the fabric shall be cut to match. The ends shall be joined by the insertion of a picket similar to the method of connecting 2 rolls of fabric.

**1208-3.7 INSTALLING GATES.** The gates shall be hung on gate fittings as shown on the plans. Gates shall be erected to swing in the direction indicated and shall be provided with gate stops as specified or as shown on the Plans. All hardware shall be thoroughly secured, properly adjusted, and left in perfect working order. Hinges and diagonal bracing in gates shall be adjusted so that the gates will hang level. All gates shall be furnished with a closure which may be secured with a padlock.

## SECTION 1208 – CHAIN LINK FENCING

**1208-3.8 EXISTING FENCE CONNECTIONS.** Wherever the new fence joins an existing fence, either at a corner or at the intersection of straight fence lines, a corner post with a brace post shall be set at the junction and braced the same as herein described for corner posts or as shown on the plans.

If the connection is made at other than the corner of the new fence, the last span of the old fence shall contain a brace span.

### **1208-4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107 and as follows:

**1208-4.1 CHAIN LINK FENCE.** Chain Link Fence shall be measured from outside to outside of corner, end, or gate post.

## **SECTION 1209 – SANITARY SEWER AND WATER SERVICE CONNECTIONS**

### **1209-1 DESCRIPTION**

This item shall consist of furnishing and installing sanitary sewer and water service connections from the main lines located in public easements or rights-of-way, such as streets and alleys, up to within five feet of a building foundation or meter pit . The materials, equipment, and construction methods shall be in full compliance with the ordinances of the City of Bismarck, the North Dakota State Plumbing Code, regulations set forth by the North Dakota Department of Environmental Quality (NDDEQ), and in accordance with these specifications and standard details.

### **1209-2 MATERIALS**

**1209-2.1 POLYVINYL CHLORIDE SEWER PIPE.** PVC sewer pipe and fittings shall conform to the requirements of ASTM D3034 for type PSM, PVC sewer pipe and fittings and shall have an SDR of 35 which shall be stamped on the pipe. PVC sewer pipe with a bury depth of equal to or greater than 18 feet shall have an SDR of 26. Gasketed type joints on PVC pipe and fittings are preferred. Use of PVC sewer pipe joint cement must be approved by the ENGINEER prior to construction. The polyvinyl chloride sewer pipe joint cement shall consist of a viscous brushable solution of polyvinyl chloride in suitable active solvents. The cement shall be purchased from the pipe manufacturer and used in accordance with the manufacturer's instructions. It shall produce a joint of sufficient strength to permit normal installation handling within 5 minutes after jointing when exercising reasonable care.

**1209-2.2 JOINT MATERIALS.** Joint materials for sewer pipe shall conform to Section 801.

**1209-2.3 COPPER WATER PIPE.** Copper water pipe shall be 1" to 2" only and conform to ASTM B88, Type K Soft copper. Copper water service connections shall be flared or compression type Pack Joint coupling as manufactured by Mueller, Ford or approved equal.

**1209-2.4 POLYETHYLENE WATER PIPE.** Polyethelene (PE) water service pipe shall be 1" to 2" only. PE pipe shall be manufactured from ultra-high molecular weight PE of virgin materials and shall meet the requirements of Type III class "C" category 5-P34 PE as defined in ASTM D1248 with a working pressure of 250 psi.

PE pipe shall conform to ASTM D2239 with a SIDR of 7 or conform to ASTM D2737 with a SIDR of 9. If PE pipe with SIDR of 9 is used, pipe shall be 1¼" CTS in lieu of 1" IPS nominal size.

PE water service connections shall be compression type Pack Joint couplings as manufactured by Mueller, Ford or approved equivalent and shall include the installation of a stainless steel insert stiffener at all connections. The use of other couplings shall not be permitted.

## SECTION 1209 – SANITARY SEWER AND WATER SERVICE CONNECTIONS

**1209-2.5 CORPORATION STOP.** Corporation stops shall be Mueller, McDonald, Ford, or approved equivalent and shall be a ball valve with AWWA tapered threads. No plug or key style corporation stops will be allowed.

**1209-2.6 CURB STOP.** Curb stops shall be Mueller, McDonald, Ford, or approved equivalent and shall be a straight ball valve, without drain, having a Minneapolis Pattern. Curb stops shall be installed on a 6(six)-inch square by 4(four)-inch thick concrete pad.

**1209-2.7 CURB BOX.** Curb boxes shall be McDonald No. 5622 or Mueller No. H- 10302 (1½-inch diameter upper section) for all size curb stops, or approved equivalent. Stationary rods shall not be installed with curb stop boxes. The length of the curb box extended shall be 8 feet. The curb stop box cap shall have a pentagon cast iron threaded plug.

All curb boxes shall be encased with 8-mil linear low-density (LLD) polyethylene film in accordance with ANSI/AWWA C105/A21.5. All encasements shall be considered incidental.

**1209-2.8 CONCRETE.** Concrete for pipe cradles and saddles shall conform to the requirements of Section 501.

**1209-2.9 TAPPING SLEEVE WITH TAPPING GATE VALVE.** For connecting to pipe sizes 6 inches to 24 inches, the tapping sleeve shall be stainless steel with a stainless steel flange and bolts and shall conform to the “Smith Blair” Type 663 or “Romac” Type SST, or approved equivalent. For connections to pipe sizes 24 inches or larger, the tapping sleeve shall be epoxy lined and coated with stainless steel bolts and shall conform to the “Smith Blair” Type 622 Split Sleeve with O-Ring Seal. The tapping valve shall conform to Section 901 for Gate Valves.

The City of Bismarck Public Works Department will tap the water main at a charge to the CONTRACTOR. The CONTRACTOR shall be responsible for all other work connected with installation of the tapping sleeve and valve, including the necessary space around the water main required for the tapping machine and assisting the Public Works Department in positioning the tapping machine.

**1209-2.10 TAPPING SADDLE WITH CORPORATION VALVE.** Corporation taps made into all material, size, and class water mains shall be reinforced with a tapping saddle.

Tapping saddles used on PVC water main shall provide full support around the circumference of the pipe and provide a bearing area of sufficient width along the axis of the pipe 2 inches minimum, ensuring that the pipe will not be distorted when a saddle is tightened.

Tapping saddles for connecting to PVC, ductile iron, cast iron, and sand cast iron water main up to 12 inches in diameter shall be one of the following: (a) Romac Style 306, (b) PowerSeal Model 3412, (c) Smith Blair Series 370, (d) Ford FS313 or (e) approved equivalent.

## SECTION 1209 – SANITARY SEWER AND WATER SERVICE CONNECTIONS

Tapping saddles for connections to PVC, ductile iron, cast iron, asbestos cement, and sand cast iron water main over 12 inches in diameter shall be Romac Style 305 or approved equivalent.

Tapping saddles for connections to HDPE water main shall be mechanical saddles type Ford FS313. No Belleville washer style mechanical saddles or electorfused saddles will be allowed.

Tapping saddles for prestressed concrete water mains shall be approved by the ENGINEER.

Tapping saddles shall be installed according to manufacturer's installation instructions. The tapping saddle bolts shall be torqued using a calibrated torque wrench with a handle at least 12 inches in length. The CONTRACTOR should be prepared to show certification of torque wrench calibration at the request of the ENGINEER.

### **1209-3 CONSTRUCTION REQUIREMENTS**

**1209-3.1 GENERAL.** Construction requirements shall conform to Section 801 for sewer service connections and Section 901 for water service connections. All pipe and fittings shall be installed in accordance with the manufacturer's recommendations unless otherwise specified herein. All copper water service lines shall be constructed "snaked" within the trench.

On new construction, for each sewer stubout, a 2x2 inch wood marker shall be placed a minimum of one foot from the end of the sewer stubout, shall extend vertically and plumb to not less than two feet above the existing surrounding ground, and painted green.

On new construction, for each water curb stop , a metal T-Post marker shall be placed a maximum of one foot from the curb stop box, extended vertically to a minimum of three feet above the existing surrounding ground, and painted blue.

The CONTRACTOR shall be responsible for maintaining the markers until the project has been accepted by the ENGINEER. The cost of the stubout markers shall be considered incidental to other bid items.

When connecting to a sewer main and a wye is not available, the connection shall be made using an Inserta Tee manufactured by Inserta Fittings Co., or approved equivalent. A factory-assembled wye may be cut in using gasketed repair couplers. When connecting to VC sewer main, repair couplers manufactured by Fernco, Inc. with Shear Guard by GPK, or approved equivalent, may be used.

Bedding material in accordance with Section 801 shall be placed in the trench, prior to laying any type of sewer pipe, 2 inches below bottom of pipe up to 6 inches or smaller, 4 inches when pipe used is 8 inches or larger. Bedding material shall be installed to the centerline of the pipe and the full width of the excavating trench.

## SECTION 1209 – SANITARY SEWER AND WATER SERVICE CONNECTIONS

**1209-3.2 SANITARY SEWER RISERS.** When the depth of the sewer exceeds 12 feet, risers shall be installed. Risers shall be sufficiently long to reach within 10 feet of the top of curb elevation. When risers are five feet or greater, 1¼-inch crushed rock shall be used to encase the wye and support the vertical bend. Risers shall be laid on a slope not to exceed 2:1 vertical to horizontal.

**1209-3.3 SANITARY SEWER SERVICE BENDS.** Sanitary sewer service bends shall be compatible with the type of sewer service pipe and wye branch selected to provide a 90 degree angle between the sewer mainline and sewer service line.

**1209-3.4 DISCONNECT WATER SERVICE LINE.** Disconnecting a water service line shall consist of turning off the corporation stop at the main and disconnecting the pipe after the corporation stop.

### **1209-4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107 and as follows:

**1209-4.1 SEWER SERVICE PIPE.** On new construction, the sewer service pipe shall be measured from centerline of sewer main to plugged end of service connection. On reconstruction projects, the sewer service pipe shall be measured from end of the wye to the end of the existing sewer service pipe.

**1209-4.2 WATER SERVICE PIPE.** On new construction, the water service pipe shall be measured on an in-line basis from the centerline of the water main at the water service connection to the end of the water service pipe. On reconstruction projects, the water service pipe shall be measured on an in-line basis from the water service connection directly to the end of the existing water service pipe.

**1209-4.3 WATER SERVICE CONNECTION.** Water service connections shall include one tapping sleeve, one tap to the water main, and one corporation stop (when required). The connection shall be measured as a combined unit.

**1209-4.4 CURB STOP AND BOX.** The curb stop and curb box shall be measured as a combined unit.

## **SECTION 1210 – PAVEMENT MARKING**

### **1210-1 DESCRIPTION**

This work consists of furnishing and installing specified pavement markings and related items in accordance with these Specifications at the designated locations as shown in the plans or as directed by the ENGINEER.

All pavement marking installation, materials, and construction requirements not covered in these specifications shall be in accordance with Section 762 of the latest edition of the *Standard Specifications for Road and Bridge Construction*, North Dakota Department of Transportation.

### **1210-2 MATERIALS**

**1210-2.1 GENERAL.** All paint and glass beads shall be preapproved by the North Dakota Department of Transportation Materials and Research Division.

**1210-2.2 GLASS BEAD CERTIFICATION.** The manufacturer shall furnish one copy of a certificate for each lot of the material furnished, giving the properties of the beads, and certifying that they meet the required specifications. The affidavit shall show designation of the sample, lot number, and date of manufacture.

**1210-2.3 PREFORMED PATTERNED TAPE PAVEMENT MARKING.** Preformed Patterned Tape Pavement Markings shall be 380IES as manufactured by 3M, or an approved equivalent, and shall be approved by the ENGINEER prior to ordering. The Preformed Patterned Tape Pavement Markings shall be installed using primer and as recommended by manufacturer.

**1210-2.4 PREFORMED PATTERNED THERMOPLASTIC PAVEMENT MARKING.** Preformed Patterned Thermoplastic Pavement Markings shall be Preformed Thermoplastic PreMark with Vizigrip as manufactured by Ennis-Flint, or 125mil Optamark as manufactured by Geveko Markings, or 3M Durable Retroreflective Liquid Pavement Markings Series 500, or approved equivalent, and shall be approved by the ENGINEER prior to ordering.

Preformed Patterned Thermoplastic Pavement Markings installed on asphalt pavements shall be 125 +/-5 mils thick. The thermoplastic pavement markings installed on concrete pavements shall be 125 +/- 5 mils thick. The thermoplastic pavement markings shall be installed as recommended by the manufacturer.

**1210-2.5 EPOXY WET REFLECTIVE PAVEMENT MARKING LINE.** Epoxy pavement markings material shall conform to the NDDOT Standard Specifications Section 880.02 Epoxy Pavement Marking Paint. Epoxy painted pavement markings shall have 3M Connected Roads All Weather Elements Series 70 for Epoxy Pavement Markings,

## SECTION 1210 – PAVEMENT MARKING

Visimax Plus Type IV EC/AC White and Yellow Glass beads, or an approved equivalent or alternative.

### **1210-2.6 PREFORMED PATTERNED TAPE CONTRAST PAVEMENT MARKING.**

Prefomed Patterned Contrast Tape Pavement Marking shall be as manufactured by 3M series 380IES-5 Stamark High Performance Contrast Marking Tape or approved equivalent, and shall be approved by the ENGINEER prior to ordering.

### **1210-3 CONSTRUCTION REQUIREMENTS**

**1210-3.1 PAVEMENT MARKING CERTIFICATION.** All CONTRACTORS installing pavement marking material for the City shall provide a crew of which 50 percent are trained and “certified” by the manufacturer. “Certified” CONTRACTORS must be able to provide proof of the certification through a manufacturer-provided ID card or certification paper.

**1210-3.2 PAINTED PAVEMENT MARKING.** Painted pavement marking shall be installed as soon as the new pavement has been placed and traffic control devices have been removed. All longitudinal painted pavement marking lines shall be installed with a striping truck as described in Section 1210-3.4, unless approved by the ENGINEER. The painted pavement marking shall have a thickness of between 18 mils and 21 mils.

### **1210-3.3 PAINTED PAVEMENT MARKING MONITORING SYSTEM**

**DESCRIPTION.** All striping trucks shall require a computerized data logging system (DLS) for monitoring the application of pavement marking to the roadway. DLS is an addition to pavement marking equipment to record data relating to pavement marking installation.

All painted pavement marking operations shall be in accordance with NDDOT Standard Specifications for Road and Bridge Construction Section 762. The system shall document for a minimum length of 300 linear feet. The following data shall be included in the documentation from the DLS:

- a. Application vehicle speed to nearest 0.1 mph.
- b. Weight (lbs) and/or volume (gal as measured through a piston displacement pump mechanism) of paint material used by color.
- c. Weight (lbs) of reflective material used.
- d. Pavement surface temperature (°F).
- e. Air temperature (°F).
- f. Dew point (°F).
- g. Humidity (%).
- h. The system shall record the average material application rates and material thickness calculated over the section painted.

An electronic or printed record of the data shall be provided to the ENGINEER upon request. The ENGINEER may determine that more frequent submission is

## SECTION 1210 – PAVEMENT MARKING

necessary, particularly if equipment malfunctions occur. Either the printed or electronic records shall be produced in their final form prior to the records being removed from the pavement marking equipment (i.e., the CONTRACTOR presents this to the ENGINEER in the field). If only one record is produced at the pavement marking equipment, the other may be produced in an office. However, the first record shall be presented to the ENGINEER prior to any of the data entering an office environment.

The electronic record shall be a comma or spaces delimited text file, adequate for insertion into a computerized spreadsheet software package or a spreadsheet format acceptable to the ENGINEER.

The CONTRACTOR shall provide the ENGINEER the above records for all longitudinal non-handwork lines painted.

The CONTRACTOR shall have equipment with functional DLS equipment. It shall be operational, calibrated, and in use during pavement marking operations.

The CONTRACTOR shall provide the ENGINEER the DLS manufacturer's recommendations for equipment calibration frequency and provide certification that the equipment meets manufacturer's recommended calibrations.

A 100-foot distance shall be traveled prior to the start of pavement marking operations to verify the physical and electronic measurement of distance traveled is consistent.

DLS shall not be measured or paid and shall be incidental to other bid items.

**1210-3.4 SURFACE PREPARATION.** Prior to the placement of any preformed plastic pavement marking that cannot be rolled into hot asphalt, the placement area shall be cleared of debris using a high-velocity compressed air blower with minimum 185 cfm airflow and 120 psi at the air nozzle. The air nozzle shall be no less than 1/2 inch inside diameter commercial grade air compressor. The compressor shall be equipped with a moisture evaporator. A leaf blower shall NOT be an acceptable substitute for compressed air.

**1210-3.5 GROOVING FOR PAVEMENT MARKINGS.** The CONTRACTOR shall groove to make a recess in the pavement surface for the pavement markings.

Epoxy Wet Reflective Pavement Markings shall meet the following tolerances:

Depth	50 mils ± 5 mils
Smoothness	Ridges, within the groove, no more than 6 mils higher than either adjacent valley
Width	Line width plus 1/2 inch

## SECTION 1210 – PAVEMENT MARKING

Length	Line length plus 3 inches per end of line
Line End Tapers	3 inches

All other pavement markings shall meet the following grooving tolerances:

Depth	125 mils ± 5 mils
Smoothness	Ridges, within the groove, no more than 6 mils higher than either adjacent valley
Width	Line width plus 1/2 inch
Length	Line length plus 3 inches per end of line
Line End Tapers	3 inches

For messages, the area grooved shall be the same area as the messages. Grooving a rectangular area to contain the message shall not be allowed unless approved by the ENGINEER. Grooving shall meet the depth requirements specified above. The equipment and method used shall be approved by the pavement marking manufacturer.

The groove shall be made in a single pass dry cut using stacked diamond cutting heads mounted on a floating head with controls capable of providing uniform depth and alignment. The bottom of the groove shall have a fine corduroy finish. Grooves shall be clean and dry prior to pavement marking application. The equipment shall be self-vacuuming, and be capable of vacuuming and containing all dust contaminants from entering the air, and leave the cut groove ready for pavement marking installation. If the ENGINEER in the field deems that the dust collection is not adequate, the ENGINEER may shut down the CONTRACTOR's operation until the problem has been fixed according to the satisfaction of the ENGINEER. The pavement marking shall be placed in the grooves the same day as the pavement is grooved.

**1210-3.6 OBLITERATION OF PAVEMENT MARKINGS.** Removal of pavement markings shall not permanently damage the surface or texture of the pavement. Where blast cleaning is used for removal of markings or other objectionable material, the sand or other blast material left on the pavement shall be removed immediately. No carbide or diamond tip blades or wheels are allowed on removal equipment. All removal methods shall be demonstrated by the CONTRACTOR and approved by the ENGINEER in the field before removal is allowed.

### 1210-4 MEASUREMENT AND PAYMENT

Measurement and payment shall be as specified in Section 107 and as follows:

## SECTION 1210 – PAVEMENT MARKING

All traffic control necessary for installing the pavement marking items shall be included in the unit price bid.

**1210-4.1 DLS MONITORING SYSTEM.** All manufacturer representation, labor, equipment, reports, and documentation for the DLS monitoring system shall not be measured separately but included in the unit price bid.

**1210-4.2 GROOVED PAVEMENT MARKINGS.** For grooved pavement markings, the markings and grooving shall not be measured separately but included in the unit price bid.

## **SECTION 1211 – TRAFFIC CONTROL**

### **1211-1 DESCRIPTION**

This work consists of furnishing, installing, documentation, and maintaining all required traffic control devices according to an approved traffic control plan or details shown on the plans. This includes specifications providing for watch persons, flaggers, pilot cars, and necessary precautions for protecting the public, the workers, and the work.

The CONTRACTOR must submit a traffic control plan to the ENGINEER for approval at least two weeks prior to setting up the detour closing a roadway.

The CONTRACTOR shall provide, prior to construction, all proposed haul routes to the ENGINEER for approval. The ENGINEER may require a haul road inspection at his discretion.

Press releases shall be submitted to the ENGINEER for review a minimum of three days prior to each change in operation or phase. The CONTRACTOR shall notify the Traffic ENGINEER a minimum of 48-hours prior to implementation of the traffic control plan for a road closure, detour or lane reduction for the issuance of a press release. A press release is required to announce the reopening of a roadway with a detour when not otherwise notified.

The CONTRACTOR is responsible for the placement and maintenance of all work zone signs and barricades during construction. All traffic control devices shall be installed and maintained in a safe and orderly manner complying with the provisions of Chapter 6 of the most recent update of the *Manual on Uniform Traffic Control Devices for Streets and Highways*, U.S. Department of Transportation.

The CONTRACTOR is responsible for maintaining and protecting traffic, the public and the work during a temporary suspension of work.

The CONTRACTOR shall designate a superintendent and an alternate for emergency repair service to traffic control devices. Telephone numbers for these personnel shall be provided to the ENGINEER at the preconstruction meeting. These personnel shall be available at all times to respond to an emergency.

When an emergency occurs and the superintendent and alternate are not available to take protective measures, the CITY may authorize others to do the necessary work and deduct the cost of the work from the CONTRACTOR.

### **1211-2 MATERIALS AND EQUIPMENT**

All materials and construction details not specifically addressed in the Plans, Special provisions, and Construction Specifications for Municipal Public Works, Bismarck, North

## SECTION 1211 – TRAFFIC CONTROL

Dakota shall be in conformance with Section 704 of the most recent edition and supplements of the Standard Specifications for Road and Bridge Construction, North Dakota Department of Transportation, NDDOT CAD Standard Drawings, and the provisions of Chapter 6 of the most recent update of the *Manual on Uniform Traffic Control Devices for Streets and Highways*.

Traffic control devices used on the project will be rated according to the American Traffic Safety Services Association (ATSSA) *Quality Standards for Work Zone Traffic Control Devices*. The definitions of “acceptable,” “marginal,” and “unacceptable” and the evaluation guidelines shall be as defined in ATSSA’s *Quality Standards for Work Zone Traffic Control Devices*.

The ENGINEER retains the right to reject any traffic control device that is considered “marginal” or “unacceptable”. All traffic control devices that are rejected shall be immediately removed from the public right-of-way and replaced with “acceptable” devices.

Payment for traffic control devices, labor, plans, and maintenance shall be measured and paid by the lump sum as “Traffic Control” for each unit.

### **1211-3 CONSTRUCTION REQUIREMENTS**

**1211-3.1 GENERAL.** Traffic Control includes furnishing, installing, and maintaining the required signs, barricades, channelizing devices, flashing arrow boards, and other warning devices, relocating or removing devices as dictated by the work progress, and providing watchpersons/traffic control supervisor to patrol the work.

The CONTRACTOR shall furnish, install, and maintain all required traffic control devices, and shall provide watchpersons and flaggers as necessary to protect the work and to ensure public and workers’ safety. All required traffic control devices shall be available for installation when needed and shall be maintained, relocated, covered, or removed as necessary.

If the CONTRACTOR has not furnished, installed, located, maintained, or removed traffic control devices as required, the ENGINEER may direct work to cease until the deficiencies have been corrected. The ENGINEER may authorize others to do the necessary work and deduct the cost of the work from the CONTRACTOR, if deficiencies are not corrected in a timely manner and pose a risk to public safety.

If the CONTRACTOR’s construction operations or sequence requires additional traffic control devices, such as signing, flashing arrow boards, barricades, channelizing devices or flaggers, they shall be furnished at the CONTRACTOR’s expense and construction operations shall be suspended in that area until the condition is corrected and the required traffic control devices have been installed.

## SECTION 1211 – TRAFFIC CONTROL

Traffic control devices shall be operated only as long as they are needed. Only those devices that apply to existing conditions shall be in place.

**1211-3.2 WORK AREA SIGNING.** Appropriate traffic control devices as shown on the traffic control plan drawings shall be erected and maintained for each type of work area required by the operations. When no details are provided for the particular type of construction situation involved, traffic control devices shall be installed according to the *MUTCD* or as directed by the ENGINEER. No construction work shall be started until the proper traffic control devices for the work area are in place.

When traffic is carried through the construction area, two-way traffic shall be maintained when practicable or when required per the project plans or special provisions. One-way traffic shall be directed by flag persons or maintained under control of an approved traffic signal system. All signs and other traffic control devices shall indicate actual conditions and shall be relocated, removed, or changed, as conditions require. Traffic Control Devices necessary only during hours when work is actually being performed shall be removed or completely covered when no work is in progress.

All channelizing devices shall be reflectorized and be a minimum of 36 inches in height. Non-reflectorized channelizing devices shall not be allowed.

When pedestrian facilities are impacted due to maintenance or construction, signs mounted on pedestrian barricades shall be placed to allow pedestrian traffic to route around the work zone per detail 1211-1. Pedestrians shall be rerouted to pedestrian facilities when feasible. In residential areas the ENGINEER will determine what type of pedestrian guidance is required.

The cost to remove and reset existing traffic signs to accommodate construction shall be included in the price bid for other items.

**1211-3.3 TEMPORARY SUSPENSION.** During a temporary suspension of work, the CONTRACTOR is responsible for maintaining and protecting traffic. When work is suspended for winter and roadways are reopened for normal operations, all traffic control devices shall be removed from the public right-of-way. Resetting of signs removed due to temporary suspension will not be measured for payment.

**1211-3.4 TRAFFIC CONTROL SUPERVISOR.** The CONTRACTOR shall designate a qualified traffic control supervisor. This supervisor shall be in addition to the watchperson. If this traffic control supervisor becomes unavailable on the project, the CONTRACTOR shall designate a qualified replacement supervisor.

**a. Qualifications.** The traffic control supervisor shall:

1. Have completed a NDDOT-approved comprehensive course of study based on Part VI of the *MUTCD* or have completed certification by American Traffic Safety Services Association (ATSSA) as a Traffic Control Supervisor and furnish proof hereof.

## SECTION 1211 – TRAFFIC CONTROL

2. Be familiar with the requirements traffic control plans and specifications.
3. Have a total of at least 12 months field experience with traffic control plans, layouts, and maintenance.
4. Be competent to supervise personnel in traffic control operations.

**b. Duties.** The traffic control supervisor shall:

1. Provide traffic control as required by the plans, specifications, *MUTCD*, or as directed by the ENGINEER.
2. Supervise the installation, operation, inspection, maintenance, and removal of the traffic control system.
3. Correct traffic control devices to reduce potential for conditions that cause erratic vehicle movements, unexpected braking, etc.
4. Monitor and propose changes to improve traffic flow through the work zone.
5. Be accessible to the job site within one hour of notification and be “on call” on a 24-hour basis.
6. Provide the ENGINEER with daily documentation of all traffic control activities.
7. Function as watchperson in his/her absence.

**1211-3.5 WATCHPERSONS.** Watchpersons shall be provided to patrol the project to assure that the traffic control devices are properly placed in accordance with the traffic control plans and standards. The project shall be patrolled a minimum of every 4 hours, including once before 9 a.m. and at least once after 6 p.m. during construction activities, and twice daily, before 10 am and after 4pm on weekends and days when no work is in progress. The CONTRACTOR shall provide written documentation (log or diary) to the ENGINEER of the watchperson’s hours and activities.

The CONTRACTOR shall immediately assist the watchperson, whenever needed, to correct conditions that cause erratic traffic movement, unexpected braking, etc., and erect, repair, replace, or relocate the required traffic control devices. Emergency assistance shall be provided to motorists, when needed, due to roadway conditions. Suspension of watchperson service may be permitted during periods of authorized suspension or after substantial completion of the work, provided the job site is in safe condition.

**1211-3.6 EMERGENCY CONTROL.** Written notification shall be provided to the ENGINEER, the State Police, and local law enforcement agencies of the names, addresses, and telephone numbers of the CONTRACTOR’s Superintendent and an alternate at the preconstruction meeting. Either the Superintendent or the alternate shall be on call for notification of any emergencies that may arise during periods when construction operations are not in progress. Changes in the designation of the superintendent or the alternate shall immediately be made known, in writing, to the ENGINEER and the law enforcement agencies.

The CONTRACTOR’s superintendent or alternate, or traffic control foreman shall meet with the ENGINEER before work commences to review traffic control plans, and shall

## SECTION 1211 – TRAFFIC CONTROL

be available at all reasonable times to periodically discuss modifications to the traffic control plan with the ENGINEER or his representative.

When an emergency occurs and the superintendent or alternate are not available to take protective or corrective measures, the department will authorize others to do the necessary work and deduct the cost of the work from the CONTRACTOR.

**1211-3.7 MAINTENANCE OF TRAFFIC CONTROL DEVICES.** At the time of initial set up and major phase changes, 100 percent of each type of device (signs, barricades, vertical panels, drums, cones, tubular markers, warning lights, arrow panels, etc.) shall be classified as acceptable. The CONTRACTOR shall certify in writing to the ENGINEER that all traffic control devices installed are classified as acceptable.

For signs, barricades, vertical panels, drums, cones, tubular markers, and arrow panels, the number of acceptable devices of each type may decrease to 75 percent of the initial quantity as a result of damage or deterioration during the course of work. The remaining 25 percent of each type of devices may be in the marginal category. Warning lights shall be “acceptable” or “marginal” at the limits defined in the ATSSA Standards. All unacceptable devices found on the job site shall be replaced within 12 hours.

Traffic control devices not covered by the evaluation guidelines shall be maintained to operate effectively and be in good repair.

Traffic control devices shall be cleaned as necessary to remove dirt, mud, or other foreign material which reduces the brightness of the reflectorized sheeting or warning lights.

**1211-3.8 NON-CONFORMANCE.** Any devices found not meeting ATSSA or MUTCD standards shall be removed from site within 24 hours and replaced with proper devices.

Should traffic control be found insufficient or not meeting MUTCD or ATSSA Standards by ENGINEER, the CONTRACTOR shall, upon notification, have 24 hours on collector and local streets and four hours on arterial streets to remedy deficiencies as per the ENGINEER. If deficiencies are not corrected within this time, the ENGINEER may authorize others to perform the necessary work and deduct the invoiced cost of the work plus 20 percent from moneys owed to the CONTRACTOR.

**1211-3.9 FLAGGING.** The garments worn by flaggers shall comply with the American National Standard for High-Visibility Safety Apparel and Headwear ANSW/ISEA 107-2020.

Flaggers shall not be assigned other duties while working as authorized flaggers.

The CONTRACTOR is responsible for providing certified flaggers. The CONTRACTOR will acknowledge in writing, before any flagging work begins on the project, that all flaggers are certified before performing flagging on the project. Certification shall be based on a written examination found at [ndflaggertraining.com](http://ndflaggertraining.com).

## SECTION 1211 – TRAFFIC CONTROL

**1211-3.10 GARMENT REQUIREMENTS FOR ALL PERSONNEL.** All personnel working within city rights-of-way shall wear garments complying with the current ANSI/ISEA 107 standard for Type R, Class 2 (minimum).

### 1211-4 MEASUREMENT AND PAYMENT

Measurement and payment shall be as specified in Section 107 and as follows:

**1211-4.1 TRAFFIC CONTROL.** Traffic Control includes all requirements per Section 1211-3.

Payment (over the lump sum bid for “Traffic Control”) may be authorized for additional traffic control devices if the type or number of such devices requested by the ENGINEER exceeds the requirements indicated by the traffic control plan or when the need for additional traffic control devices is created as a result of contract revisions.

No additional payment will be authorized for additional traffic control devices required as a result of the CONTRACTOR’s method or sequence of operation, whether or not the type of operation is included in the typical work area layouts shown on the traffic control plan sheets.

Traffic Control shall be payment shall be graduated according to the following schedule:

<u>Percent of Bid Price Paid</u>	<u>Contract Requirement</u>
40%	All initial traffic control devices required to start construction have been installed.
50%	Contract is 25% complete.
75%	Contract is 50% complete.
90%	Contract is 75% complete.
100%	Contract is complete.

When a project contains multiple units with individual traffic control bid items for each unit, “Contract” in the above table shall refer to the contract total for the unit to which the bid item applies and the traffic control bid item for each unit shall be paid according to the amount complete within that unit.

When additional traffic control devices are requested by the ENGINEER and qualify for payment, the cost for furnishing and installing such devices will be agreed upon by the ENGINEER and CONTRACTOR prior to installation. If no agreement can be made, the ENGINEER may authorize others to complete the additional work.

The above payments for installation include the cost of removing or relocating the traffic control devices. No additional payment will be made when traffic control devices are covered up, or temporarily taken out of service, and then returned to use.

## SECTION 1211 – TRAFFIC CONTROL

All standard traffic control devices furnished by the CONTRACTOR shall remain the property of the CONTRACTOR.

Flagging shall be included in the bid item “Traffic Control.”

If the CONTRACTOR is required to furnish special non-standard signs not shown on the Plans, payment will be made at invoice price plus 15 percent, and the sign will become the City’s property after it has been removed from service. Payment for sign supports and installation of special signs will be as per payment for additional traffic control above.

## **SECTION 1212 – HIGHWAY POSTS AND SIGNS**

### **1212-1 DESCRIPTION**

This item shall consist of furnishing, fabricating, and installing highway signs, delineators, and supporting structures.

### **1212-2 MATERIALS**

All materials furnished and installed in this work shall be new and shall be per the plans and comply with the following:

- a) NDDOT “Standard Specifications for Road and Bridge Construction”, Current Edition, as revised.
- b) Manual on Uniform Traffic Control Devices (MUTCD), Current Edition, as revised.

All sign faces shall be fabricated as per the plans and the alphabets shown in the MUTCD.

**1212-2.1 CONCRETE.** Concrete shall be as per Section 501.

**1212-2.2 SIGN MATERIAL.** All sign backing material shall be a minimum of 0.1 inches thick unless otherwise noted on the plans.

### **1212-3 CONSTRUCTION REQUIREMENTS**

All installation shall be per the plans and comply with the following:

- a) NDDOT “Standard Specifications for Road and Bridge Construction”, Current Edition, as revised.
- b) Manual on Uniform Traffic Control Devices (MUTCD), Current Edition, as revised, published by the FHWA.

**1212-3.1 SIGN POST INSTALLATION.** When sign installation occurs in a permanent surface, a 4-inch PVC sleeve shall be installed around the post for the thickness of the permanent surface. The sleeve shall be backfilled with loose, clean sand. The cost shall be incidental to sign bid items.

Drive anchors for telescoping perforated tubes supports 2” to 4” above finish grade. The cost shall be incidental to sign bid items.

## SECTION 1212 – HIGHWAY POSTS AND SIGNS

**1212-3.2 LOCATING AND POSITIONING OF SIGNS.** Signs shall be located according to the plans. Installed signs will be inspected at night, if any sign is ineffective at night, the sign shall be replaced at the CONTRACTOR's expense.

**1212-3.3 ROAD CLOSED – TYPE III SINGLE BARRICADE.** Shall consist of installing a single Type III barricade with a Road Closed Sign, R11-2-48, meeting ASTM D4956 Type XI, per Detail 1212-1.

**1212-3.4 ROAD CLOSED – TYPE III TRIPLE BARRICADE.** Shall consist of installing 3 Type III barricades, 2 without road closed signs and the center barricade a Road Closed Sign, R11-2-48, meeting ASTM D4956 Type XI, per Detail 1212-1.

### **1212-4 MEASUREMENT AND PAYMENT**

Measurement and payment shall be as specified in Section 107 and as follows:

All costs to properly complete the work specified herein and/or shown on the plans shall be included in the prices bid for these or other items unless applicable bid items are included in the contract.

## **SECTION 1213 – MAILBOXES**

### **1213-1 DESCRIPTION**

This item shall consist of removal, relocation and reinstallation of mailboxes when required due to conflict or being inaccessible during construction activities.

### **1213-2 CONSTRUCTION REQUIREMENTS**

**1213-2.1 MAILBOXES - REMOVE AND RESET.** In the event existing mailboxes are in conflict with or are inaccessible due to construction activities the CONTRACTOR shall remove, relocate to temporary location and relocate to the final location.

CONTRACTOR shall be responsible for:

- a. Removal and replacement of mailboxes and shall make every effort to remove to replace in the same day. In the event this is not possible, CONTRACTOR shall construct a temporary wood base to hold mailboxes upright.
- b. Coordination with Bismarck Post Office. The Post Office shall be informed when a mailbox is removed and not replaced for more than 24 hours to coordinate mail delivery.


Mailboxes shall be reinstalled with the front of box directly above the box side (property side) of the curb with the bottom of the box 38 inches above the top of curb. Boxes shall be plumb, level, set square with street, and tamped solidly in place.

Mailboxes installed on concrete pads and metal pedestals shall not be removed. A conduit shall be installed under the base as directed by the ENGINEER.

### **1213-3 MEASUREMENT AND PAYMENT**


Measurement and payment shall be as specified in Section 107 and as follows:

**1213-3.1 MAIL BOXES - REMOVE AND RESET.** Multiple boxes on a single or double support structure shall be measured and paid for per support removed and replaced.




TYPICAL ROUGH GRADING WIDTHS  
 80' R/W & 48' FACE TO FACE CURB = 57' WIDE ROUGH GRADING  
 80' R/W & 44' FACE TO FACE CURB = 53' WIDE ROUGH GRADING  
 66' R/W & 40' FACE TO FACE CURB = 49' WIDE ROUGH GRADING

**TYPICAL ROUGH GRADING SECTION**  
 (PRIOR TO UNDERGROUND INSTALLATIONS)



**TYPICAL FINAL GRADING SECTION**  
 AFTER UNDERGROUND INSTALLATIONS, GRADING SHALL BE AT DESIGN SUBGRADE ELEVATION






**TYPICAL CURB GRADING DETAIL**  
 (AFTER UNDERGROUND INSTALLATIONS)



**TYPICAL GRADING SECTIONS**

SCALE:  
 Not to Scale  
 DATE:  
 2/2019

STANDARD  
 DETAIL NO.  
**200-1**



NOTES:  
WEIGHT EQUAL TO 40 PSF

GEOTEXTILE FABRIC TO BE ATTACHED TO THE  
UNDERSIDE OF EACH SECTION WITH A 2'-0"  
OVERHANG ON TWO SIDES. FABRIC TO BE  
GEOTEX 801 OR EQUAL.


CONCRETE TO BE 4000 PSI @ 28 DAYS.



## CONCRETE EROSION BLANKETS

SCALE:  
Not to Scale  
DATE:  
3/2017



STANDARD  
DETAIL NO.  
**205-1**




**EROSION CONTROL BERM**

SCALE:  
Not to Scale  
DATE:  
3/2017

STANDARD  
DETAIL NO.  
**205-2**




**TRENCH DETAIL**




**INSTALLATION WITHOUT TRENCH**


1. SILT FENCE SHALL BE PLACED ON SLOPE CONTOURS TO MAXIMIZE PONDING EFFICIENCY.
2. INSPECT AND REPAIR FENCE AFTER EACH STORM EVENT AND REMOVE SEDIMENT WHEN NECESSARY.
3. REMOVED SEDIMENT SHALL BE DEPOSITED TO AN AREA THAT WILL NOT CONTRIBUTE SEDIMENT OFF-SITE AND CAN BE PERMANENTLY STABILIZED.




**AC PAVEMENT FAILURE**




**SUBBASE/SUBGRADE FAILURE**



**UTILITY CUT PATCH**



**TYPICAL MILL & OVERLAY DETAIL**



**TYPICAL MILL & OVERLAY DETAIL**


NOTE: TACK COAT SHALL BE INSTALLED BETWEEN ALL LIFTS OF ASPHALT




**AC PATCH**

SCALE:  
Not to Scale  
DATE:  
2/2021


STANDARD  
DETAIL NO.  
**400-1**




**(A) FLUSH-FILL**




**(B) SIMPLE OVERBAND**




**(C) STANDARD RESERVOIR-AND-FLUSH**




**(D) STANDARD RECESSED OVERBAND**




**(E) DEEP RESERVOIR-AND-FLUSH  
(backer rod)**



**(F) DEEP RECESSED OVERBAND  
(backer rod)**





**SAW AND SEAL**  
 ( Random Crack > 1/2" Width )





**JOINT AND RANDOM CRACK**  
 ( 1/2" Wide or Less )

METHOD REQUIRED WILL BE MARKED BY THE ENGINEER



1. ALL JOINTS SHALL BE SEALED WITH HOT POURED ELASTIC TYPE JOINT SEALER IN ACCORDANCE WITH SECTION 500 OF THE STANDARD SPECIFICATIONS.
2. THE LONGITUDINAL AND TRANSVERSE JOINT SAWING AND SEALING SHALL BE INCIDENTAL TO THE PRICE BID FOR P.C.C. PAVEMENT OR RELATED ITEM.




DETAIL "A"



DETAIL "B"



CURB & GUTTER SECTIONS



JOINT TERMINATION






JOINT DETAILS


SCALE:  
Not to Scale  
DATE:  
2/2023

STANDARD  
DETAIL NO.  
**500-2**

1. DOWEL BARS SHALL BE SPACED AT 1' O.C. FOR FULL DEPTH REPAIRS.
  - DOWEL BARS SHALL BE PLACED NO LESS THAN 12" OR MORE THAN 18" FROM LONGITUDINAL JOINT.
  - IF EXISTING SAW CUT DOWEL BARS ARE PRESENT, DRILLED IN DOWEL BARS SHALL BE PLACED AT THE HORIZONTAL MIDPOINT BETWEEN EXISTING SAW CUT DOWEL BARS.
2. DOWEL BARS SHALL BE PLACED AT THE VERTICAL MIDPOINT OF THE EXISTING PCC PAVEMENT,
3. SMOOTH BARS AND DOWEL BAR ASSEMBLIES SHALL BE ALIGNED PARALLEL TO THE ROADWAY CENTERLINE AND PAVEMENT SURFACE.



**DOWEL BAR & EPOXY INSTALLATION**



**DOWEL PLACEMENT**


SCALE:  
Not to Scale  
DATE:  
3/2021

STANDARD  
DETAIL NO.  
**500-3**

1. EXISTING CONCRETE SHALL BE REMOVED WITH A CHIPPING HAMMER OR OTHER METHODS, AS APPROVED BY THE ENGINEER. A MILLING MACHINE MAY BE USED, AS APPROVED BY THE ENGINEER, BUT SAWING AND CHIPPING SHALL STILL BE REQUIRED TO FINISH THE REMOVAL.
2. GROUT SHALL BE APPLIED TO THE SIDES, EXCLUDING JOINT FACES, AND BOTTOM OF THE REPAIR AREA.
3. A SPACER MATERIAL, AS APPROVED BY THE ENGINEER, SHALL BE PLACED ON THE JOINT FACE TO MAINTAIN THE JOINT DURING REPAIR. THE MATERIAL SHALL HAVE THE CAPABILITY OF MAINTAINING A WIDTH EQUAL TO THAT OF THE EXISTING JOINT, AND BEING EASILY REMOVED AFTER THE POUR. IN THE CASE OF REPAIR ON BOTH SIDES OF THE JOINT EACH SIDE SHALL BE POURED SEPARATELY.

IN THE CASE OF REPAIR ON ONE SIDE OF THE JOINT, IF DEEMED NECESSARY BY THE ENGINEER, A BITUTHENE WATERPROOFING MEMBRANE WILL BE PLACED ON THE FACE OF THE EXISTING JOINT IN LIEU OF THE SPACER MATERIAL AND PRIOR TO THE CONCRETE POUR.

4. IN THE CASE OF REPAIR ON BOTH SIDES OF THE JOINT, IF DEEMED NECESSARY BY THE ENGINEER, A BITUTHENE WATERPROOFING MEMBRANE SHALL BE PLACED ON THE FACE OF THE NEWLY POURED JOINT IN LIEU OF THE SPACER MATERIAL PRIOR TO THE CONCRETE POUR. THAT MATERIAL SHALL BE A MINIMUM OF 260 MIL (APPROX. 1/4") THICK, OR EQUAL TO THE WIDTH OF THE EXISTING JOINT, WHICHEVER IS LARGER. THE MATERIAL SHALL BE CUT TO FIT OVER THE ENTIRE FACE OF THE EXISTING JOINT. THE MATERIAL SHALL BE PLACED TO PROVIDE FOR EXPANSION AND TO PREVENT WATER FROM ENTERING THE EXISTING JOINT THROUGH THE SIDES OR BOTTOM. THE MATERIAL SHALL BE HAND PRESSED INTO PLACE TO CONFORM TO THE FACE OF THE EXISTING JOINT. IN THE CASE OF REPAIR ON BOTH SIDES OF THE JOINT, A BACKER BOARD MATERIAL, AS APPROVED BY THE ENGINEER, SHALL BE PLACED OVER THE BITUTHENE MATERIAL ON THE SIDES FACING THE SECOND POUR PRIOR TO THE SECOND POUR. THE BACKER BOARD SHALL BE REMOVED AFTER THE REPAIR IS COMPLETED.




SPALL REPAIR DETAIL

	SPALL
	CONCRETE REMOVAL AREA


1. EXISTING CONCRETE SHALL BE REMOVED WITH A CHIPPING HAMMER OR OTHER METHODS, AS APPROVED BY THE ENGINEER. A MILLING MACHINE MAY BE USED, AS APPROVED BY THE ENGINEER, BUT SAWING AND CHIPPING SHALL STILL BE REQUIRED TO FINISH THE REMOVAL.
2. GROUT SHALL BE APPLIED TO THE SIDES, EXCLUDING JOINT FACES, AND BOTTOM OF THE REPAIR AREA.
3. A SPACER MATERIAL, AS APPROVED BY THE ENGINEER, SHALL BE PLACED ON THE JOINT FACE TO MAINTAIN THE JOINT DURING REPAIR. THE MATERIAL SHALL HAVE THE CAPABILITY OF MAINTAINING A WIDTH EQUAL TO THAT OF THE EXISTING JOINT, AND BEING EASILY REMOVED AFTER THE POUR. IN THE CASE OF REPAIR ON BOTH SIDES OF THE JOINT EACH SIDE SHALL BE POURED SEPARATELY.

IN THE CASE OF REPAIR ON ONE SIDE OF THE JOINT, IF DEEMED NECESSARY BY THE ENGINEER, A BITUTHENE WATERPROOFING MEMBRANE WILL BE PLACED ON THE FACE OF THE EXISTING JOINT IN LIEU OF THE SPACER MATERIAL AND PRIOR TO THE CONCRETE POUR.

4. IN THE CASE OF REPAIR ON BOTH SIDES OF THE JOINT, IF DEEMED NECESSARY BY THE ENGINEER, A BITUTHENE WATERPROOFING MEMBRANE SHALL BE PLACED ON THE FACE OF THE NEWLY POURED JOINT IN LIEU OF THE SPACER MATERIAL PRIOR TO THE CONCRETE POUR. THAT MATERIAL SHALL BE A MINIMUM OF 260 MIL (APPROX. 1/4") THICK, OR EQUAL TO THE WIDTH OF THE EXISTING JOINT, WHICHEVER IS LARGER. THE MATERIAL SHALL BE CUT TO FIT OVER THE ENTIRE FACE OF THE EXISTING JOINT. THE MATERIAL SHALL BE PLACED TO PROVIDE FOR EXPANSION AND TO PREVENT WATER FROM ENTERING THE EXISTING JOINT THROUGH THE SIDES OR BOTTOM. THE MATERIAL SHALL BE HAND PRESSED INTO PLACE TO CONFORM TO THE FACE OF THE EXISTING JOINT. IN THE CASE OF REPAIR ON BOTH SIDES OF THE JOINT, A BACKER BOARD MATERIAL, AS APPROVED BY THE ENGINEER, SHALL BE PLACED OVER THE BITUTHENE MATERIAL ON THE SIDES FACING THE SECOND POUR PRIOR TO THE SECOND POUR. THE BACKER BOARD SHALL BE REMOVED AFTER THE REPAIR IS COMPLETED.






CROSS SECTION – REPAIR AREA ON BOTH SIDES OF THE JOINT



CROSS SECTION – REPAIR AREA ON ONE SIDE OF THE JOINT

1. FULL DEPTH SAW CUT THE MARKED REMOVAL AREA.
2. REMOVE CONCRETE FULL DEPTH, RESTORE IN PLACE BASE IF DISTURBED.
3. FURNISH AND INSTALL 18" LONG NO. 9 DEFORMED BARS. THE SPACING FOR TRANSVERSE EDGES SHALL BE 1' O.C. AND SKEWED 20° FROM THE FACE OF THE JOINT. TRANSVERSE BARS SHALL BE PLACED NO LESS THAT 0.5' FROM ANY JOINT OR REPAIR EDGE.
4. FURNISH AND INSTALL 18" LONG NO. 5 DEFORMED BARS. THE SPACING FOR LONGITUDINAL EDGES SHALL BE PARALLEL TO THE JOINT. IF JOINT IS LESS THAN 4' IN LENGTH, USE TWO BARS EVENLY SPACED, IF LONGER THAN 4' SPACE AT 2' O.C. LONGITUDINAL BARS SHALL BE PLACED NO LESS THAT 0.5' FROM END OF TRANSVERSE BARS.
5. RESTORE DOWEL BARS WHICH SHALL BE DRILLED MID POINT BETWEEN EXISTING SAWED DOWEL BARS, SPACED 1' O.C.
6. CLEAN EXPOSED SURFACE OF INPLACE CONCRETE. COAT EXPOSED SURFACES OF THE DOWEL BARS, IF ANY, WITH GREASE.
7. PLACE, CONSOLIDATE, FINISH, AND CURE CONCRETE.
8. IF DEEMED NECESSARY BY THE ENGINEER, PLACE 260 MIL THICKNESS OF BITUTHENE MEMBRANE OR EQUAL (APPROX. 1/4") AT TRANSVERSE JOINT.
9. RESTORE TRANSVERSE AND LONGITUDINAL JOINTS.
10. CLEAN AND SEAL RESTORED TRANSVERSE AND LONGITUDINAL JOINTS.
11. SEE SHEET 500-1 FOR JOINT DETAIL.



- DISTRESSED AREA
- SAW CUT LIMITS
- EX. CONCRETE JOINT






## SPOT FULL DEPTH REPAIR

SCALE:  
Not to Scale  
DATE:  
3/2021


STANDARD  
DETAIL NO.  
**504-3**

1. FULL DEPTH SAW CUT THE MARKED REMOVAL AREA.
2. REMOVE CONCRETE FULL DEPTH, RESTORE IN PLACE BASE IF DISTURBED.
3. FURNISH AND INSTALL 18" LONG NO. 9 DEFORMED BARS. THE SPACING FOR TRANSVERSE EDGES SHALL BE 1' O.C. AND SKEWED 20° FROM THE FACE OF THE JOINT. TRANSVERSE BARS SHALL BE PLACED NO LESS THAT 0.5' FROM ANY JOINT OR REPAIR EDGE.
4. FURNISH AND INSTALL 18" LONG NO. 5 DEFORMED BARS. THE SPACING FOR LONGITUDINAL EDGES SHALL BE PARALLEL TO THE JOINT. IF JOINT IS LESS THAN 4' IN LENGTH, USE TWO BARS EVENLY SPACED, IF LONGER THAN 4' SPACE AT 2' O.C. LONGITUDINAL BARS SHALL BE PLACED NO LESS THAT 0.5' FROM END OF TRANSVERSE BARS.
5. RESTORE DOWEL BARS WHICH SHALL BE DRILLED MID POINT BETWEEN EXISTING SAWED DOWEL BARS, SPACED 1' O.C.
6. CLEAN EXPOSED SURFACE OF INPLACE CONCRETE. COAT EXPOSED SURFACES OF THE DOWEL BARS, IF ANY, WITH GREASE.
7. PLACE, CONSOLIDATE, FINISH, AND CURE CONCRETE.
8. IF DEEMED NECESSARY BY THE ENGINEER, PLACE 260 MIL THICKNESS OF BITUTHENE MEMBRANE OR EQUAL (APPROX. 1/4") AT TRANSVERSE JOINT.
9. RESTORE TRANSVERSE AND LONGITUDINAL JOINTS.
10. CLEAN AND SEAL RESTORED TRANSVERSE AND LONGITUDINAL JOINTS.
11. SEE SHEET 500-1 FOR JOINT DETAIL.





**END OF SIDEWALK RUN OR AT EXPANSION JOINT, APPROXIMATELY 100' INTERVALS**



**TYPICAL 4.5' WIDE SIDEWALK AT LOT LINES, CROSSWALKS OR 100' INTERVALS**

NOTE: AGGREGATE BASE AS PER SECTION 601







**STANDARD CONCRETE SIDEWALK**

SCALE:  
Not to Scale  
DATE:  
2/2023

STANDARD  
DETAIL NO.  
**600-1**

- NOTE NO. 1 CONTRACTION JOINT SCORED 1" DEEP
- NOTE NO. 2 LONGITUDINAL CONTRACTION JOINTS SHALL BE SPACED EQUIDISTANT, WITH 7' MAX. SPACING, SCORED 1/3 DEPTH OF CONCRETE.
- NOTE NO. 3 SIGN & FLAG POLE HOLDERS, WHERE DESIGNATED BY THE ENGINEER, SHALL BE PLACED 2' BEHIND THE FACE OF THE CURB. ALL GATE VALVES, CURB STOP BOXES, HYDRANTS, TRAFFIC CONTROL FOUNDATIONS AND SIGN POSTS SHALL BE WRAPPED WITH APPROVED EXPANSION JOINT, OR APPROVED BOND BREAKER MATERIAL.
- NOTE NO. 4 TRANSITIONS BETWEEN 4.5' & 6' SIDEWALKS SHALL BE TAPERED. TAPERS SHALL OCCUR IN NO LESS THAN 10' UNLESS APPROVED BY ENGINEER.



NOTE: AGGREGATE BASE AS PER SECTION 601




**COMMERCIAL CONCRETE SIDEWALK**



SCALE:  
Not to Scale  
DATE:  
12/2023

STANDARD  
DETAIL NO.  
**600-2**


SEE NOTE NO. 10




TYPE 2



**FLARED SIDES OF CURB RAMP**



**FLARED SIDES OF CURB RAMP**



**SECTION A-A**

- NOTE NO. ① NEW RAMPS SHALL BE DOWELED INTO EXISTING SIDEWALK.
- NOTE NO. ② SCORED JOINT OR DRILLED AND DOWELLED.
- NOTE NO. ③ RAMPS TO BE BUILT WHERE FULL SIDEWALKS EXIST SHALL BE REMOVED TO THE NEAREST EXPANSION OR CONTRACTION JOINT. THE ENGINEER WILL DETERMINE WHAT TYPE OF JOINT TO REPLACE.
- NOTE NO. ④ SIDE FLARE SLOPE MAX 10:1 ADJACENT TO SIDEWALK, MAX 4:1 ADJACENT TO GRASS.
- NOTE NO. ⑤ DETECTABLE WARNING PANEL PLACED 6" TO 8" FROM FACE OF CURB. PANEL SHALL NOT BE IN THE FLARE. PANEL SHALL BE 2' DEEP AND A MIN. OF 4' WIDE.
- NOTE NO. ⑥ TOTAL RAMP AREA SHALL BE 6" CONCRETE AND PAID AS 6" CONCRETE.
- NOTE NO. ⑦ MAX SLOPE RATE 12:1 (15' LONG MAXIMUM ALLOWED FOR STEEPER STREET/CURB GRADES AS APPROVED).
- NOTE NO. ⑧ PROVIDE MIN. 4'X4' LANDING AREA WITH MAX 2% SLOPE IN ANY DIRECTION.
- NOTE NO. ⑨ AGGREGATE BASE AS PER SECTION 601.
- NOTE NO. ⑩ 3/4" OR 1/2" EXPANSION JOINT W/ 1/2" X 12" SMOOTH REINFORCING STEEL OR #4 REINFORCING STEEL, WITH 8" PAPER TUBES OR SPEED DOWELS. WHEN USING 5/8" DRILL BIT, BOND BREAKER MAY BE ELIMINATED.




**TYPE 1 & 2 CURB RAMPS**

SCALE:  
Not to Scale  
DATE:  
2/2023

STANDARD  
DETAIL NO.  
**600-3**



1/4" BRASS BOLTS SHALL BE TAPPED INTO THE SUPPORT BRACES TO HOLD THE 1/4" STEEL SIDEWALK TRENCH LID DOWN. SUPPORT BRACES SHALL BE INSTALLED ONE AT EACH END AND 2' CENTER TO CENTER THEREAFTER.



1"x1" ANGLE IRON WITH NO. 4 REBAR ANCHORS 3" LONG WELDED TO THE FRAME AT A 45° ANGLE DOWN. ANGLE IRON ANCHORS SHALL BE PLACED AT 18" CENTER TO CENTER.

1/4"x2" STEEL SUPPORT BRACES WITH 1/2" STEEL SPACERS, ALL OF WHICH SHALL BE WELDED TO THE 1"x1" ANGLE IRON.

CONTRACTION JOINTS SHALL BE SCORED 1/3 THE DEPTH OF THE CONCRETE AT A MINIMUM SPACING OF 12'. ALL JOINTS IN THE GUTTER SHALL BE SEALED.



REMOVE CURB SECTION. CURB SHALL BE TAPERED TO TRENCH DRAIN AT 45° ANGLE OR AS DIRECTED BY THE ENGINEER.

NOTE NO. ①  
INSTALL DRILLED IN DOWELS OR REINFORCING STEEL BARS AS DIRECTED BY ENGINEER.

TRENCH DRAINS SHALL BEGIN AT PROPERTY LINE OR PROPOSED BACK EDGE OF SIDEWALK AND SHALL EXTEND TO 2" FROM THE FACE OF THE CURB. ALL DRAINS MUST BE COMPLETELY COVERED INCLUDING THE BOULEVARD BETWEEN THE SIDEWALK AND THE CURB. GRADE FOR DEPTH SHALL BE DETERMINED BY THE ENGINEER.

NOTE: AGGREGATE BASE AS PER SECTION 601




## SIDEWALK TRENCH DRAIN


SCALE:  
Not to Scale  
DATE:  
2/2023

STANDARD  
DETAIL NO.  
**600-5**


- NOTE NO. 1 CENTER JOINT TO BE USED ON ALL DRIVEWAYS 18' IN WIDTH OR LESS. JOINT SHALL BE A CONTRACTION JOINT SCORED OR SAWED, 1/3 THE DEPTH OF THE CONCRETE. JOINT SHALL BE SEALED. DRIVEWAYS 19' TO 30' IN TOP WIDTH SHALL BE DIVIDED INTO 3 PARTS. DRIVEWAYS 31' AND LARGER SHALL BE DIVIDED INTO 4 PARTS.
- NOTE NO. 2 CONTRACTION JOINT SCORED OR SAWED 1/3 THE DEPTH OF THE CONCRETE. JOINT SHALL BE SEALED.
- NOTE NO. 3 FLARE DROP TO 3/4" LIP OF DRIVEWAY SHALL DROP @ 1/2 OF FLARE DISTANCE. SEE PLAN VIEW. FLARE WIDTHS (X) SHALL BE 3' FOR RESIDENTIAL, 5' FOR COMMERCIAL, OR AS DIRECTED BY THE ENGINEER.
- NOTE NO. 4 OPTIONAL JOINT WHEN POURED CONTINUOUS.
- NOTE NO. 5 WHEN THE LENGTH (Y) IS 9.5' OR OVER, A HORIZONTAL CONTRACTION JOINT SHALL BE SCORED OR SAWED. JOINT SHALL BE SEALED.
- NOTE NO. 6 ALL DRIVEWAY WIDENINGS SHALL BE SET AT A 90° ANGLE TO THE STREET OR CURB AND GUTTER ALIGNMENT, UNLESS OTHERWISE APPROVED BY THE ENGINEER.



**PLAN VIEW**



**SECTION A-A**



**SECTION B-B**
















NOTE: AGGREGATE BASE AS PER SECTION 601




**DROP CURB DRIVEWAY  
RESIDENTIAL & COMMERCIAL**

SCALE:  
Not to Scale  
DATE:  
2/2023


STANDARD  
DETAIL NO.  
**600-6**




38' (COMMERCIAL ONLY)





40' (COMMERCIAL ONLY)



OVER 32' TO 42'



- NOTE NO. 1 (2) 1/2"x12" SMOOTH REINFORCING STEEL, OR (3) NO. 4 REINFORCING STEEL SHALL BE DRILLED IN WITH A 5/8" BIT ON EITHER END OF THE DRIVEWAY AS DIRECTED BY THE ENGINEER.
- NOTE NO. 2 CENTER JOINT TO BE USED ON ALL DRIVEWAYS 23' IN WIDTH OR LESS. JOINT SHALL BE A CONTRACTION JOINT SCORED OR SAWED 1/3 THE DEPTH OF THE CONCRETE. JOINT SHALL BE SEALED. DRIVEWAYS 24' TO 33' IN TOP WIDTH SHALL BE DIVIDED INTO 3 PARTS, DRIVEWAYS 34' AND LARGER SHALL BE DIVIDED INTO 4 PARTS. WHEN THE DISTANCE IS 9.5' OR OVER, A HORIZONTAL CONTRACTION JOINT SHALL BE SCORED OR SAWED. JOINT SHALL BE SEALED.
- NOTE NO. 3 WHEN THE DISTANCE IS 4' OR OVER USE CONTRACTION JOINT DESCRIBED IN NOTE NO. 2.
- NOTE NO. 4 JOINT SHALL BE A CONTRACTION JOINT WITH CURB CUT FULL DEPTH AND THE REMAINDER OF THE JOINT CUT 1/3 THE DEPTH OF THE CONCRETE. JOINT SHALL BE SEALED.
- NOTE NO. 5 WHEN WIDENING A RADIUS DRIVEWAY, THE WIDENING SHALL BE INSTALLED AS A RADIUS DRIVEWAY, FLARES MIXED WITH RADII SHALL NOT BE ALLOWED, UNLESS APPROVED BY ENGINEER.



NOTE: AGGREGATE BASE AS PER SECTION 601






**RADIUS DRIVEWAY WITH 6" OR 8" CONCRETE**

SCALE:  
Not to Scale  
DATE:  
2/2023

STANDARD  
DETAIL NO.  
**600-9**

- NOTE NO. 1 FOR 6" OR 8" CONCRETE THIS SHALL BE A SCORED OR SAWED JOINT, A MINIMUM OF 1/3 THE DEPTH OF THE CONCRETE.
- NOTE NO. 2 CENTER JOINT TO BE USED ON ALL DRIVEWAYS 23' IN WIDTH OR LESS. JOINT SHALL BE A SAWED CONSTRUCTION JOINT OR CONTRACTION JOINT SCORED, 1/3 THE DEPTH OF THE CONCRETE. JOINT SHALL BE SEALED. DRIVEWAYS 24' TO 33' IN TOP WIDTH SHALL BE DIVIDED INTO 3 PARTS. DRIVEWAYS 34' AND LARGER SHALL BE DIVIDED INTO 4 PARTS. HORIZONTAL CUTS SHALL FOLLOW JOINTS SAWED OR CONTRACTION JOINT OF 4" CONCRETE.
- NOTE NO. 3 THIS SHALL BE A CONTRACTION JOINT. CONTRACTION JOINT SHALL BE SCORED 1/3 THE DEPTH OF THE CONCRETE. ALL JOINTS SHALL BE SEALED. IF THIS IS A CUT-IN DRIVEWAY, (2) 1/2"x12" SMOOTH REINFORCING STEEL OR (3) NO. 4 REINFORCING BARS SHALL BE DRILLED IN WITH A 5/8" BIT ON BOTH ENDS OF THE DRIVEWAY OR AS DIRECTED BY THE ENGINEER.
- NOTE NO. 4 WHEN COMMERCIAL DRIVEWAY DOES NOT HAVE A SIDEWALK SECTION, DRIVEWAY SHALL INCLUDE A MINIMUM 4' WIDE P.A.R., P.A.R. SHALL HAVE MAX GRADE OF 12:1 AND MAX CROSS SLOPE OF 2%.
- NOTE NO. 5 SLOPE OF FLARES VARY WITH DRIVEWAY DEPTH AND FLARE WIDTH.




NOTE: AGGREGATE BASE AS PER SECTION 601



**COMMERCIAL DRIVEWAY  
WITH 6" OR 8" CONCRETE**

SCALE:  
Not to Scale  
DATE:  
2/2023

STANDARD  
DETAIL NO.  
**600-10**




**MOUNTABLE CURB & GUTTER**


SCALE:  
Not to Scale  
DATE:  
3/2019

STANDARD  
DETAIL NO.  
**600-11**


- NOTE NO. 1 3/4" EXPANSION WITH 3/4"x24" SMOOTH REINFORCING STEEL & 16" PAPER TUBES OR SPEED DOWELS. ALL PAPER TUBES SHALL BE PLUGGED OR CRIMPED ON OPEN END. JOINTS SHALL BE PLACED EVERY 100' OR AS DETERMINED BY THE ENGINEER. JOINTS SHALL BE 1/2" LOWER THAN THE TOP OF CURB. THIS JOINT MUST BE SEALED.
- NOTE NO. 2 CONTRACTION JOINT SCORED 1/3 THE DEPTH OF THE CONCRETE.
- NOTE NO. 3 THIS KEYED CONSTRUCTION JOINT WHEN SPECIFIED, SHALL BE PAID FOR AS "EXTRA WORK" IN ACCORDANCE WITH SECTION 104 UNLESS SPECIFICALLY CALLED FOR IN THE SPECIAL PROVISIONS OR SHOWN ON THE PLANS.
- NOTE NO. 4 CURB & GUTTER SHALL BE 6" AND UNREINFORCED UNLESS OTHERWISE SPECIFIED.




**6" OR 8" CURB & GUTTER  
SECTION A-A**




**6" OR 8" CURB & GUTTER  
FRONT VIEW**




**OUTFLOW CURB & GUTTER  
SECTION A-A**




**CURB & GUTTER THROUGH DRIVEWAY  
FRONT VIEW**




**SECTION C-C**



**HEADER CURB  
FRONT VIEW**



**CURB REPAIR**




**KEYED CONSTRUCTION JOINT DETAIL**



**STANDARD CURB, CURB & GUTTER**

SCALE:  
Not to Scale  
DATE:  
2/2023

STANDARD  
DETAIL NO.  
**600-12**



- NOTE NO. 1 DRILLED IN SMOOTH REINFORCING STEEL OR NO. 4 REBAR DRILLED WITH 5/8" BIT.
- NOTE NO. 2 NO. 4 REBAR INSTALLED ON BACK OF INLET SHALL EXTEND 6" INTO THE CURB ON BOTH SIDES.
- NOTE NO. 3 BACK OF CURB MUST ENCASE BARREL OF MANHOLE.




**MOUNTABLE CURB & GUTTER W/ INLET**

SCALE:  
Not to Scale  
DATE:  
3/2017


STANDARD  
DETAIL NO.  
**600-14**

- NOTE NO. 1 3/4" EXPANSION JOINT WITH DRILLED IN 1/2"X12" SMOOTH REINFORCING STEEL OR #4 REINFORCING STEEL. WHEN USING 5/8" DRILL BIT, BOND BREAKER MATERIAL MAY BE ELIMINATED. ALL JOINTS SHALL BE SEALED.
- NOTE NO. 2 CONTRACTION JOINT SCORED 1/3 THE DEPTH OF THE CONCRETE. JOINT SHALL BE SEALED.





RADIUS EQUAL TO DISTANCE FROM FACE OF CURB TO RIGHT OF WAY LINE OF WIDEST STREET OF INTERSECTION UNLESS OTHERWISE SPECIFIED

- NOTE NO. 1 FOR NEW CONSTRUCTION WHEN SPANDREL IS POURED SEPARATELY OR FOR VALLEY GUTTER REPAIRS, 18" NO. 5 DEFORMED BARS SHALL BE DRILLED IN 1' ON CENTER.
- NOTE NO. 2 CONTRACTION JOINT SCORED  $\frac{1}{3}$  THE DEPTH OF THE CONCRETE. ALL JOINTS SHALL BE SEALED.
- NOTE NO. 3  $\frac{3}{4}$ " EXPANSION JOINT WITH DRILLED IN  $\frac{1}{2}$ "X12" SMOOTH REINFORCING STEEL OR #4 REINFORCING STEEL. WHEN USING  $\frac{5}{8}$ " DRILL BIT, BOND BREAKER MATERIAL MAY BE ELIMINATED. ALL JOINTS SHALL BE SEALED.



STR. WIDTH	PVMT. WIDTH	JT. SPACING
28'	25'	8.3'
32'	29'	9.7'
37'	34'	8.5'
38'	35'	8.8'
40'	37'	9.3'
44'	41'	8.2'
48'	45'	9.0'
52'	49'	9.8'



**SECTION B-B**  
**TRANSITION TO AN 8" VALLEY GUTTER**

**PLAN VIEW**


NOTE: AGGREGATE BASE AS PER SECTION 601



**VALLEY GUTTER**

SCALE:  
Not to Scale  
DATE:  
2/2023


STANDARD  
DETAIL NO.  
**600-16**




- NOTE NO. 1 DRILLED IN SMOOTH REINFORCING STEEL OR NO. 4 REBAR DRILLED WITH 5/8" BIT. SMOOTH REINFORCING STEEL SHALL BE GREASED THE FULL LENGTH. ALL PAPER TUBES SHALL BE PLUGGED OR CRIMPED ON OPEN END AS DETERMINED BY THE ENGINEER. ALL JOINTS SHALL BE SEALED.
- NOTE NO. 2 CONTRACTION JOINT SCORED TO 1/3 DEPTH OF THE CONCRETE.
- NOTE NO. 3 WIDENING CURB BEHIND INLET SHALL BE INCIDENTAL.
- NOTE NO. 4 NO. 4 REBAR INSTALLED ON BACK OF INLET SHALL EXTEND 6" INTO THE CURB ON BOTH SIDES.

**NOTES:**


1. BOULEVARD WIDTH VARIES BASED ON WIDTH OF STREET & WIDTH OF RIGHT-OF-WAY.
2. SIDEWALK ADJACENT TO CURB SHALL BE A MINIMUM OF 5' TO COMPLY WITH ADA STANDARDS.
3. A 5X5 PASSING SPACE IS REQUIRED AND SHALL BE INSTALLED FOR NEW SIDEWALKS GREATER THAN 200' IN LENGTH. INSTALL ONE PASSING SPACE FOR EVERY 200 LF OF NEW 4.5' SIDEWALK.



**RESIDENTIAL SIDEWALK & RIGHT-OF-WAY GRADING**



**COMMERCIAL/MULTI-FAMILY SIDEWALK & RIGHT-OF-WAY GRADING**



**SIDEWALK ADJACENT TO CURB**



NOTE: AGGREGATE BASE AS PER SECTION 601



**SIDEWALK & RIGHT-OF-WAY GRADING DETAIL**

SCALE:  
Not to Scale  
DATE:  
2/2023

STANDARD  
DETAIL NO.  
**600-18**




- NOTE NO. 1 PRIVATE DRIVE IMPROVEMENTS ARE REQUIRED PRIOR TO DRIVEWAY INSTALLATION UNLESS APPROVED BY THE ENGINEER
- NOTE NO. 2 DRIVEWAYS SHALL BE PLACED ON THE OWNER'S PROPERTY AND SHALL NOT EXTEND INTO ANOTHER PROPERTY OWNER'S PROPERTY, OR PAST THE PROJECTED PROPERTY LINE WITHIN THE R/W UNLESS APPROVED BY THE ENGINEER
- NOTE NO. 3 WHEN WIDENING A RADIUS-TYPE DRIVEWAY, THE WIDENING SHALL BE INSTALLED AS A RADIUS-TYPE DRIVEWAY, FLARES MIXED WITH RADII SHALL NOT BE ALLOWED, UNLESS APPROVED BY THE ENGINEER
- NOTE NO. 4 NEW CONSTRUCTION DRIVEWAYS AND WIDENINGS SHALL NOT BE BUILT WITHIN 6 FEET OF A FIRE HYDRANT OR WITHIN 3 FEET OF A STREET LIGHT OR POWER POLE, UNLESS APPROVED BY THE ENGINEER
- NOTE NO. 5 NEW CONSTRUCTION DRIVEWAYS AND WIDENING SHALL NOT BE BUILT WITHIN 10 FEET OF ANY TREE IN THE RIGHT-OF-WAY, UNLESS APPROVED BY THE CITY FORESTER
- NOTE NO. 6 BUILDING SETBACK REQUIREMENTS VARY BASED ON ZONING DISTRICTS; HOWEVER, A 25-FOOT FRONT YARD SETBACK IS TYPICALLY REQUIRED FOR RESIDENTIALLY ZONED PROPERTIES
- NOTE NO. 7 TYPICALLY, NEW RESIDENTIAL DRIVEWAYS SHALL USE 4.5' WALK SET 0.5' FROM PROPERTY LINE. IF 6' SIDEWALK IS USED, WALK SHALL BE SET ON PROPERTY LINE. VERIFY WITH ENGINEER PRIOR TO CONSTRUCTION.
- NOTE NO. 8 RESIDENTIAL ONLY. NON-RESIDENTIAL SEE SIGHT TRIANGLE REQUIREMENTS.




## TYPICAL DRIVEWAY INSTALLATION

SCALE:  
Not to Scale  
DATE:  
02/2023

STANDARD  
DETAIL NO.  
**600-19**






## PIPE BEDDING QUANTITIES - SANITARY SEWER


4" to 27" Based on SDR35 PVC  
30" to 48" Based on ASTM F-794 PVC

<u>PIPE SIZE</u>	<u>TRENCH WIDTH</u>	<u>C.Y. / FT.</u>	<u>TONS / FT.</u>
4"	48"	0.0736	0.1251
6"	48"	0.0842	0.1431
8"	48"	0.0941	0.1600
10"	48"	0.1031	0.1753
12"	49"	0.1134	0.1928
15"	51"	0.1322	0.2247
18"	55"	0.1535	0.2610
21"	58"	0.1750	0.2975
24"	61"	0.1952	0.3318
27"	64"	0.2170	0.3689
30"	68"	0.2450	0.4165
36"	74"	0.2915	0.4956
42"	80"	0.3397	0.5775
48"	87"	0.3971	0.6751

5 Tons / Manhole



**RCP PIPE**



**HDPE PIPE**

**PIPE BEDDING QUANTITIES - STORM SEWER**

Based on RC Pipe and 1.70 TON/CY

<u>PIPE SIZE</u>	<u>TRENCH WIDTH</u>	<u>C.Y. / FT.</u>	<u>TONS / FT.</u>
12"	52"	0.13	0.23
15"	56"	0.16	0.27
18"	59"	0.18	0.31
21"	63"	0.21	0.35
24"	66"	0.23	0.39
27"	70"	0.26	0.44
30"	73"	0.28	0.48
33"	77"	0.31	0.53
36"	80"	0.34	0.58
42"	87"	0.4	0.68
48"	94"	0.46	0.78
54"	101"	0.52	0.89
60"	108"	0.59	1.00
66"	115"	0.66	1.12
72"	122"	0.73	1.24
78"	129"	0.80	1.36
84"	136"	0.88	1.49

5 Tons / Manhole

2.5 Tons / Inlet

2.5 Tons / F.E.S.



**STORM SEWER PIPE BEDDING**

SCALE:  
Not to Scale  
DATE:  
2/2023

STANDARD  
DETAIL NO.  
**802-1**



**NOTES:**

1. CONNECTION AND PIPE TO BE BACKFILLED PER CLASS SPECIFIED.
2. IN LIEU OF AN INTERNAL CYLINDER, AN HDPE WATERTIGHT REPAIR COUPLER CAN BE USED.
3. INTERNAL CYLINDER ADAPTER IS NOT RECOMMENDED FOR DOWNSTREAM CONNECTIONS.

DOUBLE WIDE MARMAC  
COUPLER TO BE WRAPPED  
AROUND CONNECTION




**SECTION A-A**



**HDPE TO REINFORCED CONCRETE  
PIPE CONNECTION DETAIL**

SCALE:  
Not to Scale  
DATE:  
3/2017

STANDARD  
DETAIL NO.  
**802-2**




SECTION VIEW



**PERFORATED PIPE IN-LINE CLEANOUT**


SCALE:  
Not to Scale  
DATE:  
1/2026

STANDARD  
DETAIL NO.  
**802-3**




SECTION VIEW


- NOTE NO. 1 BLOCKING OF TYPICAL HORIZONTAL BEND WILL INCLUDE ALL BENDS 11 1/4° (1/32) TO 90° (1/4)
- NOTE NO. 2 BLOCK TEE AS SHOWN. IN THE EVENT THAT ONE SIDE OF THE MAIN IS PLUGGED, 2 THRUST BLOCKS WILL BE REQUIRED.
- NOTE NO. 3 BLOCKING OF PLUG IS TO INCLUDE PLYBOARD BETWEEN THE PLUG AND CONCRETE.
- NOTE NO. 4 BLOCKING OF CROSS WITH 2 PLUGS IS AS SHOWN. WITH ONLY 1 PLUG PROCEED SAME AS TEE.
- NOTE NO. 5 JOINTS SHALL BE RESTRAINED IF SIZE IS REDUCED 2 PIPE SIZES OR MORE.
- NOTE NO. 6 ALL BENDS SHALL BE RESTRAINED.
- NOTE NO. 7 ALL HYDRANTS TO BE BLOCKED AS SHOWN. KEEP CONCRETE AWAY FROM WEEP HOLES.
- NOTE NO. 8 THE END AREA OF CONCRETE THRUST BLOCKS SHALL BE SUBMITTED WITH SOIL BEARING CHARACTERISTICS TO THE ENGINEER FOR APPROVAL.
- NOTE NO. 9 THRUST BLOCKING FOR PIPE 12" AND LARGER SHALL BE POURED AS SHOWN. NO PRECAST BLOCKS SHALL BE ALLOWED.




TYPICAL HORIZONTAL BEND  
NOTE NO. 1




TEE AND WYE  
NOTE NO. 2



DEAD END OR PLUG  
NOTE NO. 3




CROSS - NOTE NO. 4




REDUCER - NOTE NO. 5

TYPICAL VERTICAL BENDS  
NOTE NO. 6



HYDRANT NOTE NO. 7



WATERMAIN SHALL BE MEASURED AND PAYMENT WILL BE MADE FOR:

A & G LINEAR FEET OF PIPE OF DIAMETER "M".

B,C,D & F LINEAR FEET OF PIPE OF DIAMETER "N".


E LINEAR FEET OF PIPE OF DIAMETER "O".



### WATERMAIN PAYMENT DIAGRAM

SCALE:  
Not to Scale  
DATE:  
3/2017

STANDARD  
DETAIL NO.  
**900-2**



**PIPE BEDDING QUANTITIES - WATERMAIN**

6" to 18" Based on C900, C905 PVC or C909 PVCO

20" Based on CL250 DI

24" Based on CL250 DI

30" to 48" Based on CL150 DI

<u>PIPE SIZE</u>	<u>TRENCH WIDTH</u>	<u>C.Y. / FT.</u>	<u>TONS / FT.</u>
4"	48"	0.1287	0.2188
6"	48"	0.1496	0.2543
8"	48"	0.1693	0.2878
10"	48"	0.1862	0.3165
12"	49"	0.2068	0.3516
16"	54"	0.2638	0.4485
18"	56"	0.2905	0.4939
20"	58"	0.3175	0.5398
24"	62"	0.3726	0.6334
30"	68"	0.4578	0.7783
36"	74"	0.5468	0.9296
42"	81"	0.6521	1.1086
48"	87"	0.7497	1.2745

5 Tons / Manhole

2.5 Tons / Hydrant


0.1 Tons / LF of Service Line (2" & Under)



**WATERMAIN PIPE BEDDING**

SCALE:  
Not to Scale  
DATE:  
3/2019

STANDARD  
DETAIL NO.  
**900-3**



**KEY:**

- |                  |   |                      |
|------------------|---|----------------------|
| ① TEE            | ④ CONCRETE PAD MIN. 18" SQUARE X 6" THICK | ⑦ HYDRANT            |
| ② ¾" - 1 ½" ROCK | ⑤ GATE VALVE                              | ⑧ GATE VALVE ADAPTER |
| ③ HYDRANT LEAD   | ⑥ HYDRANT DRAIN OPENING                   | ⑨ RESTRAINED JOINTS  |

**NOTES:**


- ¾" - 1 ½" SIZE ROCK SHALL BE TO A LEVEL 6" ABOVE WASTE OPENING OR GREATER, WITH A MINIMUM 30" WIDE. MINIMUM QUANTITY ½ CU. YD.
- ALL HYDRANT LEADS SHALL BE C-900 AND SHALL HAVE A TYPICAL OVERALL LENGTH OF 5 FT. VALVE AND HYDRANT SHALL HAVE 2 FT. MINIMUM DISTANCE BETWEEN THEM.
- WRAP HYDRANT UP TO GROUND LINE WITH 8 MILL (MIN.) POLY TAPE ENDS AND SEAMS. DO NOT ALLOW POLY OR CONCRETE TO COVER DRIP OR DRAIN OPENINGS.
- ALL JOINTS SHALL BE RESTRAINED.




**HYDRANT SETTING**

SCALE:  
Not to Scale  
DATE:  
03/2019

STANDARD  
DETAIL NO.  
**900-4**



PLAN




SECTION




**TRENCH DETAIL IN CONDUIT**

SCALE:  
Not to Scale  
DATE:  
01/2023

STANDARD  
DETAIL NO.  
**1002-1**



PLAN







SECTION



**TRENCH DETAIL DIRECT BURIED**

SCALE:  
Not to Scale  
DATE:  
01/2023

STANDARD  
DETAIL NO.  
**1002-2**



1. CONDUIT SHALL BE 24" BELOW GRADE AND SLOPED 3% FOR DRAINAGE.
2. PROVIDE 12"-18" LOOP IN CABLES AT EACH CONDUIT END.


1. CONDUIT SHALL BE 24" BELOW GRADE AND SLOPED 3% FOR DRAINAGE.
2. CONDUIT SHALL EXTEND 6" BEYOND CONCRETE AT BOTH ENDS.
3. PROVIDE 9" LOOP IN CABLES AT EACH CONDUIT END.




## STREET CROSSING DETAIL IN CONDUIT


SCALE:  
Not to Scale  
DATE:  
01/2023

STANDARD  
DETAIL NO.  
**1002-3**




1. CONDUIT SHALL BE 24" BELOW GRADE AND SLOPED TO DRAIN.
2. PROVIDE FROST LOOPS AT EACH CONDUIT ENDS.
3. PROVIDE PLASTIC BUSHING OR BELL FITTING AT ALL CONDUIT ENDS.






PLAN




ELEVATION

**FEED POINT TYPES**

- TYPE I = CIRCUIT 1
- TYPE II = CIRCUITS 1 & 2
- TYPE III = CIRCUITS 1-3
- TYPE IV = CIRCUITS 1-4



**TOP VIEW**



**FRONT VIEW**


NOTE NO. 1 - THE CIRCUIT WOULD INCLUDE THE ASSOCIATED BREAKER, LIGHTING CONTACTOR/RELAY, CONDUIT, & CONDUCTOR.  
 NOTE NO. 2 - FOLLOW LAYOUT OF COMPONENTS WITHIN THE ENCLOSURE AS SHOWN AND RESERVE SPACE FOR FUTURE COMPONENTS.  
 NOTE NO. 3 - FOR EXISTING FEEDPOINT REPLACEMENTS, MAINTAIN EXISTING CIRCUITRY AND RELAY NUMBERING.




**PAD MOUNTED FEED POINT DETAIL  
(SHEET 1 OF 2)**

SCALE:  
Not to Scale  
DATE:  
1/2026

STANDARD  
DETAIL NO.  
**1003-1**



SIDE VIEW



ISOMETRIC VIEW




**PAD MOUNTED FEED POINT DETAIL  
(SHEET 2 OF 2)**

SCALE:  
Not to Scale  
DATE:  
1/2026

STANDARD  
DETAIL NO.  
**1003-2**


PROVIDE METER TRIM AND MOUNT IN ACCORDANCE WITH UTILITY COMPANY REQUIREMENTS.  
 1 1/2" L.B. GASKETED COVER FOR SERVICE CONDUCTORS CABINET ENCLOSURES - SEE SPEC.

2" RIGID GALVANIZED STEEL CONDUIT (1 PER CIRCUIT) AND (2)-1" RIGID GALVANIZED STEEL CONDUITS. EXTEND 18" BELOW GRADE. PROVIDE PLASTIC BUSHING.



FRONT


SIDE



FRONT

SIDE

NOTE  
 PROVIDE UNISTRUT P-1280 END CAPS ON ALL UNISTRUT CHANNEL ENDS.





NOTE NO. 1 - MAIN BREAKER TO BE ON TOP OF PANEL BOARD  
 NOTE NO. 2 - PROVIDE ONE RELAY/CONTACTOR FOR EACH STREETLIGHT CIRCUIT




## FEED POINT WIRING DETAIL

SCALE:  
Not to Scale  
DATE:  
01/2024

STANDARD  
DETAIL NO.  
**1003-4**



NAME TO MATCH  
PROJECT NUMBER




NOTE NO.1 - NAMEPLATES TO BE AFFIXED TO CABINET WITH STAINLESS STEEL OR ALUMINUM RIVETS AND 3M ADHESIVE.



**FEEDPOINT NAMEPLATE DETAIL**

SCALE:  
Not to Scale  
DATE:  
1/2026

STANDARD  
DETAIL NO.  
**1003-5**





TYPE	D	W
BL	3'-3"	6 1/8"
L, L1	4'-11"	9"
DL1	4'-3"	8"




**EMBEDDED BASE DETAIL**

SCALE:  
Not to Scale  
DATE:  
1/2026


STANDARD  
DETAIL NO.  
**1004-1**






**TYPE L & L1 POLE DETAIL**

NO SCALE




**TYPE BL POLE DETAIL**

NO SCALE



**TYPE CL & CL1 POLE DETAIL**  
NO SCALE



**TYPE DL1 POLE DETAIL**

NO SCALE

NOTE NO.1 - MANHOLE CASTING AND COVER SHALL BE AS DEFINED IN SECTION 1205.

NOTE NO.2 - ALLOWANCE FOR ADJUSTMENT - 0" TO 6" - SEE STANDARD DETAIL NO. 1206-1.

NOTE NO.3 - P2 GASKETED JOINT FOR 48" MANHOLES, CX-4 JOINT FOR ALL OTHER SIZES OF MANHOLES AND EXTERIOR SEAL BY PRESS-SEAL GASKET CORP. EZ WRAP AND EZ STIK NO. 4 PRIMER, SPECIALTY PRODUCTS "MAC WRAP", INFI-SHIELD EXTERNAL GATOR WRAP, OR AN APPROVED EQUAL.


NOTE NO.4 - IF PRECAST MANHOLE BASE IS USED, FLOOR SHALL BE GROUTED AND SLOPED, AS SHOWN, FROM 1/2" THE DIAMETER OF THE PIPE. SEE SECTION 1205 FOR PRECAST MANHOLE BASE REINFORCEMENT.

NOTE NO.5 - MANHOLE TOP SECTION SHALL BE ECCENTRIC FOR 48" MANHOLES.

NOTE NO.6 - CAST IN PLACE MANHOLE BASES SHALL BE DIMENSIONED AS SHOWN UNLESS OTHERWISE INDICATED. BASES SHALL BE REINFORCED WITH NO.4 REBAR SPACED 15" ON CENTER BOTH WAYS.

NOTE NO.7 - IF REQUIRED PER SECTION 1205, I/I BARRIER AS MANUFACTURED BY AP/M PERMAFORM OR AN APPROVED EQUAL. ADJUSTMENT RINGS SHALL NOT EXCEED THE HEIGHT OF THE I/I BARRIER.

NOTE NO.8 - STEPS SHALL NOT BE PLACED IN SANITARY SEWER, STORM SEWER, AIR RELEASE MANHOLES OR INLETS UNLESS SPECIFIED. IF SPECIFIED, THE MANHOLE STEPS SHALL BE DELTA SUREFOOT OR APPROVED EQUAL. STEPS SHALL BE SPACED 16" ON CENTER.




**SANITARY SEWER MANHOLE**

SCALE:  
Not to Scale  
DATE:  
1/2024

STANDARD  
DETAIL NO.  
**1205-1**

- NOTE NO.1 - MANHOLE CASTING AND COVER SHALL BE AS DEFINED IN SECTION 1205, CENTER OVER FLOW LINE.
- NOTE NO.2 - ALLOWANCE FOR ADJUSTMENT - 0" TO 6" - SEE STANDARD DETAIL NO. 1206-1.
- NOTE NO.3 - P2 GASKETED JOINT FOR 48" MANHOLES, CX-4 JOINT FOR ALL OTHER SIZES OF MANHOLES AND EXTERIOR SEAL BY PRESS-SEAL GASKET CORP. EZ WRAP AND EZ STIK NO. 4 PRIMER, SPECIALTY PRODUCTS "MAC WRAP", INFI-SHIELD EXTERNAL GATOR WRAP, OR AN APPROVED EQUAL.
- NOTE NO.4 - IF PRECAST MANHOLE BASE IS USED, FLOOR SHALL BE GROUTED AND SLOPED, AS SHOWN, FROM 1/2 THE DIAMETER OF THE PIPE. SEE SECTION 1205 FOR PRECAST MANHOLE BASE REINFORCEMENT.
- NOTE NO.5 - DROP MANHOLE SHALL BE MIN 60" INSIDE DIAMETER.
- NOTE NO.6 - CAST IN PLACE MANHOLE BASES SHALL BE DIMENSIONED AS SHOWN UNLESS OTHERWISE INDICATED. BASES SHALL BE REINFORCED WITH NO.4 REBAR SPACED 15" ON CENTER BOTH WAYS.
- NOTE NO.7 - IF REQUIRED PER SECTION 1205, I/I BARRIER AS MANUFACTURED BY AP/M PERMAFORM OR AN APPROVED EQUAL, IF SPECIFIED. ADJUSTMENT RINGS SHALL NOT EXCEED THE HEIGHT OF THE I/I BARRIER.
- NOTE NO.8 - STEPS SHALL NOT BE PLACED IN SANITARY SEWER, STORM SEWER OR AIR RELEASE MANHOLES OR INLETS UNLESS SPECIFIED. IF SPECIFIED, THE MANHOLE STEPS SHALL BE DELTA SUREFOOT OR APPROVED EQUAL. STEPS SHALL BE SPACED 16" ON CENTER.
- NOTE NO.9 - ALL STAINLESS STEEL SHALL BE GRADE 316.
- NOTE NO.10 - INTERIOR OF MANHOLE SHALL BE EPOXY COATED AS PER PLANS




## SANITARY SEWER DROP MANHOLE

SCALE:  
Not to Scale  
DATE:  
1/2026

STANDARD  
DETAIL NO.  
**1205-2**

RECOMMENDED PRECAST SIZE REQUIREMENTS

BARREL DIAMETER	MAXIMUM SIZE RCP		
	2 @ 90	2 @ 180	RCP
48"	15"	30"	33"
54"	18"	36"	36"
60"	21"	42"	42"
66"	24"	48"	48"
72"	30"	48"	48"



SEE STANDARD  
DETAIL 1206-1

NOTE NO.1 - MANHOLE CASTING SHALL BE AS DEFINED IN SECTION 1205.

NOTE NO.2 - P2 GASKETED JOINT FOR 48" MANHOLES, CX-4 JOINT FOR ALL OTHER SIZES OF MANHOLES AND EXTERIOR SEAL BY PRESS-SEAL GASKET CORP. EZ WRAP AND EZ STIK NO. 4 PRIMER, SPECIALTY PRODUCTS "MAC WRAP", INFI-SHIELD EXTERNAL GATOR WRAP, OR AN APPROVED EQUAL.

NOTE NO.3 - PRECAST CONCRETE MANHOLE SHALL CONFORM TO ASTM C478, WALL B.

NOTE NO.4 - PRECAST REINFORCED CONCRETE MANHOLE BASES SHALL CONFORM TO SECTION 1205.

NOTE NO.5 - MANHOLE TOP SECTION SHALL BE ECCENTRIC FOR 48" MANHOLES. MANHOLE TOP SECTION FOR MANHOLES OVER 48" SHALL BE FULL DIAMETER SECTION WITH FLAT TOP.

NOTE NO.6 - IF REQUIRED PER SECTION 1205, I/I BARRIER AS MANUFACTURED BY AP/M PERMAFORM OR AN APPROVED EQUAL. ADJUSTMENT RINGS SHALL NOT EXCEED THE HEIGHT OF THE I/I BARRIER.

NOTE NO.7 - STEPS SHALL NOT BE PLACED IN SANITARY SEWER, STORM SEWER, AIR RELEASE MANHOLES OR INLETS UNLESS SPECIFIED. IF SPECIFIED, THE MANHOLE STEPS SHALL BE DELTA SUREFOOT OR APPROVED EQUAL. STEPS SHALL BE SPACED 16" ON CENTER.

NOTE NO.8 - GROUT TO SLOPE FLOOR TO INVERT OF LOWEST PIPE.

ROCK SHALL BE WRAPPED IN R1 FABRIC WHEN GROUND WATER IS PRESENT



**STORM SEWER MANHOLE**

SCALE:  
Not to Scale  
DATE:  
1/2024


STANDARD  
DETAIL NO.  
**1205-3**

NOTE NO.1 - MANHOLE CASTING AND COVER SHALL BE AS DEFINED IN SECTION 1205.

NOTE NO.2 - EXTERIOR SEAL BY PRESS-SEAL GASKET CORP. EZ WRAP AND EZ STIK NO. 4 PRIMER, SPECIALTY PRODUCTS "MAC WRAP", INFI-SHIELD EXTERNAL GATOR WRAP, OR AN APPROVED EQUAL.

NOTE NO.3 - IF REQUIRED PER SECTION 1205, I/I BARRIER AS MANUFACTURED BY AP/M PERMAFORM OR AN APPROVED EQUAL. ADJUSTMENT RINGS SHALL NOT EXCEED THE HEIGHT OF THE I/I BARRIER.

NOTE NO.4 - STEPS SHALL NOT BE PLACED IN SANITARY SEWER, STORM SEWER OR AIR RELEASE MANHOLES OR INLETS UNLESS SPECIFIED. IF SPECIFIED, THE MANHOLE STEPS SHALL BE DELTA SUREFOOT OR APPROVED EQUAL. STEPS SHALL BE SPACED 16" ON CENTER.



**CAST IN PLACE STORM SEWER MANHOLE**

SCALE:  
Not to Scale  
DATE:  
1/2024

STANDARD  
DETAIL NO.  
**1205-4**


NOTE NO.1 - INLET CASTING SHALL BE AS DEFINED IN SECTION 1205.

NOTE NO.2 - ALLOWANCE FOR ADJUSTMENT SHALL BE 1 1/2" MINIMUM TO 3" MAXIMUM. SEE STANDARD DETAIL NO.1206-1.

NOTE NO.3 - BOLTS FOR CASTING SHALL BE TEMPER FINISH, DOUBLE HEAT TREATED- 1038 S.A.E. GRADE 5, WITH CAD-DICHROMATE PLATING.

NOTE NO.4 - SLOPE FLOOR TO INVERT OF LOWEST PIPE.

NOTE NO.5 - STEPS SHALL NOT BE PLACED IN SANITARY SEWER, STORM SEWER OR AIR RELEASE MANHOLES OR INLETS UNLESS SPECIFIED. IF SPECIFIED, THE MANHOLE STEPS SHALL BE DELTA SUREFOOT OR APPROVED EQUAL. STEPS SHALL BE SPACED 16" ON CENTER.



**SECTION A-A**  
**TYPE 24" INLET**



**TYPE 24" INLET**

SCALE:  
Not to Scale  
DATE:  
2/2023


STANDARD  
DETAIL NO.  
**1205-5**

NOTE NO.1 - TYPE 36" INLET CASTING SHALL BE AS DEFINED IN SECTION 1205.  
 TYPE 72" INLET CASTING SHALL BE AS DEFINED IN SECTION 1205.

NOTE NO.2 - ALLOWANCE FOR ADJUSTMENT SHALL BE 1 1/2" MINIMUM TO 3" MAXIMUM. SEE STANDARD DETAIL NO.1206-1.

NOTE NO.3 - BOLTS FOR CASTING SHALL BE TEMPER FINISH, DOUBLE HEAT TREATED-1038 S.A.E. GRADE 5, WITH CAD-DICHROMATE PLATING.

NOTE NO.4 - STEPS SHALL NOT BE PLACED IN SANITARY SEWER, STORM SEWER OR AIR RELEASE MANHOLES OR INLETS UNLESS SPECIFIED. IF SPECIFIED, THE MANHOLE STEPS SHALL BE DELTA SUREFOOT OR APPROVED EQUAL. STEPS SHALL BE SPACED 16" ON CENTER.



NOTE NO.1 - TYPE 36" INLET CASTING SHALL BE AS DEFINED IN SECTION 1205.  
 TYPE 72" INLET CASTING SHALL BE AS DEFINED IN SECTION 1205.


NOTE NO.2 - ALLOWANCE FOR ADJUSTMENT SHALL BE 1 1/2" MINIMUM TO 3" MAXIMUM. SEE STANDARD DETAIL NO.1206-1.

NOTE NO.3 - ALL BARS SHALL BE NO.5 DEFORMED REINFORCING BARS SPACED 6" CENTER TO CENTER BOTH WAYS.


NOTE NO.4 - BOLTS FOR CASTING SHALL BE TEMPER FINISH,DOUBLE HEAT TREATED-1038 S.A.E. GRADE 5, WITH CAD-DICHROMATE PLATING.

NOTE NO.5 - STEPS SHALL NOT BE PLACED IN SANITARY SEWER, STORM SEWER OR AIR RELEASE MANHOLES OR INLETS UNLESS SPECIFIED. IF SPECIFIED, THE MANHOLE STEPS SHALL BE DELTA SUREFOOT OR APPROVED EQUAL. STEPS SHALL BE SPACED 16" ON CENTER.

NOTE NO.6 - SLOPE FLOOR TO INVERT OF LOWEST PIPE.



**SECTION A-A**



**SECTION B-B**



**TYPE 36" AND TYPE 72" INLET (SHEET 2 OF 2)**

SCALE:  
 Not to Scale  
 DATE:  
 1/2026

STANDARD  
 DETAIL NO.  
**1205-7**



NOTE NO.1 - INLET CASTING SHALL BE AS DEFINED IN SECTION 1205.

NOTE NO.2 - ALLOWANCE FOR ADJUSTMENT SHALL BE 1 1/2" MINIMUM TO 3" MAXIMUM. SEE STANDARD DETAIL NO.1206-1.

NOTE NO.3 - ALL BARS SHALL BE NO.5 DEFORMED REINFORCING BARS. AT LEAST TWO BARS SHALL BE PLACED 3" CENTER TO CENTER AROUND THE INLET OPENING. ALL OTHER BARS SHALL BE SPACED 6" CENTER TO CENTER BOTH WAYS.

NOTE NO.4 - REINFORCED CONCRETE ROOF SLAB MAY BE PRECAST OR CAST IN PLACE.


NOTE NO.5 - BOLTS FOR CASTING SHALL BE TEMPER FINISH, DOUBLE HEAT TREATED-1038 S.A.E. GRADE 5, WITH CAD-DICHROMATE PLATING.






**ROOF SLAB FOR TYPE 36" & 72" INLET  
W/ TYPE 24" CASTING**

SCALE:  
Not to Scale  
DATE:  
3/2017

STANDARD  
DETAIL NO.  
**1205-8**




**PERSPECTIVE**





**SLOTTED DRAIN INLET - (SHEET 1 OF 2)**

SCALE:  
Not to Scale  
DATE:  
3/2017

STANDARD  
DETAIL NO.  
**1205-9**




**SIDE VIEW**




**SECTION B-B**

**TYPICAL COUPLING BAND**



**SECTION A-A**



**TYPICAL SECTION**




**SLOTTED DRAIN INLET - (SHEET 2 OF 2)**

SCALE:  
Not to Scale  
DATE:  
1/2026

STANDARD  
DETAIL NO.  
**1205-10**


- NOTE NO.1 - MANHOLE CASTING AND COVER SHALL BE AS DEFINED IN SECTION 1205.
- NOTE NO.2 - 48" TYPE II COVER IN SECTION 1205.
- NOTE NO.3 - MANHOLE CASTING ADJUSTMENT - SEE STANDARD DETAIL NO. 1206-1.
- NOTE NO.4 - 2" STYROFOAM INSULATION SHALL BE AS DEFINED IN SECTION 901 INSTALLED AROUND THE OUTSIDE OF THE TOP 4 FEET OF THE MANHOLE AND HELD IN PLACE BY BANDS OR GLUE UNTIL BACKFILLED.
- NOTE NO.5 - P2 GASKETED JOINT FOR 48" MANHOLES, CX-4 JOINT FOR ALL OTHER SIZES OF MANHOLES AND EXTERIOR SEAL BY PRESS-SEAL GASKET CORP. EZ WRAP AND EZ STIK NO. 4 PRIMER, SPECIALTY PRODUCTS "MAC WRAP", INFI-SHIELD EXTERNAL GATOR WRAP, OR AN APPROVED EQUAL.
- NOTE NO.6 - INSTALL 2" STYROFOAM INSULATION AS DEFINED IN SECTION 901 GLUED TO THE BOTTOM OF THE PRECAST COVER.
- NOTE NO.7 - SHALL BE PSX PRESS BOOT SECTION 1205.
- NOTE NO.8 - AUTOMATIC AIR RELEASE VALVE - SEE SECTION 1205.
- NOTE NO.9 - SEAL WITH EZ STIK PREMIUM BUTYL JOINT SEALANT OR AN APPROVED EQUAL.
- NOTE NO.10 - SEE SECTION 1205 FOR PRECAST MANHOLE BASE REINFORCEMENT.
- NOTE NO.11 - I/I BARRIER WITH CAP 'N SEAL AS MANUFACTURED BY AP/M PERMAFORM OR AN APPROVED EQUAL. ADJUSTMENT RINGS SHALL NOT EXCEED THE HEIGHT OF THE I/I BARRIER.
- NOTE NO.12 - STEPS SHALL NOT BE PLACED IN SANITARY SEWER, STORM SEWER OR AIR RELEASE MANHOLES OR INLETS UNLESS SPECIFIED. IF SPECIFIED, THE MANHOLE STEPS SHALL BE DELTA SUREFOOT OR APPROVED EQUAL. STEPS SHALL BE SPACED 16" ON CENTER.
- NOTE NO.13 - PROVIDE 6" CAST ALUMINUM EXPANSION PLUG.




### AIR RELEASE MANHOLE

SCALE:  
Not to Scale  
DATE:  
1/2024


STANDARD  
DETAIL NO.  
**1205-11**



### MANHOLE CASTING STANDARD ADJUSTMENT



### INLET STANDARD ADJUSTMENT



### VALVE BOX ADJUSTMENT

NOTE NO.1 - USE PRECAST CONCRETE ADJUSTING RINGS FOR ADJUSTMENT OF MANHOLES AND TYPE 24" INLET AND TYPE 24" INLET/ MANHOLE. USE CONCRETE BLOCKS FOR ADJUSTMENT OF TYPE 36" AND TYPE 72" INLETS. GROUT SHALL BE PLACED BETWEEN ALL SURFACES. GROUT ON THE INSIDE EDGE OF ADJUSTING RINGS SHALL HAVE A SMOOTH FINISH.

NOTE NO.2 - INLET BACK SHALL BE ADJUSTED TO CONFORM WITH CURB & GUTTER GRADES AND CURB ALIGNMENT.

NOTE NO.3 - MANHOLE CASTING SHALL BE ADJUSTED TO CONFORM WITH SLOPE AND GRADE OF PROPOSED CONCRETE OR PAVEMENT.

NOTE NO.4 - MANHOLE CASTING SHALL BE ADJUSTED AFTER THE AC LEVELING COURSE OR THE AC BASE COURSE HAS BEEN PLACED.

NOTE NO.5 - INLET AND MANHOLE CASTINGS SHALL BE CONSIDERED ADJUSTED ONLY WHEN RAISED OR LOWERED BY ADDING OR REMOVING ADJUSTING RINGS OR GROUT.

NOTE NO.6 - ADAPTOR RING SHALL BE AMERICAN HIGHWAY PRODUCTS MANHOLE RISER OR AN APPROVED EQUAL.


NOTE NO.7 - ALLOWANCE FOR MANHOLE AND INLET ADJUSTMENT - 0" TO 6".




## MANHOLE , INLET & VALVE BOX ADJUSTMENT IN ASPHALT

SCALE:  
Not to Scale  
DATE:  
1/2026


STANDARD  
DETAIL NO.  
**1206-1**



**MANHOLE CASTING STANDARD ADJUSTMENT**



**INLET STANDARD ADJUSTMENT**



**VALVE BOX ADJUSTMENT**

NOTE NO.1 - USE PRECAST CONCRETE ADJUSTING RINGS FOR ADJUSTMENT OF MANHOLES AND TYPE 24" INLET AND TYPE 24" INLET/MANHOLE. USE CONCRETE BLOCKS FOR ADJUSTMENT OF TYPE 36" AND LARGER.

NOTE NO.2 - INLET BACK SHALL BE ADJUSTED TO CONFORM WITH CURB & GUTTER GRADES AND CURB ALIGNMENT.

NOTE NO.3 - MANHOLE CASTING SHALL BE ADJUSTED TO CONFORM WITH SLOPE AND GRADE OF PROPOSED CONCRETE OR PAVEMENT.

NOTE NO.4 - VALVES AND CURB STOP BOXES MUST BE WRAPPED IN ACCORDANCE WITH SECTION 1206.

NOTE NO.5 - INLET AND MANHOLE CASTINGS SHALL BE CONSIDERED ADJUSTED ONLY WHEN RAISED OR LOWERED BY ADDING OR REMOVING ADJUSTING RINGS OR GROUT.

NOTE NO.6 - ALLOWANCE FOR MANHOLE AND INLET ADJUSTMENT - 0" TO 6".



**MANHOLE , INLET & VALVE BOX  
ADJUSTMENT IN CONCRETE**


SCALE:  
Not to Scale  
DATE:  
1/2026

STANDARD  
DETAIL NO.  
**1206-2**

NOTES: BED FRAME IN MORTAR, INSTALL PRECAST TWO-INCH RINGS, AND PLASTER INSIDE AND OUT WITH MORTAR.

INSTALLED COST AT EXISTING LOCATIONS SHALL BE INCLUDED IN PRICE BID FOR "ADJUST FLOATING MANHOLE CASTING", OR "FURNISH & ADJUST FLOATING MANHOLE CASTING".


INSTALLATION COST AT NEW MANHOLE LOCATIONS SHALL BE INCLUDED IN THE PRICE BID FOR "MANHOLES".



**CROSS SECTION OF CONNECTION TO CONICAL MANHOLE - TYPICAL**

FRAMES WHEN COMPRESSED ARE 11 1/2" IN HEIGHT. SET UPPER FRAME 1 1/2" ABOVE LOWER FRAME.

WHEN INSTALLING A BOX OUT INTO EXISTING PAVEMENT, DRILL 20" LONG NO.5 REBAR 6" DEEP - 15" O.C. SEE STD. DETAIL 1206-4




**CROSS SECTION**




**FLOATING MANHOLE CASTING DETAIL (SHEET 1 OF 2)**

SCALE: Not to Scale  
DATE: 3/2017



STANDARD DETAIL NO. 1206-3




**PLAN VIEW**



**SECTION OF EXTRUDED NEOPRENE GASKET**



COMP. #S LID 1733-078 207 Lbs  
or LID 1733-0716 109 Lbs



FR. 1955-0004  
272 Lbs

FR. 1955-0003  
160 Lbs


MATERIAL: Cast Gray Iron ASTM A-48, Class 358  
FINISH: Black Asphalt Emulsion WEIGHT: 639#/Unit




**FLOATING MANHOLE CASTING DETAIL  
(SHEET 2 OF 2)**

SCALE:  
Not to Scale  
DATE:  
3/2017

STANDARD  
DETAIL NO.  
**1206-4**



**SINGLE GATE & FENCE DETAIL**



**DOUBLE GATE DETAIL**




**CHAIN LINK FENCE AND GATES**

SCALE:  
Not to Scale  
DATE:  
3/2017


STANDARD  
DETAIL NO.  
**1208-1**

**NOTES:**

1. SERVICE CONNECTION FOR 1 INCH THROUGH 2 INCH PIPE, CURBSTOP & CORPORATION STOP SHALL BE AS DEFINED IN SECTION 1209.



**PLAN VIEW**





**ELEVATION VIEW**




**TYPICAL 1"-2" WATER SERVICE**

SCALE:  
Not to Scale  
DATE:  
1/24/2024


STANDARD  
DETAIL NO.  
**1209-1**



- NOTE NO. 1 BARRICADES SHALL BE ORANGE AND ARE NOT REQUIRED TO BE REFLECTORIZED.
- NOTE NO. 2 ALL BALLASTING SHALL BE DONE BEHIND THE BARRICADE.
- NOTE NO. 3 BARRICADE WIDTH SHALL BE SUFFICIENT TO COVER THE WIDTH OF THE SIDEWALK.
- NOTE NO. 4 MINIMUM OF 2 BARRICADES SHALL BE USED AT ALL SIDEWALK CLOSURES.



**DETAIL B-1 SINGLE BARRICADE**




**DETAIL B-3 TRIPLE BARRICADE**



**ROAD CLOSED TYPE III BARRICADES**

SCALE:  
Not to Scale  
DATE:  
3/2017

STANDARD  
DETAIL NO.  
**1212-1**



2x8, 2x6, AND 2x4 BOLTED TOGETHER (8' LENGTHS)